

## A G E N D A



## Recommendation for Council Action

|                     |         |      |               |     |
|---------------------|---------|------|---------------|-----|
| Austin City Council | Item ID | 7218 | Agenda Number | 47. |
|---------------------|---------|------|---------------|-----|

|               |           |             |              |
|---------------|-----------|-------------|--------------|
| Meeting Date: | 6/23/2011 | Department: | Public Works |
|---------------|-----------|-------------|--------------|

## Subject

Authorize negotiation and execution of an Interlocal Agreement between the City of Austin and the Texas Department of Transportation (TXDOT) for relocation of existing water lines in conflict with the TXDOT SH 71 East at Riverside Drive Project (CSJ: 0113-13-149) in the amount of \$1,585,678 plus a \$237,851.70 contingency, for a total contract amount not to exceed \$1,823,529.70.

## Amount and Source of Funding

Funding is available in the Fiscal Year 2010-2011 Capital Budget of Austin Water Utility.

## Fiscal Note

A fiscal note is attached.

|                               |   |
|-------------------------------|---|
| Purchasing Language:          |   |
| Prior Council Action:         |   |
| For More Information:         | Adewale Odufuye, 974-7119; Kathi Flowers, 972-0213; Susan Garnett, 974-7064 |
| Boards and Commission Action: | To be reviewed by the Water and Wastewater Commission on June 8, 2011.      |
| MBE / WBE:                    |   |
| Related Items:                |   |

## Additional Backup Information

This project includes relocation of existing water lines in conflict with the TXDOT Roadway and Intersection Improvements at SH 71 East and Riverside Drive.

This project will relocate 2,712 linear feet of factory restrained 24" ductile iron water pipe, 20 linear feet of 16" ductile iron water pipe, 300 linear feet of 12" ductile iron water pipe, 148 linear feet of 6" ductile iron water pipe, as well as 400 linear feet of 48" encasing pipe. The project also includes 6", 8", 12" and 24" gate valves, fire hydrants, ductile iron fittings, and trench excavation safety protective systems. Construction dates are dependent upon the TXDOT Project letting schedule. Work is currently scheduled to begin in August 2011.

Due to the potential for unknown subsurface conditions and utility conflicts when working in the right of way, a 15% contingency has been included to allow for the expeditious processing of any change orders.

This project is located within zip code 78741.

