COVER SHEET: PROJECT INFORMATION

- GP.1 STANDARD NOTES AND DETAILS: EROSION/SEDIMENTATION CONTROL
- GP.2 STANDARD NOTES AND DETAILS: TREE PROTECTION AND ENVIRONMENTAL
- L-1 TEMPORARY SEDIMENTATION, EROSION CONTROL and TREE PROTECTION PLAN
- L-2 SITE UTILITY PLAN
- L-3 SITE IRRIGATION PLAN
- L-4 SITE LANDSCAPE PLAN
- L-5 IRRIGATION DETAILS

#### NOTES:

- CONTRACTOR SHALL NOTIFY THE PUBLIC WORKS DEPARTMENT 24 HOURS PRIOR TO STARTING CONSTRUCTION OR CLEARING OPERATIONS.
- 2. CONTRACTOR SHALL CALL "ONE CALL" AT 1-800-344-8377 FOR UTILITY LOCATIONS AT LEAST 48 HOURS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET RIGHT-OF-WAY.
- THIS PROJECT IS LOCATED WITHIN THE <u>SHOAL CREEK</u>
   WATERSHED (CLASSIFIED AS <u>URBAN</u>) AND SHALL BE DEVELOPED,
   CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH CHAPTER 25 OF THE CODE OF THE CITY OF AUSTIN.
- XA/NO PORTION OF THIS SITE IS LOCATED WITHIN PARKLAND OR LAND USED FOR PARK PURPOSES. (IF SUCH LAND IS INCLUDED, DOCUMENTATION OF PARKS AND RECREATION DEPARTMENT APPROVAL IS REQUIRED AT THE TIME OF SUBMITTAL FOR GENERAL PERMIT
- \_A/NOXPORTION OF THIS SITE IS LOCATED WITHIN THE 100-YEAR FLOODPLAIN PER CITY OF AUSTIN AND FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS.
- THIS PROJECT \_IS/IS NOT X WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS DEFINED BY THE CITY OF AUSTIN. THIS PROJECT \_IS/IS NOT X WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS REQULATED BY THE TEXAS NATURAL RESOURCES CONSERVATION
- THERE \_ARE/ARE NO \_XCRITICAL ENVIRONMENTAL FEATURES WITHIN 150' OF ANY PORTION OF THIS PROJECT. A FIELD INVESTIGATION \_HAS BEEN PERFORMED AS A PART OF THIS PROJECT. A FIELD INVESTIGATION \_HAS NOT BEEN PERFORMED
- 8. PARTY RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE:


COMPANY: MARTY STUMP - PARD PHONE: 512-974-9460 PARTY RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION MAINTENANCE: COMPANY: MARTY STUMP - PARD

- 9. THE STANDARD SHEETS INCLUDED IN THIS PLAN SET WERE PROVIDED BY THE GENERAL PERMIT PROGRAM OFFICE FOR USE ON GENERAL PERMIT PROJECTS ONLY. IF ANY MODIFICATIONS TO THE SHEETS WERE MADE, THEY ARE CLEARLY INDICATED ON THE SHEET ITSELF AND IN THE COVER SHEET INDEX.
- 10. ADDITIONAL TRENCH E/S CONTROL: TRIANGULAR SEDIMENT FILTER DIKE (TYPE I)
  WILL BE INSTALLED ACROSS FULL WIDTH OF TRAFFIC CLOSURE AND DOWNSTREAM OF CONSTRUCTION AREA, PERPENDICULAR TO CURB. FILTER DIKE TO FOLLOW ACTIVE CONSTRUCTION. REMOVING AND RE-SETTING TYPE I DIKE IS CONSIDERED SUBSIDIARY TO BARRICADES AND TRAFFIC HANDLING.
- 11. PHASING, IF PROPOSED BY THE CONTRACTOR, WILL BE DELINEATED AND THE INFORMATION PROVIDED TO THE GENERAL PERMIT OFFICE PRIOR TO THE FIELD PRE-CONSTRUCTION MEETING.
  ADDITIONALLY, THE GENERAL PERMIT OFFICE WILL BE NOTIFIED VIA E-MAIL A MINIMUM
  OF 24 HOURS IN ADVANCE OF TRANSITION BETWEEN PHASES.

	GENERAL PERMIT PROGRAM CORRECTIONS RECORD					
No.	DESCRIPTION	BY	CORRECT (C) ADD (A) VOID (V) SHEET Nos.	TOTAL No. SHEETS IN CORRECTION PLAN SET	CITY OF AUSTIN APPROVAL/DATE	DATE IMAGED
لــــا		<u></u>				

# CITY OF AUSTIN PARKS AND RECREATION DEPT.

## WOOLDRIDGE SQUARE LANDSCAPE IMPROVEMENTS



LOCATION MAP

N.T.S.

#### CONSTRUCTION SEQUENCE:

- 1. INSTALLATION OF TREE PROTECTION AND EROSION CONTROLS.
- 2. PRECONSTRUCTION CONFERENCE WITH ENVIRONMENTAL INSPECTOR.
- 3. DELINEATION OF CONSTRUCTION ENTRANCE AND CONSTRUCTION STAGING AREA.
- 5. REMOVE DELINEATION OF CONSTRUCTION ENTRANCE AND CONSTRUCTION STAGING
- 6. RE-VEGETATION.
- 7. FINAL INSPECTION. REMOVAL OF TREE PROTECTION AND EROSION CONTROLS.

NOTES: GENERAL PERMIT PROGRAM APPROVAL DOES NOT CONSTITUTE

VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HISHER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY CITY ENGINEERS.

FOR RECULATORY REVIEW

PROJECT INFORMATION:

STREET ADDRESS: 900 GUADALUPE ST. OWNER: CITY OF AUSTIN

#### CONTACT:

MR. MARTY STUMP 919 W.  $28\frac{1}{2}$  STREET AUSTIN, TX 78705 (512) 974-9460

LANDSCAPE ARCHITECT: MR. MARTY STUMP 919 W. 28½ STREET AUSTIN, TX 78705 (512) 974-9460

SUBMITTAL PREPARED BY: MR. REY HERNANDEZ 919 W. 28½ STREET AUSTIN, TX 78705 (512) 974-9464



\PP	ROVALS:	
		_

SUBMITTED FOR APPROVAL BY:

#### APPROVED BY

GENERAL PERMIT HOLDER GP-12-0000.PAR

ANNUAL GENERAL PERMIT NUMBER

3/13/2004 ANNUAL GENERAL PERMIT EXPIRATION DATE

APPROVED BY:

THE PART OF THE PROPERTY OF THE PARTY OF THE	DATE
SENERAL PERMIT PROGRAM COORDINATOR VATERSHED PROTECTION DEPARTMENT	DATE

CITY OF AUSTIN TRACKING NUMBER

SUBMITTAL DATE:

DATE

CITY OF AUSTIN - STANDARD NOTES EROSION AND SEDIMENTATION CONTROL (MODIFIED FOR USE ON GENERAL PERMIT PROJECTS)

- THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL AREA PROTECTIVE FENCING PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUEBING, OR EXCHANTION
- THE PLACEMENT OF EROSION/SEDMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE ENGROMENTAL CRITERIA MANUAL AND THE APPROVED EROSION AND SEDMENTATION CONTROL PLAIL
- THE PLACEMENT OF TREE/NATURN, AREA PROTECTIVE FENCING SHALL GE IN ACCORDANCE WITHE CITY OF AUSTIN STINGARD NOTICE FOR TREE AND INJURAL AREA PROTECTION AND THE APPROVED GROUNG/TIEE AND INJURAL AREA PROVIDED GROUNG/TIEE AND INJURAL AREA PLAN.
- PRE-CONSTRUCTION CONFERENCE SHALL BE HELD ON-SITE WITH THE CONTRACTOR, DESIGN MADERY, PETMET MPLICANT, AND CONEINS, PETMET OFFICE RESPECTOR AFTER RESTALLATION OF THE ROSCOM/SEMBLEMENTON CONTINUS, AND THE TREE-MOUTHAIN, AREA PROTECTION MESSARES AND PROOF OR BECAMING MAY SITE PREPARATION WORS. THE CONTINUETOR SHALL MOTTRY THE GENERAL PETMET OFFICE TS/12/744—2337, AT LEAST 3 ONES PROOF TO THE MEDTING DATE.
- THE COMMACTOR IS REQUIRED TO INSPECT THE COMMACTS AND FENCES AT MERICY INTERNALS AND AFTER SIGNERCHAIN MARKAL LEWING TO INSURE THAT THEY ARE FUNCTIONING PROPERTY. THE PRISONS IN REPORTS SHALL INSURING PROPERTY HAVE ANY INCRESSIVE REPURS TO DAMACED AFEIS. SHALL RANGE MICH SHALL SHAL
- PRIOR TO FINAL ACCEPTANCE BY THE CITY, HALL ROADS AND WATERWAY CROSSINGS CONSTRUCTED. FOR TEMPORARY CONTRACTOR ACCESS MAST RE REMOVED, ACCUMILATED SEDIMENT REMOVED FROM THE WILDERBY AND THE AREA RESTORED TO THE ORIGINAL GRACE AND REFERENTED. ALL UND CLEVANG CIERCE SHALL BE DISPOSED OF IN APPROVED SYGL, DISPOSAL STEEL.
- ... Work must stop f a void in the rock substrate is discovered which is one source of or larger in total med, blurs ar from within the substrate, and/or consistently codes water during and rim eyent. At this time, it is the responsibility of the project inacer to amediately contact the general permit oppic inspector for further investigat
- FELD REVISIONS TO THE EROSION AND SEDMENTIATION CONTROL PLAN MAY BE REQUIRED BY THE GENERAL PERMIT OFFICE INSPECTOR QUARKS THE COURSE OF CONSTRUCTION TO CORRECT CONTROL MOREOLUCIES. MAKER REVISIONS MUST BE APPROXIMED BY THE GENERAL PERMIT OFFICE OF THE WATERSHED PROTECTION AND DEVELOPMENT REVIEW DEPARTMENT.
- PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS NOTED BELOW


  - FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 1 POUND PER 1,000 SQUARE FEET WITH A PURITY OF 95% WITH 85% GERMANATIO
  - c. FERTILIZER SHALL HAVE AN ANALYSIS OF 15-15-15 AND SHALL BE APPLIED AT THE RATE OF 85 POUNDS PER ACRE.
- THE TOPSOIL BUT WILL SUPPLIENTLY SOMETHE SOIL TO A DEPTH OF SIX MOVES. THE METHOD SHALL COUNTY AT THE HOW INTERNALS DURING THE FIRST TWO MOVES SHALL POSTPOILE THE MUSTERING SCHEDULE FOR MOWE SHALL POSTPOILE THE MUSTERING SCHEDULE FOR MOW WEEK.
- MULCH TYPE USED SHALL BE HAY, STRAW OR MULCH APPLIED AT A RATE OF 45 POUNDS PER 1000 SQUARE FEET.
- RESTORATION SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1-1/2 inches high with BSX coverage, provided no bare spots larger than 16 square feet exist.
- NATIVE GRASS IS OR IS NOT X REQUIRED ON THIS PROJECT. NATIVE GRASS SECTION SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL.

#### 11. DEVELOPER INFORMATION

CONTACT: MARTY STUMP ADDRESS: 919 W. 28 1/2 ST. AUSTIN TX 78705 PHONE: 512-974-9460 FAX: 512-974-9489 OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS COMPANY: C.O.A. CONTACT: MARTY STUME ADDRESS: 919 W. 28 1/2 ST. AUSTIN DX 78705 PHONE: 512-974-9480 FAX: 512-974-9469 PARTY RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE:

The contractor shall not dispose of surplis dicharded material from the site without notifying the constal permit office, at 469—530, at least 48 hours proof to the spole regional. This notification shall beclude the disposal location and a copy of the permit issued to receive the material.

INLET PROTECTION SHALL BE INSTALLED MANERATELY PROR TO STREET WORK, AND WILL BE REMOVED AS SOON AS THE GRIEFAL PERMIT OFFICE INSPECTIOR AGREES THAT THERE IS NO POTENTIAL FOR STRANSPORTER





THE TEMPORARY SPOILS/STOCKPILE STORAGE AREA AND STAGING AREA WILL BE LOCATED DIRECTLY ADJACENT TO THE EXCAVATION AND ON THE PAVEMENT


2. ANY SPOIL NOT INTENDED TO BE REUSED WILL BE HAULED TO AN APPROVED OR PERMITTED DISPOSAL SITE DAILY.


INSTALL TRIANGULAR SEDIMENT FILTER DIKE (TYPE I) ACROSS FULL WIDTOF TRAFFIC CLOSURE AND DOWNSTREAM OF CONSTRUCTION AREA PERPENDICULAR TO CURB. FILTER DIKE TO FOLLOW ACTIVE CONSTRUCTION ACTIVE CONSTRUCTION. REMOVING AND RE-SETTING TYPE I DIKE IS CON SUBSIDIARY TO BARRICADES AND TRAFFIC HANDLING

ADDITIONAL EROSION/SEDIMENTATION CONTROL FOR WORK IN PAVED AREAS









TRIANGULAR SEDIMENT FILTER DIKE

6582

CITY OF AUSTIN

RECORD COPY SIGNED

BY J. PATRICE MURPHY

8/27/00

REPONSULITY FOR APPROPRIE USE

OF THIS STANDARD.



∑ V

CONTRO

INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6") AND DISPOSED OF IN A MANNER WHICH WILL NOT CAUSE ADDITIONAL SILTATION. AFTER THE DEVELOPMENT SITE IS COMPLETLY STABILIZED, THE DIKES AND ANY REMAINING SITE SHOULDERLY STABILIZED, THE DIKES AND ANY REMAINING SITE SHOULDERLY STABILIZED, THE DIKES AND ANY REMAINING STABILIZED IN GENERAL NOTE & ABOVE.

SEDIMENTATION

PERMIT

GENERAL

**EROSION/** 

EXISTING GRADE -200 mm 653655 6536 6536 65 PROFILE R.D.W. PLAN VIEW

USE ONLY OPEN GRADED ROCK 100 to 200 mm (4 to 8") DIAMETER FOR STREAM FLOW CONDITIONS. USE OPEN GRADED ROCK 75 to 125 mm (3 to 5") DIAMETER FOR OTHER CONDITIONS.

100 mm-(4")

CROSS SECTION

600 mm (24") MIN.

FLOV

THE ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 25 mm (1") OPENING AND MINIMUM WIRE DIMMETER OF 120 mm (20 GAUGE). ROCK BERMS IN CHANNEL APPLICATIONS SHALL BE ANCHORED FIRMLY WITH THE SUBSTRATE A MINIMUM OF 150 mm (6") WITH T-POSTS OR WITH 15M OR 20M (§5 OR §6) REBAR, WITH MAXIMUM SPACING APART OF 1.2 m (48") ON CENTER.

450 mm (18") MIN.

STANDARD SYMBOL FOR ROCK BERM (RB)


\_\_\_\_RE\_\_\_\_

ROCK BERM

-woven wire sheathing

DAILY INSPECTION SHALL BE MADE ON SEVERE-SERVICE ROCK BERMS; SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES 150 mm (6"). WHEN THE SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MAINTER.

CITY OF AUSTIN	ROCK BERM	
RECORD COPT SIGNED 5/23/00 BY J. PATRICE BURPHY ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	21 G39S-



GENERAL PERMIT PROGRAM STANDARD ENVIRONMENTAL NOTES

- IN ORDER TO SECURE APPROVAL FOR USE OF ADDITIONAL AREAS, CONTRACTOR MUST PROVIDE COMPLETE SUBMITTAL TO GENERAL PERMIT OFFICE AND ALLOW A ONE WEEK COMMENT PERSON FOR EACH REVIEW. CONTRACTOR SHOULD REQUEST MORE INFORMATION ON THE ELEMENT
- Contractor must betall and matrial eroson/sedimentation controls and tree protection for all such areas in accordance with the City of alstin demonstration critical manual and as included in the approved submittal or directed in the field by the creative, point of the control of the protection of the process of the protection of the process of the protection of the process of the protection of the protection of the protection of the protection of the process of the protection of the protectio
- A SIGNED COPY OF THE GENERAL PERMIT OFFICE APPROVAL MUST BE KEPT ON SITE AND 5. ACCESSIBLE AT ALL TIMES DURING PROJECT CONSTRUCTION.

CONTRACTOR IS RESPONSIBLE FOR DEWATERING OF WORK AREA. CONTRACTOR MAST SECURE CITY OF AUSTIN APPROVAL OF PROPOSED DEMATERING PROCEDURES PRIOR TO INSTALLATION OR USE APPROVAL MUST BE SECURED FROM THE GENERAL PERMIT OFFICE OF THE MATERISHED PROTECTION AND DEVELOPMENT REVIEW DEPARTMENT. CONTRACTOR MUST PROVIDE COMPLETE

#### FUEL STORAGE NOTE:

FUEL STORAGE IS PROHIBITED ON THIS PROJECT. ADDITIONALLY, THE CONTRACTOR IS REQUIRED TO MOTHY THE GENERAL PERMIT OFFICE MANDANELY FOLLOWING ANY SPAL OF FUEL OR OTHER TOOCH METERAL. COMPRISON TO FOLLOW-UP WITH WRITTEN DOCUMENTATION, INCLUDING A COMPLETE DESCRIPTION OF THE INCIDENT, MATERIAL SPALLED, AND ACTIONS TAKEN TO CONTRAN AND CLEMAN—UP MATERIAL.

#### FUGITIVE DUST CONTROL NOTE:

ALL PROJECTS APPROVED BY THE GENERAL PERMIT OFFICE MUST COMPLY WITH THE CODE OF THE CITY OF AUSTIN AND THE EMPRONAEDTIAL CRITICIA MANUAL REQUIREDMENT OF CONTROL ARROWMEND LOST. COMPANIANCE IS REQUIRED FOR BITTINE PROJECT SITE AS WELL AS ASSOCIATED OPERATIONS. CONTACT THE GENERAL PERMIT OFFICE FOR RECOMMENDED CONTROL MICHAEL STATE AS A SECOND OPERATIONS.

#### PROJECT SEQUENCE: (REFER TO COVER FOR PROJECT-SPECIFIC ADDITIONS, IF APPLICABLE.)

- SECURE APPLICABLE COA PERMITS, INCLUDING APPROVAL UNDER GENERAL PERMIT AND LITULTY STREET CUT PERMIT.
- NOTIFY GENERAL PERMIT OFFICE INSPECTOR PRIOR TO PLACEMENT OF E/S CONTROLS AND TREE PROTECTION FENCING. ALL PROPOSED PHASING OF CONTROLS MUST SE SUBMITTED TO AND APPROVED BY THE INSPECTOR PRIOR TO THE FIELD PRE-CONSTRUCTION CONFERENCE.
- NOTIFY COA TEMPORARY TRAFFIC CONTROL INSPECTOR PRIOR TO PLACEMENT OF TRAFFIC CONTROLS. ALL PROPOSED PHASING OF CONTROLS MUST BE INDICATED ON APPROVED TRAFFIC CONTROL, PLAN AND SEALED BY PROFESSIONAL ENGINEER.
- PLACE TEMPORARY E/S CONTROLS AND TREE PROTECTION FENCING PRIOR TO BEGINNING ANY EXCAVATION. INSTALL C.J.P. SIGN, IF APPLICABLE.
- HOLD ENVIRONMENTAL PRE-CONSTRUCTION CONFERENCE ON SITE WITH THE CONTRACTOR, OWNER'S REPRESENTATIVE, AND GENERAL PERMIT OFFICE INSPECTIOR AFTER INSTALLATION OI E/S CONTROLS AND TREE PROTECTION FEBLORIAND PROR TO MAY TRENCHING OPERATIONS.

#### PROJECT CONSTRUCTION

- BEGIN CONSTRUCTION. CONTACT GENERAL PERMIT OFFICE INSPECTOR FOR ADDITIONAL PRE-CONSTRUCTION CONFERENCES FOR EACH PHASE, IF REQUIRED.
- CONTACT GENERAL PERMIT OFFICE TO SCHEDULE FIELD INSPECTION PRIOR TO BEGINNING INSTALLATION OF PERMANENT E/S CONTROLS.
- COMPLETE RESTORATION OF ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES FOR THIS PROJECT. (PERMANENT E/S CONTROLS)
- HOLD ENVIRONMENTAL POST-CONSTRUCTION CONFERENCE ON SITE WITH THE CONTRACTOR, OWNER'S REPRESENTATIVE, AND GENERAL PERMAT OFFICE INSPECTOR. ALL PERMANENT E/S CONTROLS MUST BE ACCEPTED BY THE GENERAL PERMAT OFFICE INSPECTOR.
- FOLLOWING FINAL ACCEPTANCE OF PERMANENT E/S CONTROLS BY THE GENERAL PERMIT OFFICE INSPECTIOR, REMOVE TEMPORARY E/S CONTROLS, CLEAN EXISTING STORM DRAININGE SYSTEMS AS NECESSARY DUE TO CONSTRUCTION OPERATIONS.
- DRESS-UP AND RESTORE ANY AREAS DISTURBED BY REMOVAL OF TEMPORARY E/S CONTROLS DESCRIBED ABOVE.
- 7. REMOVE TEMPORARY TRAFFIC CONTROL DEVICES.

CITY OF AUSTIN - STANDARD NOTES TREE AND NATURAL AREA PROTECTION (MODIFIED FOR USE ON GENERAL PERMIT PROJECTS)

- ALL TREES AND NATURAL AREAS SHOWN ON PLAN TO BE PRESERVED SHALL BE PROTECTED DURING CONSTRUCTION WITH TEMPORARY FENCING.
- PROTECTIVE FENCES SHALL BE ERECTED ACCORDING TO CITY OF AUSTIN STANDARDS FOR TREE PROTECTION.

- - SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC OR STORAGE OF FOURMENT OR MATERIALS
  - ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATE THAN 6 INCHES CUT OR FILL) OR TRENCHING NOT REVIEWED AND AUTHORIZED BY THE GENERAL PERMIT OFFICE OF THE WATERSHED PROTECTION DEPARTMENT;
  - WOUNDS TO EXPOSED ROOTS, TRUNK OR LIMBS BY MECHANICAL EQUIPMENT:
  - OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CEMENT TRUCK CLEANING, AND FIRES.
- EXCEPTIONS TO INSTALLING PROTECTIVE FENCES AT CRITICAL ROOT ZONES MAY BE PERMITTED IN THE FOLLOWING CASES:
- WHERE THERE IS TO BE AN APPROVED GRADE CHANCE, IMPERMEABL PAVING SURFACE, TREE WELL, OR OTHER SUCH SITE DEVELOPMENT, ERECT THE FENCE APPROXIMATELY 2 TO 4 FEET BEYOND THE AREA DISTURBED:
- WHERE PERMEABLE PAVING IS TO BE INSTALLED, ERECT THE FENCE AT THE OUTER LIMITS OF THE PERMEABLE PAVING AREA
- WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE NO CLOSER THAN 6 FEET TO THE BUILDING

WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE BEING CLOSER THAN 4 FEET TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PHANKING TO A HEIGHT OF 8 FEET (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING.


- WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN AREAS OF UNPROTECTED ROOT ZONES, THOSE AREAS SHOULD BE COVERED WITH 4 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION
- ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FURS WITH THE SOIL BACKFILL ROP LEREAS WITH COOP CULLIFORD THE SOIL BACKFILL ROW SHAPE AND THE SOIL BACKFILL BOWNS POACES FOR EXPOSE WITH FURSING A REPORT AREA WITH A MANUAL WITH A BANKFILL WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EMPORATION.
- 10.
- TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES SHOULD BE WATERED DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. TREE CROWNS SHOULD BE SPRAYED WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
- ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE RRIGATION SHALL BE PLACED AS FAR FROM EXISTING TREE TRUNKS AS POSSIBLE. 12.
- NO LANDSCAPE TOPSOIL DRESSING GREATER THAN 4 INCHES SHALL BE PERMITTED WITHIN THE DRIPLINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE.
- PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND EQUIPMENT SHALL TAKE PLACE BEFORE CONSTRUCTION DECINE.
- DEVIATIONS FROM THE ABOVE NOTES MAY BE CONSIDERED ORDINANCE VIOLATIONS IF THERE IS SUBSTANTIAL NONCOMPLIANCE OR IF A TREE SUSTAINS DAMAGE AS A RESULT.
- TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.

### SUPPLEMENTAL TREE PROTECTION NOTES

- ALL TREES 8" AND LARGER LOCATED WITHIN THE LIMITS OF CONSTRUCTION OR WITH CANOPIES/CRITICAL ROOT ZONES EXTENDING INTO THE LIMITS OF CONSTRUCTION HAVE BEEN SURVEYED AND ARE SHOWN IN THIS PLAN SET. DAMAGE TO, OR REMOVAL OF, TREES SHOWN IN DOCUMENT SET TO BE PRESERVED SHALL CONSTITUTE A VOLATION OF THE CITY OF AUSTIM (COA) PERMIT.
- ALL TREE PROTECTION FENCING MUST COMPLY WITH CITY OF AUSTIN REQUIREMENTS AS OUTLINED IN THE ENVIRONMENTAL CRITERIA MANUAL AND AS INDICATED BY STANDARD COA NOTES AND DETAILS INCLUDED WITHIN THIS DOCUMENT SET. CONTRACTOR SHALL INSTALL FENCING PRIOR TO PRE-CONSTRUCTION CONFERENCE, MAKE ADJUSTMENTS TO FENCING AS DIRECTED BY THE COA ENVIRONMENTAL INSPECTOR, AND MAINTAIN FENCING UNITE. PROJECT IS COMPLETE.
- TYPE AND LOCATION OF ALL TREE PROTECTION FENCING MUST BE APPROVED IN THE FIELD BY THE GENERAL PERMIT OFFICE INSPECTOR PRIOR TO CONSTRUCTION
- ALL TRENCHING WITHIN THE CRITICAL ROOT ZONE OF A TREE TO BE PRESERVED WILL BE AIR SPADED.
- CONTACT GENERAL PERMIT OFFICE FOR INSPECTION PRIOR TO ANY PRUNING ACTIVITIES ON TREES IN PROJECT AREA.
- TREE SURVEY SIZE REQUIREMENTS VARY BY PROJECT AREA AND/OR PROPERTY OWNERSHIP.

#### OAK WILT PREVENTION NOTES

- PRUNING OF AN EXISTING TREE THAT IS NECESSARY AS PART OF THIS PROJECT SHALL BE CONDUCTED IN ACCORDANCE WITH AMSI A300—1995 STANDARDS, OR LATEST APPROVED EDITION. PRUNING SHALL BE COME WITH CLEAN, SHARP TOOLS. TO PREVENT BARK TEARS, THE WEIGHT OF THE BRANCH SHALL BE REMOVED BEFORE MAKING FINAL PRUNING CUT.
- ALL PRUNING SHALL PRESERVE THE NATURAL CHARACTER OF THE TREE.
- ONLY COLLAR CUTS ARE ACCEPTABLE. NO FLUSH CUTS OR STUB CUTS WILL BE ALLOWED.
- ALL TREE BRANCHES NECESSARY TO BE REMOVED FOR THE SAFE CONSTRUCTION OF THIS PROJECT SHALL BE IDENTRIED BY THE CONTRACTOR AND APPROVED BY THE GENERAL PERMIT OFFICE INSPECTIOR PRIOR IT REMOVAL.
- ALL BRANCHES THAT ARE BROKEN OR DAMAGED DURING CONSTRUCTION SHALL BE REMOVED.
- PRUNING CUTS OR DAMAGED AREAS ON AN OAK TREE SHALL BE PAINTED <u>WITHIN FIME MINITES</u> WITH A STANDARD TREE WOUND DRESSING. THE WOUND DRESSING SHALL BE EITHER TREEKOTE ARROSOL OR TANALEFOOT PRUNING SEALER (OR APPROVED EDUAL).
- ANY TREE ROOTS THAT ARE EXPOSED, CUT, OR TORN DURING CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SURROUNDING SOIL. (REFER ALSO TO NUMBER 9 OF THE TREE AND NATURAL AREA PROTECTION NOTES INCLUDED IN THIS PLAN SET,)



255

6 m FOR -500 mm DIA. TREE (20'-D" FOR 20" DIA. TREE)


CITY OF AUSTIN


WOOD CHIP MULCH AREA 100 mm-150 mm (4"-8") DEPTH

RECORD COPY SIGNED
BY J. PATRICE MURPHY
ADOPTED

THE MICHICAL APPROPRIATE USE
OF THE STANDARD.

\*AS NEEDED TO PROVIDE MINIMUM NECESSARY WORK SPACE. IF LESS THAN 1.5 m (5'), THEN ADD BOARDS STRAPPED TO TRUNK.





WOOD CHIP MULCH

BUILDING



March xx, 2012


ğ

TAL NOTES

OFFICE

1

(5)



#### **LEGEND**

----- SILT FENCE

---- TREE PROTECTION

-LOC-LOC- LIMITS OF CONSTRUCTION


EXISTING STUMP

#### T.E.S.C. NOTES

- 1. NO TREES ARE TO BE REMOVED UNDER THIS CONTRACT.
- 2. COORDINATE WITH R.O.W. MANAGEMENT AND TRAVIS COUNTY FOR TEMPORARY USE OF PORTION OF PARKING LANE ON SAN ANTONIO STREET FOR CONSTRUCTION ENTRANCE
- MOVEMENT OF TREE PROTECTION FENCE (TPF) WILL ONLY BE ALLOWED DURING TREE CARE ACTIVITIES OR AIR SPADE TRENCHING FOR IRRIGATION INSTALLATION. TPF MUST BE RE-INSTALLED IMMEDIATELY FOLLOWING TREE CARE AND IRRIGATION INSTALLATION AND/OR AT THE END OF EACH WORKING DAY. NO EQUIPMENT OR MATERIAL STAGING IS ALLOWED IN THE CRZ.

## EXISTING TREE LEGEND


	NO.	TYPE	DBH
	1	POST OAK	36"
	2	CEDAR ELM	19"
	3	POST OAK	27"
	4	CEDAR ELM	15"
	5	CEDAR ELM	26"
	6	PECAN	19"
	7	POST OAK	18"
	8	CEDAR ELM	28"
	9	PECAN	25"
	10	PECAN	23"
	11	SYCAMORE	20"
	12	PECAN	23"
	13	LIVE OAK	14"
	14	PECAN	24"
	15	PECAN	32"
	16	SYCAMORE	21"
i	17	SYCAMORE	22"
	18	SYCAMORE	23"
	19	PECAN	17"
	20	MOUNTAIN LAUREL	8"




FOR REVIEW ORLY TON

WOOLDRIDGE SQUARE LANDSCAPE IMPROVEMENTS WOOLDRIDGE SQUARE 900 GUADALUPE ST TEMPORARY SEDIMENTATION, EROSION CONTROL AND TREE PROTECTION PLAN

**SCALE** AS NOTED DATE 06/09/12 SHEET






- 1. NEW ELECTRICAL SERVICE ENTRY AT WEST OF SITE (SAN ANTONIO ST), UNDERGROUND, CONNECTING TO EXISTING DISTRIBUTION GRID. DESIGN OF SERVICE BY AUSTIN ENERGY.
- 2. NEW ELECTRIC SERVICE AND LOAD CENTER TO BE NEATLY CONCEALED IN ABOVE GROUND, LOCKING STAINLESS STEEL VAULT. SUBMIT CUT-SHEET FOR OWNER APPROVAL.
- 3. SERVICE TO BE OF AMPLE VOLTAGE, PHASE AND AMPERAGE, DESIGNED BY AUSTIN ENERGY TO GENERALLY PROVIDE POWER TO SITE IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO:
- -ACCESSORY ELECTRIC (PLUGS) AT PERGOLA
  -LIGHTING AT PERGOLA (EXISTING AND IMPROVED)
- -LIMITED PARK LIGHTING (ORNAMENTAL PATH LIGHTING
- -IRRIGATION CONTROLLER
- -ELEC SUPPLY TO VENDOR/CONCESSION LOCATION
- -POWER SUPPLY FOR SPECIAL EVENTS
- -POWER TO DRINKING FOUNTAINS (CHILLERS) -POSSIBLE FUTURE POWER SUPPLY FOR
- IMPROVEMENTS IN R.O.W. (GREAT STREETS, CAP. METRO SHELTERS, ETC)



WOOLDRIDGE SQUARE LANDSCAPE IMPROVEMENTS WOOLDRIDGE SQUARE 900 GUADALUPE ST

FOR REVIEW ONLY TRUCTION SCALE DATE SHEET

SITE UTILITY PLAN AS NOTED 06/09/12



### IRRIGATION LEGEND


SYMBOL	DESCRIPTION	NOZ	P.S.I.	RAD	GPM	
0	HUNTER I-25, FULL PATTERN	10	60	52'	11	
4	HUNTER I-25-ADV ADJUSTABLE PATTERN	1D	60	52'	11	
Δ	HUNTER 1-25-ADV ADJUSTABLE PATTERN	10	60	52'	11	
ß	HUNTER I-25-ADV ADJUSTABLE PATTERN	7	60	48'	7.5	
	1 GPM TREE BUBBLER ON POLY SWING PIPE, 2 PER	1 GPM TREE BUBBLER ON POLY SWING PIPE, 2 PER TREE, SEE DETAIL				
	RAINBIRD PEB CONTROL VALVE, SIZE AS NOTED IN	RAINBIRD PEB CONTROL VALVE, SIZE AS NOTED IN VALVE LEGEND				
₩	2" MASTER VALVE, WEATHERMATIC 2104E-20-H WIT	2" MASTER VALVE, WEATHERMATIC 2104E-20-H WITH MANUAL BLEED LEVER				
•	AUTOMATIC CONTROL VALVE DESIGNATION (STATION	AUTOMATIC CONTROL VALVE DESIGNATION (STATION DESIGNATION)				
0	SCH 80 PVC BALL VALVE, LINE SIZE					
	EXISTING 2" WATER METER, CONFIRM SIZE, PRESSURE AND VOLUME					
	EXISTING BACKFLOW ASSEMBLY, CONFIRM SIZE, PRESSURE AND VOLUME					
<b>A</b>	RAINBIRD 44-NP 1" QUICK COUPLING VALVE WITH LOCKING COVER					
G	RAINBIRD ESP-12MC CONTROLLER					
	SCHED 40 PVC MAINLINE, 3" TYP.					
	CLASS 200 PVC LATERAL LINES, SIZE AS INDICATED					
	SCHED 40 PVC SLEEVE, SIZE AS INDICATED					
NOT SHOWN	#14 AWG TYPE UF CONTROL WIRE, RED=SIGNAL, WH	#14 AWG TYPE UF CONTROL WIRE, RED=SIGNAL, WHITE=COMMON				

#### IRRIGATION VALVE SCHEDULE

NO.	GPM	TYPE OF HEAD	SIZE
1 =	62.5	TURF ROTOR	2*
2	62.5	TURF ROTOR	2"
3	62.5	TURF ROTOR	2"
4	62.5	TURF ROTOR	2"
5	55	TURF ROTOR	2"
6	55	TURF ROTOR	2"
7	44	TURF ROTOR	2"
8	55	TURF ROTOR	2"
9	55	TURF ROTOR	2"
10	10	TREE BUBBLERS	1*
11	_10	TREE BUBBLERS	1"
12		SPARE	

#### IRRIGATION NOTES

- PIPE LAYOUT SHOWN GENERALLY. STAKE FOR OWNER APPROVAL PRIOR TO TRENCHING. ALIGN TO MINIMIZE IMPACT UPON CRITICAL ROOT ZONES OF EXISTING TREES, TYP.. LAYOUT MUST BE APPROVED BY PARD FORESTRY DIVISION PRIOR TO TRENCHING OPERATIONS.
- 2. MECHANICAL TRENCHING DISALLOWED WITHIN CRITICAL ROOT ZONE OF TREES. TRENCHING FOR IRRIGATION WITHIN THE CRITICAL ROOT ZONES SHALL BE PERFORMED WITH AIR SPADE UNDER SUPERVISION OF ISA CERTIFIED ARBORIST. NO ROOTS LARGER THAN ½" MAY BE CUT.
- 3. MOVEMENT OF TREE PROTECTION FENCE (TPF) WILL ONLY BE ALLOWED DURING TREE CARE ACTIVITIES OR AIR SPADE TRENCHING FOR IRRIGATION INSTALLATION. TPF MUST BE RE-INSTALLED IMMEDIATELY FOLLOWING TREE CARE AND IRRIGATION INSTALLATION AND/OR AT THE END OF EACH DAY. NO EQUIPMENT OR MATERIAL STAGING IS ALLOWED WITHIN THE CRZ.
- 4. ALL IRRIGATION EQUIPMENT SHALL BEAR FACTORY INSTALLED PURPLE MARKING OF NON-POTABLE WATER. ALL IRRIGATION PIPE SHALL BE MOLDED IN PURPLE PVC. TO DELINEATE NON-POTABLE WATER.
- 5. SEE TECHNICAL SPECIFICATIONS FOR ADDITIONAL INFORMATION





Sara Hensley
DIVISION MANAGER
Ricardo Soliz
PARK DEVELOPMENT COORDINATOR
Marty Stump
LANDSCAFE ARCHITECT
Marty Stump
Marty Stump


AUSTIN PARKS RECREATION


WOOLDRIDGE SQUARE LANDSCAPE IMPROVEMENTS WOOLDRIDGE SQUARE 900 GUADALUPE ST


WOOLDRIDGE SQUA
WOOLDRIDGE SQUA
SITE IRRIGATION PLAN


SHEET


0G/09/12 L-3












No Scale





WOOLDRIDGE SQUARE LANDSCAPE IMPROVEMENTS
WOOLDRIDGE SQUARE 900 GUADALUPE ST

APPROVED

DIRECTOR
Sara Hensley
DIVISION MANAGER
Ricardo Soliz
PARK DEVELOPMENT COORDINATOR
Marty Stump
LANDSCAFE ARCHITECT
Marty Stump

AUSTIN PARKSE RECREATION

WOOLDRIDGE SQUE THE STAND THE STAND