


<div> <div>A U S T I N C I T Y C O U N C I L</div> <div>AGENDA</div> <div>  </div> </div>	
<b>Recommendation for Council Action</b> <b>Water &amp; Wastewater Commission</b>	
<b>Council Meeting Date:</b>	August 20, 2015
<b>Department:</b>	Public Works
<b>SUBJECT</b>	
Authorize execution of a construction contract with <b>PEABODY GENERAL CONTRACTORS, INC.</b> (WBE 66.22%) for the Mains to Capitol Complex project in the amount of \$4,775,698.80 plus a \$238,784.94 contingency, for a total contract amount not to exceed \$5,014,483.74. (Districts 1 & 9)	
<b>AMOUNT AND SOURCE OF FUNDING</b>	
Funding is available in the Fiscal Year 2014-2015 Capital Budget of the Austin Water.	
<b>FISCAL NOTE</b>	
A fiscal note is attached.	
<b>Purchasing Language:</b>	Lowest bid of 4 bids received
<b>Prior Council Action:</b>	N/A
<b>For More Information</b>	John Wepryk, 512-974-7010; Dan Pedersen, 512-972-0074; Lucy Bonee, 512-974-7967; Elizabeth Godfrey, 512-974-7141
<b>Boards and Commission Action:</b>	To be reviewed by Water and Wastewater Commission on August 12, 2014.
<b>MBE/WBE:</b>	This contract will be awarded in compliance with Chapter 2-9A of the City Code (Minority Owned and Women Owned Business Enterprise Procurement Program) by meeting the goals with 11.48% MBE and 66.32% WBE participation.

The Mains to Capitol Complex is a reclaimed water project that will expand the reclaimed water pipe network to the Austin Downtown Central Business District. The project is part of Completing the Core, which is the near-term construction focus of Austin Water's Reclaimed Water Program. The pipeline will connect to an existing 12 inch reclaimed water main at Martin Luther King, Jr., Blvd. and Trinity Street. The pipeline route will extend south along Trinity Street on the east side of the Capitol Complex, then west along 11<sup>th</sup> Street and 10<sup>th</sup> Street to San Antonio Street at Woolridge Square.

The project consists of installation of approximately:

- 600 linear feet of 6-inch;
- 1,700 linear feet of 8-inch;
- 6,700 linear feet of 12-inch;
- 80 linear feet of 16-inch; and
- 900 linear feet of 24-inch ductile iron reclaimed water main pipe.

The project includes the installation of valves, service connections, erosion and sedimentation controls, tree protection, traffic control, re-vegetation, pavement, sidewalk, curb and gutter and driveway repairs.

Potential irrigation and cooling customers of the project include the Capitol Grounds, the Governor's Mansion, Travis County Office Complex, Waterloo Park, Woodridge Park, the UT Medical Center, the Waller Creek Center, and other various office buildings.

The Mains to Capitol Complex is a necessary prerequisite for the Junction 420 Main, which is scheduled to be bid in September 2015. The Junction 420 Main starts at Woolridge Square and runs down San Antonio, then across the river to Butler Park.

Due to the potential for unknown subsurface conditions and/or potential conflicts when working in the right of way, a 5% contingency in funding has been included to allow for the expeditious processing of any change orders.

The contract allows 510 calendar days for completion of this project. This project is located within zip code 78701(Districts 1 and 9) and is managed by the Public Works Department.

Peabody General Contractors, Inc. is located in Dripping Springs, Texas.

### **M/WBE Summary**


Bid documents were distributed to 8 general contractors. Bids were opened on June 18, 2015. Peabody General Contractors, Inc. submitted the lowest of 4 bids received:

Peabody General Contractors, Inc., Dripping Springs, TX	\$4,775,698.80
Facilities Rehabilitation, Taylor, TX	\$5,136,557.00
MA Smith Contracting Co, Austin, TX	\$5,963,344.20
SJ Louis Construction of Texas, San Antonio, TX	\$6,993,022.77

The contractor's choice of work methodology provides for 9 areas of subcontracting opportunities which are listed below. Participation goals stated in the solicitation were 6.21% MBE and 1.41% WBE. Total participation estimated on base bid amount of \$4,775,698.80:

M/WBE TOTAL – PRIME	\$3,162,510.45	66.22%
Peabody General Contractors, Inc., Dripping Springs, TX	\$3,162,510.45	66.22%
MBE TOTAL – SUBCONTRACTORS	\$548,188.00	11.48%
Hispanic Subtotal	\$3,000.00	0.06%
(FH) White Photo, Dripping Springs, TX (construction photography)	\$3,000.00	0.06%
Native/Asian Subtotal	\$545,188.35	11.42%
(MA) Alpha Paving, Round Rock, TX (paving)	\$540,898.35	11.33%
(FA) Metalink, Austin, TX (fencing)	\$4,290.00	0.09%
WBE TOTAL – SUBCONTRACTORS	\$5,000.00	0.10%
(WB) Roadway Specialties, Austin, TX (excavation)	\$5,000.00	0.10%
NON M/WBE TOTAL – SUBCONTRACTORS	\$1,060,000.00	22.20%
Flasher Equipment Co, Jarrell, TX (traffic control & striping)	\$200,000.00	4.20%
Techline Pipe, Hutto, TX (materials supply)	\$800,000.00	16.75%
Lauren Concrete, Round Rock, TX (concrete supply)	\$25,000.00	0.52%
Custom Crete, Austin, TX (concrete supply)	\$25,000.00	0.52%
Delta Survey, Austin, TX (surveying)	\$10,000.00	0.21%
The Contractor submitted a MBE/WBE Compliance Plan that met the goals of the solicitation or demonstrated a Good Faith Effort and was approved by the Department of Small & Minority Business Resources. Second and third low bidder information is provided.		
SECOND BIDDER - Facilities Rehabilitation, Taylor, TX	\$5,136,557.00	
98.25% MBE prime participation; 1.75% WBE; subcontractor participation.		
THIRD BIDDER - MA Smith Contracting Co, Austin, TX	\$5,963,344.20	
92.33% NON M/WBE; 6.22% MBE; 1.43% WBE; 0.02% Non M/WBE subcontractor participation		





VERIFY SCALE



BAR IS ONE INCH ON ORIGINAL  
DRAWING. IF NOT 1 INCH ON  
THIS SHEET, ADJUST SCALE

**JACOBS**

2705 BEE CAVE ROAD, SUITE 300, AUSTIN, TX 78746  
(512) 314-3100, FAX (512) 314-3135  
TBPE REGISTRATION #F-2966

**MAINS TO CAPITOL COMPLEX/AISD  
CIP 526.034**

**LOCATION MAP**

SHEET REF. NO.

**EX-A**



# CERTIFIED BID TAB

<b>CITY OF AUSTIN</b>				PROJECT SPONSOR: Austin Water Utility				BID OPENING DATE: 6/18/2015			
				BID CERTIFICATION: Monica Lopez				TIME: 1:30 PM			
<b>BID TABULATION</b>				AUTHORIZED CONTACT REP: Monica Lopez				LOCATION: 105 W. Riverside Dr.			
				PROJECT MANAGER: John Wepryk				PRICE EXPIRATION: 90 CAL. DAYS			
				PROJECT CONSULTANTS: Public Works-Engineering Services				LIQUIDATED DAMAGES: \$2,250/CAL. DAY			
PROJECT: Mains to Capitol Complex / AISD				SUB ID#: 5267.034				DURATION: 480 CAL. DAYS			
BID INVITATION NO: CLMC498								ESTIMATED AMOUNT: \$3,840,000.00			
FDU NUMBER(S): 3990 2107 4100								RESPONSES: 4			

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
LOCATION:				DRIPPING SPRINGS, TX		TAYLOR, TX		AUSTIN, TX		SAN ANTONIO, TX	
GUARANTEE: BB-Bid Bond				BB		BB		BB		BB	
ADDENDA ACKNOWLEDGED				1		1		1		1	

BID	QTY	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
104S-A	602	LF	REMOVE P.C. CONCRETE CURB	\$ 7.00	\$ 4,214.00	\$ 10.00	\$ 6,020.00	\$ 5.00	\$ 3,010.00	\$ 10.00	\$ 6,020.00
104S-C	240	SF	REMOVE P.C. CONCRETE SIDEWALKS AND DRIVEWAYS	\$ 5.00	\$ 1,200.00	\$ 5.00	\$ 1,200.00	\$ 9.00	\$ 2,160.00	\$ 15.00	\$ 3,600.00
315S-A	20,318	SY	SURFACE MILLING	\$ 5.00	\$ 101,590.00	\$ 4.00	\$ 81,272.00	\$ 6.50	\$ 132,067.00	\$ 8.50	\$ 172,703.00
315S-D	499	SY	EDGE MILLING	\$ 6.00	\$ 2,994.00	\$ 20.00	\$ 9,980.00	\$ 20.00	\$ 9,980.00	\$ 31.50	\$ 15,718.50
340S-B-1.5-D	23,982	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 1-1/2", TYPE D	\$ 20.00	\$ 479,640.00	\$ 20.00	\$ 479,640.00	\$ 12.00	\$ 287,784.00	\$ 14.00	\$ 335,748.00
340S-B-6-B	222	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 6", TYPE B	\$ 40.00	\$ 8,880.00	\$ 60.00	\$ 13,320.00	\$ 32.00	\$ 7,104.00	\$ 24.00	\$ 5,328.00
340S-B-10-B	828	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 10", TYPE B	\$ 60.00	\$ 49,680.00	\$ 90.00	\$ 74,520.00	\$ 54.00	\$ 44,712.00	\$ 41.50	\$ 34,362.00
340S-B-12-B	444	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 12", TYPE B	\$ 80.00	\$ 35,520.00	\$ 110.00	\$ 48,840.00	\$ 65.00	\$ 28,860.00	\$ 49.00	\$ 21,756.00

# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
340S-B-14-B	235	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 14", TYPE B	\$ 90.00	\$ 21,150.00	\$ 130.00	\$ 30,550.00	\$ 75.00	\$ 17,625.00	\$ 58.00	\$ 13,630.00
340S-B-16-B	418	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 16, TYPE B	\$ 100.00	\$ 41,800.00	\$ 150.00	\$ 62,700.00	\$ 85.00	\$ 35,530.00	\$ 66.00	\$ 27,588.00
340S-B-18-B	300	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 18, TYPE B	\$ 120.00	\$ 36,000.00	\$ 180.00	\$ 54,000.00	\$ 95.00	\$ 28,500.00	\$ 74.00	\$ 22,200.00
340S-B-20-B	56	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 20", TYPE B	\$ 140.00	\$ 7,840.00	\$ 200.00	\$ 11,200.00	\$ 110.00	\$ 6,160.00	\$ 82.00	\$ 4,592.00
360S-AH-7	1,291	SY	7" CONCRETE PAVEMENT (HIGH EARLY STRENGTH) INCLUDING DOWELS	\$ 100.00	\$ 129,100.00	\$ 95.00	\$ 122,645.00	\$ 47.00	\$ 60,677.00	\$ 40.00	\$ 51,640.00
360S-AH-8	1,360	SY	8" CONCRETE PAVEMENT (HIGH EARLY STRENGTH) INCLUDING DOWELS	\$ 110.00	\$ 149,600.00	\$ 103.00	\$ 140,080.00	\$ 54.00	\$ 73,440.00	\$ 45.00	\$ 61,200.00
360S-AH-10	153	SY	10" CONCRETE PAVEMENT (HIGH EARLY STRENGTH) INCLUDING DOWELS	\$ 130.00	\$ 19,890.00	\$ 140.00	\$ 21,420.00	\$ 66.00	\$ 10,098.00	\$ 52.00	\$ 7,956.00
402S-A	133	CY	CONTROLLED LOW STRENGTH MATERIAL	\$ 150.00	\$ 19,950.00	\$ 150.00	\$ 19,950.00	\$ 120.00	\$ 15,960.00	\$ 88.00	\$ 11,704.00
430S-B	592	LF	P.C. CONCRETE CURB AND GUTTER (FINE GRADING)	\$ 40.00	\$ 23,680.00	\$ 50.00	\$ 29,600.00	\$ 30.00	\$ 17,760.00	\$ 21.00	\$ 12,432.00
432SR-4	4,060	SF	RECONSTRUCT CONCRETE SIDEWALKS TO 4" THICKNESS, INCLUDING REMOVAL OF EXISTING SIDEWALK	\$ 10.00	\$ 40,600.00	\$ 15.00	\$ 60,900.00	\$ 8.50	\$ 34,510.00	\$ 7.30	\$ 29,638.00
432S-RP-I	2	EA	P.C. SIDEWALK CURB RAMP WITH PAVERS (TYPE I), INCLUDING REMOVAL OF EXISTING SIDEWALK	\$ 2,000.00	\$ 4,000.00	\$ 4,000.00	\$ 8,000.00	\$ 1,300.00	\$ 2,600.00	\$ 1,925.00	\$ 3,850.00
433S-A	240	SF	TYPE I P.C. CONCRETE DRIVEWAY	\$ 20.00	\$ 4,800.00	\$ 25.00	\$ 6,000.00	\$ 11.00	\$ 2,640.00	\$ 13.00	\$ 3,120.00
480S-RS	300	SF	RECONSTRUCT CONCRETE PAVER SIDEWALK, INCLUDING REMOVAL OF EXISTING SIDEWALK	\$ 15.00	\$ 4,500.00	\$ 40.00	\$ 12,000.00	\$ 20.00	\$ 6,000.00	\$ 11.00	\$ 3,300.00
501S	165	LF	JACKING OR BORING 24" DIA STEEL PIPE, ASTM A134, MIN 3/8" WALL THICKNESS	\$ 400.00	\$ 66,000.00	\$ 500.00	\$ 82,500.00	\$ 600.00	\$ 99,000.00	\$ 524.00	\$ 86,460.00

# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
505S-B-16	43	LF	ENCASEMENT PIPE, 16" DIA STEEL, ASTM A134, MIN 3/8" WALL THICKNESS	\$ 250.00	\$ 10,750.00	\$ 150.00	\$ 6,450.00	\$ 75.00	\$ 3,225.00	\$ 56.00	\$ 2,408.00
505S-B-24	387	LF	ENCASEMENT PIPE, 24" DIA STEEL, ASTM A134, MIN 3/8" WALL THICKNESS	\$ 275.00	\$ 106,425.00	\$ 150.00	\$ 58,050.00	\$ 100.00	\$ 38,700.00	\$ 87.00	\$ 33,669.00
505S-B-48	20	LF	ENCASEMENT PIPE, 48" DIA STEEL, ASTM A134, MIN 3/8" WALL THICKNESS	\$ 300.00	\$ 6,000.00	\$ 500.00	\$ 10,000.00	\$ 235.00	\$ 4,700.00	\$ 300.00	\$ 6,000.00
509S-1	9,337	LF	TRENCH EXCAVATION SAFETY PROTECTIVE SYSTEMS (ALL DEPTHS)	\$ 5.00	\$ 46,685.00	\$ 1.00	\$ 9,337.00	\$ 1.00	\$ 9,337.00	\$ 0.01	\$ 93.37
510-AR-6-DI	640	LF	RESTRAINED JOINT PIPE PER SPL WW-27G, 6" DIA., CLASS 350 DUCTILE IRON (ALL DEPTHS), INCLUDING EXCAVATION & BACKFILL	\$ 100.00	\$ 64,000.00	\$ 150.00	\$ 96,000.00	\$ 285.00	\$ 182,400.00	\$ 454.00	\$ 290,560.00
510-AR-8-DI	1,623	LF	RESTRAINED JOINT PIPE PER SPL SPL WW-27G, 8" DIA, CLASS 350 DUCTILE IRON (ALL DEPTHS), INCLUDING EXCAVATION & BACKFILL	\$ 120.00	\$ 194,760.00	\$ 192.00	\$ 311,616.00	\$ 300.00	\$ 486,900.00	\$ 461.00	\$ 748,203.00
510-AR-12-DI	6,684	LF	RESTRAINED JOINT PIPE PER SPL SPL WW-27G, 12" DIA, CLASS 350 DUCTILE IRON (ALL DEPTHS), INDLUDING EXCAVATION & BACKFILL	\$ 150.00	\$ 1,002,600.00	\$ 217.00	\$ 1,450,428.00	\$ 305.00	\$ 2,038,620.00	\$ 491.00	\$ 3,281,844.00
510-ARRJ-16-DI	79	LF	FACTORY RESTRAINED JOINT PIPE PER SPL WW-27F, 16" DIA, CLASS 250 DUCTILE IRON (ALL DEPTHS), INCLUDING EXCAVATION & BACKFILL	\$ 225.00	\$ 17,775.00	\$ 400.00	\$ 31,600.00	\$ 325.00	\$ 25,675.00	\$ 610.00	\$ 48,190.00
510-ARRJ-24-DI	894	LF	FACTORY RESTRAINED JOINT PIPE PER SPL WW-27F, 24" DIA, CLASS 250 DUCTILE IRON (ALL DEPTHS), INCLUDING EXCAVATION AND BACKFILL	\$ 275.00	\$ 245,850.00	\$ 387.00	\$ 345,978.00	\$ 425.00	\$ 379,950.00	\$ 651.00	\$ 581,994.00
510-BR-1.5	35	EA	CONNECTING NEW 1-1/2" RECLAIMED WATER SINGLE SERVICE INCLUDING METER BOX PER PLANS AND DETAIL F, SHEET C-31	\$ 3,500.00	\$ 122,500.00	\$ 3,000.00	\$ 105,000.00	\$ 7,200.00	\$ 252,000.00	\$ 2,025.00	\$ 70,875.00

# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
510-BR-2	5	EA	CONNECTING NEW 2" RECLAIMED WATER SINGLE SERVICE INCLUDING METER BOX PER PLANS AND DETAIL F, SHEET C-31	\$ 4,000.00	\$ 20,000.00	\$ 4,000.00	\$ 20,000.00	\$ 8,700.00	\$ 43,500.00	\$ 2,486.00	\$ 12,430.00
510-BW-1.5	1	EA	CONNECTING NEW 1-1/2" POTABLE WATER SINGLE SERVICE INCLUDING METER BOX PER PLANS AND DETAIL 520S-13B, SHEET C-29	\$ 4,000.00	\$ 4,000.00	\$ 3,000.00	\$ 3,000.00	\$ 8,800.00	\$ 8,800.00	\$ 1,900.00	\$ 1,900.00
510-JR-12"X12" DIA	1	EA	WET CONNECTIONS, 12" DIA X 12" DIA	\$ 2,000.00	\$ 2,000.00	\$ 4,500.00	\$ 4,500.00	\$ 8,900.00	\$ 8,900.00	\$ 1,400.00	\$ 1,400.00
510-KR	8	TON	DUCTILE IRON FITTINGS	\$ 20,000.00	\$ 160,000.00	\$ 18,000.00	\$ 144,000.00	\$ 17,000.00	\$ 136,000.00	\$ 1.00	\$ 8.00
511S-A-6	14	EA	VALVES, GATE TYPE, 6" DIA	\$ 1,400.00	\$ 19,600.00	\$ 1,400.00	\$ 19,600.00	\$ 2,500.00	\$ 35,000.00	\$ 1,211.00	\$ 16,954.00
511S-A-8	8	EA	VALVES, GATE TYPE, 8" DIA	\$ 2,000.00	\$ 16,000.00	\$ 1,800.00	\$ 14,400.00	\$ 2,700.00	\$ 21,600.00	\$ 1,525.00	\$ 12,200.00
511S-A-12	17	EA	VALVES, GATE TYPE, 12" DIA	\$ 4,000.00	\$ 68,000.00	\$ 2,400.00	\$ 40,800.00	\$ 3,800.00	\$ 64,600.00	\$ 2,300.00	\$ 39,100.00
511S-A-24	4	EA	VALVES, GATE TYPE, 24" DIA	\$ 38,000.00	\$ 152,000.00	\$ 18,000.00	\$ 72,000.00	\$ 28,000.00	\$ 112,000.00	\$ 19,150.00	\$ 76,600.00
511S-F-1-TR	3	EA	AUTOMATIC COMBINATION AIR/VACUUM RELEASE VALVE ASSEMBLY, 1" DIA, TRAFFIC RATED, REFERENCE DETAIL B, SHEET C-29	\$ 3,500.00	\$ 10,500.00	\$ 2,500.00	\$ 7,500.00	\$ 3,900.00	\$ 11,700.00	\$ 1,785.00	\$ 5,355.00
511S-F-1-NT	1	EA	AUTOMATIC COMBINATION AIR/VACUUM RELEASE VALVE ASSEMBLY, 1" DIA, NON-TRAFFIC RATED, REFERENCE DETAIL A, SHEET C-29	\$ 3,000.00	\$ 3,000.00	\$ 2,500.00	\$ 2,500.00	\$ 9,500.00	\$ 9,500.00	\$ 2,370.00	\$ 2,370.00
511S-F-2-NT	1	EA	AUTOMATIC COMBINATION AIR/VACUUM RELEASE VALVE ASSEMBLY, 2" DIA, NON-TRAFFIC RATED, REFERENCE DETAIL A, SHEET C-29	\$ 5,000.00	\$ 5,000.00	\$ 3,500.00	\$ 3,500.00	\$ 5,100.00	\$ 5,100.00	\$ 2,685.00	\$ 2,685.00
602S-A	133	SY	BERMUDA BLOCK SODDING	\$ 10.00	\$ 1,330.00	\$ 20.00	\$ 2,660.00	\$ 12.00	\$ 1,596.00	\$ 8.20	\$ 1,090.60
602S-B	94	SY	ST. AUGUSTINE BLOCK SODDING	\$ 10.00	\$ 940.00	\$ 20.00	\$ 1,880.00	\$ 10.00	\$ 940.00	\$ 8.20	\$ 770.80
604S-C	100	SY	NATIVE SEEDING FOR EROSION CONTROL METHOD, FIBER MULCH	\$ 5.00	\$ 500.00	\$ 5.00	\$ 500.00	\$ 10.00	\$ 1,000.00	\$ 10.00	\$ 1,000.00
605S-A	744	SY	SOIL RETENTION BLANKET CLASS I; TYPE C	\$ 5.00	\$ 3,720.00	\$ 10.00	\$ 7,440.00	\$ 2.50	\$ 1,860.00	\$ 2.50	\$ 1,860.00
609S-C	744	SY	NATIVE GRASSLAND SEEDING AND PLANTING	\$ 5.00	\$ 3,720.00	\$ 5.00	\$ 3,720.00	\$ 18.00	\$ 13,392.00	\$ 8.00	\$ 5,952.00



# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
628S-B	62	LF	SEDIMENT CONTAINMENT DIKES WITH FILTER FABRIC	\$ 15.00	\$ 930.00	\$ 50.00	\$ 3,100.00	\$ 13.00	\$ 806.00	\$ 8.50	\$ 527.00
641S	1	EA	STABILIZED CONSTRUCTION	\$ 1,300.00	\$ 1,300.00	\$ 2,000.00	\$ 2,000.00	\$ 1,000.00	\$ 1,000.00	\$ 1,500.00	\$ 1,500.00
642S	253	LF	SILT FENCE FOR EROSION CONTROL	\$ 3.00	\$ 759.00	\$ 5.00	\$ 1,265.00	\$ 2.50	\$ 632.50	\$ 4.00	\$ 1,012.00
700S-TM	1	LS	TOTAL MOBILIZATION PAYMENT	\$150,000.00	\$ 150,000.00	\$200,000.00	\$ 200,000.00	\$ 220,000.00	\$ 220,000.00	\$200,000.00	\$ 200,000.00
701S-CD15	1	EA	CHAIN LINK VEHICULAR DOUBLE SWING GATE, 6 FOOT X 15 FOOT, WITH SCREENING FABRIC	\$ 1,000.00	\$ 1,000.00	\$ 1,500.00	\$ 1,500.00	\$ 1,600.00	\$ 1,600.00	\$ 1,000.00	\$ 1,000.00
701S-T	396	LF	TEMPORARY FENCE, 6 FOOT HIGH, CHAIN LINK TYPE, WITH SCREENING FABRIC	\$ 15.00	\$ 5,940.00	\$ 40.00	\$ 15,840.00	\$ 14.00	\$ 5,544.00	\$ 20.00	\$ 7,920.00
703	1,500	LF	SAFETY FENCING	\$ 5.00	\$ 7,500.00	\$ 30.00	\$ 45,000.00	\$ 4.00	\$ 6,000.00	\$ 5.00	\$ 7,500.00
710S-A	1	EA	CLASS II BICYCLE RACK	\$ 1,000.00	\$ 1,000.00	\$ 500.00	\$ 500.00	\$ 1,800.00	\$ 1,800.00	\$ 1,000.00	\$ 1,000.00
725S-A	2	EA	TYPE A SURVEY IDENTIFICATION	\$ 2,000.00	\$ 4,000.00	\$ 500.00	\$ 1,000.00	\$ 125.00	\$ 250.00	\$ 500.00	\$ 1,000.00
802S-B-C.I.P.	3	EA	C.I.P. PROJECT SIGN	\$ 800.00	\$ 2,400.00	\$ 1,500.00	\$ 4,500.00	\$ 600.00	\$ 1,800.00	\$ 800.00	\$ 2,400.00
803S-MO	16	MO	BARRICADES, SIGNS, AND TRAFFIC HANDLING	\$ 12,000.00	\$ 192,000.00	\$ 500.00	\$ 8,000.00	\$ 7,500.00	\$ 120,000.00	\$ 1.00	\$ 16.00
829S-A	1,630	LF	TYPE I BICYCLE LANE MARKINGS, 4" IN WIDTH, WHITE IN COLOR	\$ 0.45	\$ 733.50	\$ 2.00	\$ 3,260.00	\$ 3.25	\$ 5,297.50	\$ 2.75	\$ 4,482.50
829S-B	24	EA	TYPE I BICYCLE LANE PREFERENTIAL (DIRECTIONAL ARROW) SYMBOLS, WHITE IN COLOR	\$ 150.00	\$ 3,600.00	\$ 250.00	\$ 6,000.00	\$ 190.00	\$ 4,560.00	\$ 200.00	\$ 4,800.00
829S-C	19	EA	TYPE I BICYCLE LANE (BIKE RIDER) SYMBOL, WHITE IN COLOR	\$ 300.00	\$ 5,700.00	\$ 250.00	\$ 4,750.00	\$ 270.00	\$ 5,130.00	\$ 240.00	\$ 4,560.00
863S-2	256	EA	REFLECTORIZED PAVEMENT MARKERS (TYPE I-C)	\$ 6.30	\$ 1,612.80	\$ 10.00	\$ 2,560.00	\$ 6.50	\$ 1,664.00	\$ 5.75	\$ 1,472.00
863S-3	80	EA	REFLECTORIZED PAVEMENT MARKERS (TYPE II-A-A)	\$ 6.30	\$ 504.00	\$ 10.00	\$ 800.00	\$ 6.50	\$ 520.00	\$ 5.75	\$ 460.00
870S-A-4-W	2,125	LF	WORK ZONE PAVEMENT MARKINGS (REMOVABLE), 4" IN WIDTH, WHITE IN COLOR	\$ 1.38	\$ 2,932.50	\$ 2.00	\$ 4,250.00	\$ 2.60	\$ 5,525.00	\$ 2.25	\$ 4,781.25
870S-A-4-Y	7,185	LF	WORK ZONE PAVEMENT MARKINGS (REMOVABLE), 4" IN WIDTH, YELLOW IN COLOR	\$ 1.38	\$ 9,915.30	\$ 2.00	\$ 14,370.00	\$ 2.60	\$ 18,681.00	\$ 2.25	\$ 16,166.25

# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
870S-A-4-B	25,173	LF	WORK ZONE PAVEMENT MARKINGS (REMOVABLE), 4" IN WIDTH, BLACK IN COLOR	\$ 2.34	\$ 58,904.82	\$ 2.00	\$ 50,346.00	\$ 4.40	\$ 110,761.20	\$ 3.75	\$ 94,398.75
870S-A-12-B	2,319	LF	WORK ZONE PAVEMENT MARKINGS (REMOVABLE), 12" IN WIDTH, BLACK IN COLOR	\$ 7.02	\$ 16,279.38	\$ 5.00	\$ 11,595.00	\$ 9.00	\$ 20,871.00	\$ 7.50	\$ 17,392.50
870S-A-24-B	2,025	LF	WORK ZONE PAVEMENT MARKINGS (REMOVABLE), 24" IN WIDTH, BLACK IN COLOR	\$ 14.10	\$ 28,552.50	\$ 10.00	\$ 20,250.00	\$ 15.00	\$ 30,375.00	\$ 13.00	\$ 26,325.00
870S-A-24-W	200	LF	WORK ZONE PAVEMENT MARKINGS (REMOVABLE), 24" IN WIDTH, WHITE IN COLOR	\$ 10.20	\$ 2,040.00	\$ 20.00	\$ 4,000.00	\$ 13.00	\$ 2,600.00	\$ 11.50	\$ 2,300.00
271S-A-4-90-BW	10,220	LF	REFLECTORIZED TYPE I THERMOPLASTIC PAVEMENT MARKINGS, 4" IN WIDTH, 90 MILS IN THICKNESS, BROKEN WHITE LINE IN COLOR	\$ 0.45	\$ 4,599.00	\$ 2.00	\$ 20,440.00	\$ 1.10	\$ 11,242.00	\$ 1.00	\$ 10,220.00
871S-A-4-90-SW	7,760	LF	REFLECTORIZED TYPE I THERMOPLASTIC PAVEMENT MARKINGS, 4" IN WIDTH, 90 MILS IN THICKNESS, SOLID WHITE LINE IN COLOR	\$ 0.45	\$ 3,492.00	\$ 2.00	\$ 15,520.00	\$ 1.00	\$ 7,760.00	\$ 1.00	\$ 7,760.00
871S-A-4-90-SY	5,520	LF	REFLECTORIZED TYPE I THERMOPLASTIC PAVEMENT MARKINGS, 4" IN WIDTH, 90 MILS IN THICKNESS, SOLID YELLOW LINE IN COLOR	\$ 0.45	\$ 2,484.00	\$ 2.00	\$ 11,040.00	\$ 1.00	\$ 5,520.00	\$ 1.00	\$ 5,520.00
871S-A-12-90-SW	2,319	LF	REFLECTORIZED TYPE I THERMOPLASTIC PAVEMENT MARKINGS, 12" IN WIDTH, 90 MILS IN THICKNESS, SOLID WHITE LINE IN COLOR	\$ 4.50	\$ 10,435.50	\$ 5.00	\$ 11,595.00	\$ 3.00	\$ 6,957.00	\$ 2.50	\$ 5,797.50
871S-A-24-90-SW	2,025	LF	REFLECTORIZED TYPE I THERMOPLASTIC PAVEMENT MARKINGS, 24" IN WIDTH, 90 MILS IN THICKNESS, SOLID WHITE LINE IN COLOR	\$ 9.00	\$ 18,225.00	\$ 10.00	\$ 20,250.00	\$ 5.50	\$ 11,137.50	\$ 4.75	\$ 9,618.75

# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
SP505S-B-24	57	LF	ENCASEMENT PIPE 24" DIA, STEEL COMPLETE AND IN PLACE THROUGH BOX CULVERT ON LINE F, STA 14+94.62 TO STA 15+51.88	\$ 450.00	\$ 25,650.00	\$ 150.00	\$ 8,550.00	\$ 90.00	\$ 5,130.00	\$ 145.00	\$ 8,265.00
SP505S-B-24-1	5	LF	ENCASEMENT PIPE 24" DIA, STEEL, SPLIT CASING COMPLETE AND IN PLACE AT LINE 'A' WET CONNECTION RECEIVING PIT	\$ 600.00	\$ 3,000.00	\$ 250.00	\$ 1,250.00	\$ 460.00	\$ 2,300.00	\$ 116.00	\$ 580.00
SP506-Q1	2	JOINT	EXTERNAL WATERPROOFING OF 48-INCH DIAMETER MANHOLE JOINT USING SPL WW146A, COMPLETE AND IN PLACE	\$ 2,500.00	\$ 5,000.00	\$ 500.00	\$ 1,000.00	\$ 3,000.00	\$ 6,000.00	\$ 1,000.00	\$ 2,000.00
SP510-BR-2B	1	LS	CUT, PLUG AND REMOVE PORTION OF 2" POTABLE WATER SERVICE CONNECTION (LINE B AT STA 30+ 51.56). INSTALL 35 LF 2" HDPE SERVICE LINE TO RPZ INCLUDING 2" SADDLE AND APPURTENANCES. COORDINATE WITH CAPITOL CITY STUDIOS	\$ 6,000.00	\$ 6,000.00	\$ 2,000.00	\$ 2,000.00	\$ 5,000.00	\$ 5,000.00	\$ 700.00	\$ 700.00
SP510-BW-2	1	LS	DISCONNECT EXISTING 4" POTABLE WATER BRANCH AND REMOVE EXISTING 2" METER AND BOX AT WOOLDRIDGE SQUARE (W.9TH ST. BETWEEN SAN ANTONIO ST. AND GUADALUPE ST., AS SHOWN ON SHEET C-1	\$ 6,000.00	\$ 6,000.00	\$ 2,000.00	\$ 2,000.00	\$ 1,500.00	\$ 1,500.00	\$ 10,000.00	\$ 10,000.00
SP510-BR-1.5B	1	LS	CONNECTING NEW 1-1/2" RECLAIMED WATER SERVICE INCLUDING TRENCHLESS INSTALLATION BELOW EXISTING RETAINING WALL FOUNDATION (LINE B AT STA 15+100	\$ 6,000.00	\$ 6,000.00	\$ 2,000.00	\$ 2,000.00	\$ 7,500.00	\$ 7,500.00	\$ 6,550.00	\$ 6,550.00
SP511S-J-TR	6	EA	BLOW-OFF VALVE ASSEMBLY, 4" TRAFFIC RATED, NON-FREEZING, REFERENCE DETAIL D, SHEET C-30	\$ 6,000.00	\$ 36,000.00	\$ 3,000.00	\$ 18,000.00	\$ 4,200.00	\$ 25,200.00	\$ 3,300.00	\$ 19,800.00

# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
SP511S-J-NT	9	EA	BLOW-OFF VALVE ASSEMBLY, 4" NON-TRAFFIC RATED, NON-FREEZING, REFERENCE DETAIL C, SHEET C-30								
				\$ 5,500.00	\$ 49,500.00	\$ 2,500.00	\$ 22,500.00	\$ 3,600.00	\$ 32,400.00	\$ 3,300.00	\$ 29,700.00
SP610S-P	1	EA	TREE PRUNING AND P-6 TREATMENT	\$ 2,500.00	\$ 2,500.00	\$ 1,000.00	\$ 1,000.00	\$ 625.00	\$ 625.00	\$ 2,000.00	\$ 2,000.00
SP610S-W	1	EA	TREE PROTECTION (WOOD PLANKING)	\$ 500.00	\$ 500.00	\$ 1,000.00	\$ 1,000.00	\$ 150.00	\$ 150.00	\$ 125.00	\$ 125.00
SP700S	4	EA	SPECIAL EVENT STOP WORK	\$ 1,000.00	\$ 4,000.00	\$ 50,000.00	\$ 200,000.00	\$ 7,000.00	\$ 28,000.00	\$ 5,000.00	\$ 20,000.00
SP803S-CD	6	CD	BARRICADES, SIGNS, AND TRAFFIC HANDLING (FOR WEEKEND WORK ON GUADALUPE ST.)	\$ 1,000.00	\$ 6,000.00	\$ 500.00	\$ 3,000.00	\$ 2,300.00	\$ 13,800.00	\$ 1.00	\$ 6.00
SP803S-BAS	5	EA	PROJECT SIGN FOR BUSINESS ACCESS	\$ 500.00	\$ 2,500.00	\$ 1,000.00	\$ 5,000.00	\$ 600.00	\$ 3,000.00	\$ 200.00	\$ 1,000.00
SP803S-PS	1,680	CD	PORTABLE CHANGEABLE MESSAGE SIGN	\$ 100.00	\$ 168,000.00	\$ 10.00	\$ 16,800.00	\$ 20.00	\$ 33,600.00	\$ 1.00	\$ 1,680.00
SP862S-4-W	16,385	LF	4" WHITE MARKINGS	\$ 1.38	\$ 22,611.30	\$ 2.00	\$ 32,770.00	\$ 1.30	\$ 21,300.50	\$ 1.00	\$ 16,385.00
SP862S-4-Y	3,510	LF	4" YELLOW MARKINGS	\$ 1.38	\$ 4,843.80	\$ 2.00	\$ 7,020.00	\$ 1.30	\$ 4,563.00	\$ 1.00	\$ 3,510.00
SP862S-12-W	1,614	LF	12" WHITE MARKINGS	\$ 5.10	\$ 8,231.40	\$ 10.00	\$ 16,140.00	\$ 5.00	\$ 8,070.00	\$ 2.50	\$ 4,035.00
SP862S-24-W	1,200	LF	24" WHITE MARKINGS	\$ 10.20	\$ 12,240.00	\$ 20.00	\$ 24,000.00	\$ 10.00	\$ 12,000.00	\$ 4.75	\$ 5,700.00
SS025100-12-DI-TRINITY	1	LS	FACTORY RESTRAINED JOINT PIPE, 12" DI CLASS 350 PER SPL WW-27F, COMPLETE IN PLACE, INCLUDING CORE DRILLING ABUTMENTS, CLEVIS HANGER TYPE SUPPORTS, ANCHORS, AND INSTALLATION AT WALLER CREEK CROSSING UNDER TRINITY ST - LINE A (STA-28+20 TO STA 29+11)	\$ 85,000.00	\$ 85,000.00	\$ 35,000.00	\$ 35,000.00	\$ 80,000.00	\$ 80,000.00	\$ 60,000.00	\$ 60,000.00



# CERTIFIED BID TAB

BIDDER(S):				PEABODY GENERAL CONTRACTORS, INC.		FACILITIES REHABILITATION, INC.		M.A. SMITH CONTRACTING CO., INC.		S.J LOUIS CONSTRUCTION OF TEXAS LTD	
SS025100-12-DI-E 12TH ST	1	LS	FACTORY RESTRAIND JOINT PIPE, 12" DI CLASS 350 PER SPL WW-27F, COMPLETE IN PLACE, INCLUDING CORE DRILLING ABUTMENTS, CLEVIS HANGER TYPE SUPPORTS, ANCHORS, INSTALLATION AT WALLER CREEK CROSSING UNDER EAST 12TH ST - LINE C (STA 12+33 TO STA 13+35), AND REMOVAL OR EXISTING 4" DUCTILE IRON PIPE AS REQUIRED FROM STA 12+42 TO STA 13+24	\$ 90,000.00	\$ 90,000.00	\$ 35,000.00	\$ 35,000.00	\$ 92,000.00	\$ 92,000.00	\$ 65,000.00	\$ 65,000.00
SS025100-16-DI-RED RIVER ST	1	LS	FACTORY RESTRAIND JOINT PIPE, 16" DI CLASS 250 PER SPL WW-27, COMPLETE IN PLACE, INCLUDING CORE DRILLING ABUTMENTS, CLEVIS HANGER TYPE SUPPORTS, ANCHORS, AND INSTALLATION AT WALLER CREEK CROSSING UNDER RED RIVER ST - LINE F (STA 15+68 TO STA 16+11)	\$ 80,000.00	\$ 80,000.00	\$ 50,000.00	\$ 50,000.00	\$ 74,000.00	\$ 74,000.00	\$ 54,000.00	\$ 54,000.00
SS025100-8-DI-E 10TH ST	1	LS	FACTORY RESTRAIND JOINT PIPE, 8" DI CLASS 350 PER SPL WW-27F, COMPLETE IN PLACE, INCLUDING CORE DRILLING ABUTMENTS, CLEVIS HANGER TYPE SUPPORTS, ANCHORS, AND INSTALLATION AT WALLER CREEK CROSSING UNDER E 10TH ST - LINE G (STA 11+12 TO STA 12+14)	\$ 75,000.00	\$ 75,000.00	\$ 20,000.00	\$ 20,000.00	\$ 76,000.00	\$ 76,000.00	\$ 62,000.00	\$ 62,000.00
<b>TOTAL BID:</b>					<b>\$ 4,775,698.80</b>		<b>\$ 5,136,557.00</b>		<b>\$ 5,963,344.20</b>		<b>\$ 6,993,022.77</b>

TRUE COPY OF BID TABULATION AS RECEIVED  
OR CORRECTED IN ACCORDANCE WITH  
CONDITIONS GOVERNING PROPOSALS.

 6/26/15  
CONTRACT MANAGEMENT DEPARTMENT DATE  
CONTRACT PROCUREMENT & DEVELOPMENT DIVISION,  
CITY OF AUSTIN, TX