

1 the Plan; and shall provide fee-in-lieu of affordable housing under section 4.3.3
2 D of the Plan.

3
4 B. One Hundred affordable units will be constructed as part of the development of
5 the Property subject to this ordinance.

6
7 C. The Property Owner shall pay a fee-in-lieu of providing on-site affordable
8 housing units for the additional square footage above the 2:1 floor-to-area ratio
9 (the "Bonus Square Footage"). The amount of the fee-in-lieu shall be calculated
10 by Neighborhood Housing and Community Department ("NHCD") based upon
11 the Bonus Square Footage of the Project. A building permit may not be issued
12 until:

13
14 1. The Bonus Square Footage is calculated, certified, and submitted to
15 NHCD, Attention: Real Estate and Development Division, and

16
17 2. The fee is paid to NHCD.

18
19 D. In this section, MFI means the median family income for the Austin-Round
20 Rock metropolitan statistical area, as determined annually by the United States
21 Department of Housing and Urban Development. The affordable housing units
22 on the Property shall be set aside for occupancy by households with incomes at
23 or below 30%, 50%, and 60%, resulting in an average of at or below 50% MFI
24 for all affordable units.

25
26 **PART 3.** The site development regulations for the Property within the boundaries of the
27 CURE combining district established by this ordinance are modified as follows:

28
29 A. The maximum height of a building or structure on the Property shall be limited
30 to 68 feet and no more than 5 stories.

31
32 **PART 4.** The Property is subject to Ordinance No. 20081211-082 that established zoning
33 for the East Cesar Chavez Neighborhood Plan.

34
35 **PART 5.** Except as specifically restricted under this ordinance, the Property may be
36 developed and used in accordance with the regulations established for the transit oriented
37 development (TOD) district, the central urban redevelopment (CURE) combining district
38 and other applicable requirements of the City Code.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16

PART 6. This ordinance takes effect on _____, 2017.

PASSED AND APPROVED

_____, 2017

§
§
§


Steve Adler
Mayor

APPROVED: _____

Anne L. Morgan
City Attorney

ATTEST: _____

Jannette S. Goodall
City Clerk



FIELD NOTES FOR 0.873 ACRES OF LAND

DESCRIPTION OF 0.873 OF ONE ACRE (38,036 SQUARE FEET) OF LAND, MORE OR LESS, BEING ALL OF LOTS 7 THROUGH 12, BLOCK NO. 1, R.H. PECK SUBDIVISION, A SUBDIVISION OF RECORD IN BOOK 5, PAGE 551, PLAT RECORDS, TRAVIS COUNTY, TEXAS, SAME BEING OUT OF THAT TRACT OF LAND DESCRIBED AS PARCEL 7 IN A DEED TO CAPITAL METROPOLITAN TRANSPORTATION AUTHORITY, OF RECORD IN VOLUME 10703, PAGE 972, REAL PROPERTY RECORDS, TRAVIS COUNTY, TEXAS; SAID 0.873 OF ONE ACRE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING at a 1/2" iron rod found cap at the northeast corner of this tract, said Lot 7, and said Capital Metropolitan Transportation Authority (CapMetro) Parcel 7 tract, same being in the west line of Onion Street and the south line of Fifth Street, said point of beginning having a State Plane Coordinate, Texas Central Zone, NAD83 (96CORS) grid value of N=10,068,797.34, E=3,119,008.54;

THENCE, with the east line of this tract, said Lot 7, and said CapMetro Parcel 7 tract and the west line of Onion Street, **S20°45'27"W 132.35 feet** to a mag nail found at the southeast corner of this tract, said Lot 7, and said CapMetro Parcel 7 tract, same being in the north line of a 20 foot alley;

THENCE, with the south line of this tract, said Lots 7 through 12, and said CapMetro Parcel 7 tract and the north line of said 20 foot alley, **N69°39'23"W 287.69 feet** to a 1/2" iron rod found with cap at the southwest corner of this tract, said Lot 12, and said CapMetro Parcel 7 tract, same being in the east line of Navasota Street;

THENCE, with the west line of this tract, said Lot 12, and said CapMetro Parcel 7 tract and the east line of Navasota Street, **N20°45'50"E**, passing at 2.47 feet a 1/2" iron rod found, continuing 129.62 for a total of **132.09 feet** to a mag nail found at the northwest corner of this tract, said Lot 12, and said CapMetro Parcel 7 tract, same being in the south line of Fifth Street, from which a 1/2" iron rod found at the northeast corner of CapMetro Parcel 7 tract in said CapMetro deed recorded in said Volume 10703, Page 972, bears **N69°42'29"W 40.00 feet**;

0.873 AC.

THENCE, with the north line of this tract, said Lots 12 through 7, and said CapMetro Parcel 7 tract and the south line of Fifth Street, **S69°42'29"E 287.68 feet** to the POINT OF BEGINNING and containing 0.873 of one acre, more or less, within these metes and bounds.

Bearing Basis Note

The bearings described herein are based on the Texas State Plane Coordinate System, Central Zone, NAD83 (96CORS) Datum.

SURVEYED BY:

McGRAY & McGRAY LAND SURVEYORS, INC.

3301 Hancock Dr., Ste. 6

Austin, TX 78731 (512) 451-8591

TBPLS Firm# 10095500



12/10/15

Chris Conrad, Reg. Professional Land Surveyor No. 5623

Date

Note: This copy of this description is not valid unless an original signature through an original seal appears on its face. There is a plat to accompany this description



Descriptions 2014/Plaza Saltillo/Tract C

Issued 12/10/15

AUSTIN GRID J-22

SKETCH TO ACCOMPANY DESCRIPTION OF 0.873 AC. OR 38,036 SQ. FT. OF LAND OUT OF LOTS 7-12, BLOCK NO. 1, R.H. PECK SUBDIVISION, AUSTIN, TRAVIS COUNTY, TEXAS.

SCALE 1" = 50'



FIFTH STREET
(PINE STREET)
(80' R.O.W.)

P.O.B.
GRID COORDINATES
N=10,068,797.34
E=3,119,008.54

(S67°19'45"E 287.92')
S69°42'29"E 287.68'

N69°42'29"W
40.00'

CAPITAL METROPOLITAN
TRANSPORTATION AUTHORITY
VOL. 10703, PG. 972
R.P.R.T.C. (PARCEL 6)

BLOCK NO. 1
R. H. PECK SUBDIVISION
BK. 5, PG. 551
P.R.T.C.

CAPITAL METROPOLITAN
TRANSPORTATION AUTHORITY
VOL. 10703, PG. 972
R.P.R.T.C.
(PARCEL 7)

0.873 AC.
38,036 SQ.FT.

(N23°08'50"E 132.09')
N20°45'50"E 132.09'

S20°45'27"W 132.35'
(S23°08'10"W 132.35')

LOT 12

LOT 11

LOT 10

LOT 9

LOT 8

LOT 7

SEE
DETAIL

N69°39'23"W 287.69'
(N67°16'40"W 287.94')

ALLEY (20')

ONION STREET
(40' R.O.W.)

NAVASOTA
STREET
(40' R.O.W.)

ROBERT C. BEALL AND WIFE, BETH A. BEALL
DOC. 1999026488

LOT 1

LOT 2

LOT 3

LOT 4

LOT 5

LOT 6


PAGE 3 OF 4
SURVEYED BY:

McGRAY & McGRAY
LAND SURVEYORS, INC.

3301 HANCOCK DRIVE #6
AUSTIN, TEXAS 78731
(512) 451-8591



SKETCH TO ACCOMPANY DESCRIPTION OF 0.873 AC. OR 38,036 SQ. FT. OF LAND OUT OF LOTS 7-12, BLOCK NO. 1, R.H. PECK SUBDIVISION, AUSTIN, TRAVIS COUNTY, TEXAS.




VICINITY MAP
NOT TO SCALE

NOTES:

1. THE COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, NAD83 (96 CORS) DATUM.
2. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF AN OWNERSHIP AND EASEMENT REPORT.
3. REFERENCE TO THE OUTLOT OF DIVISION "O" SHOWN HEREON ARE FROM THE "TOPOGRAPHICAL MAP OF THE GOVERNMENT TRACT ADJOINING THE CITY OF AUSITN", DATED JANUARY, 1840, ON FILE WITH THE GENERAL LAND OFFICE OF THE STATE OF TEXAS.

LEGEND

- ⊙ 1/2" IRON ROD FOUND WITH CAP
- 1/2" IRON ROD SET WITH CAP "MCGRAY MCGRAY"
- ▲ MAG NAIL FOUND
- 1/2" IRON ROD FOUND (EXCEPT AS NOTED)
- △ CALCULATED POINT
- (XXX) RECORD INFORMATION
- N.T.S. NOT TO SCALE
- P.O.B. POINT OF BEGINNING
- P.R.T.C. PLAT RECORDS TRAVIS COUNTY
- R.P.R.T.C. REAL PROPERTY RECORDS TRAVIS COUNTY
- O.P.R.T.C. OFFICIAL PUBLIC RECORDS TRAVIS COUNTY



Chris Conrad


12/10/15

CHRIS CONRAD, REG. PROF. LAND SURVEYOR NO. 5623 DATE
 Note: This copy of this plat is not valid unless an original signature through an original seal appears on its face. There is a description to accompany this plat.

PAGE 4 OF 4
 SURVEYED BY: ISSUED: 12/10/15

McGRAY & McGRAY
LAND SURVEYORS, INC.


3301 HANCOCK DRIVE #6
 AUSTIN, TEXAS 78731
 (512) 451-8591



ZONING

EXHIBIT B

Case#: C14-2016-0051



This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

This product has been produced by the Planning and Zoning Department for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.



Created: 4/28/2016