

RULE NO.: R161-21.01

NOTICE OF RULE ADOPTION

ADOPTION DATE: 3/25/21

By: Richard Mendoza, Director
Public Works Department

The Director of the Department of Public Works has adopted the following rule. Notice of the proposed rule was posted on January 14, 2021. Public comment on the proposed rule was solicited in the January 14, 2021 notice. This notice is issued under Chapter 1-2 of the City Code. The adoption of a rule may be appealed to the City Manager in accordance with Section 1-2-10 of the City Code as explained below.

A copy of the complete text of the adopted rule is attached to this notice.

EFFECTIVE DATE OF ADOPTED RULE

A rule adopted by this notice is effective on March 25, 2021.

TEXT OF ADOPTED RULE

R161-21.01: Notice of Adoption to Sections 101S, 102S, & 641S in the Standard Specification Manual contains no changes from the proposed rule.

101S: Adding limitation to lump sum payments given before final payment to decrease risk of overpayment of services.

102S: Adding limitation to lump sum payments given before final payment to decrease risk of overpayment of services.

641S: Adding inclusion of traffic control costs unless specified in 803S, as well as, changing unit bid price type from 'linear foot' to 'each'.

SUMMARY OF COMMENTS

The Department of Public Works did not receive comments regarding Rule R161-21.01.

AUTHORITY FOR ADOPTION OF RULE

The authority and procedure for adoption of a rule to assist in the implementation, administration, or enforcement of a provision of the City Code is provided in Chapter 1-2 of the City Code. The authority to regulate construction is established in Section 25-6-267 and Section 25-6-268 of the City Code

APPEAL OF ADOPTED RULE TO CITY MANAGER

A person may appeal the adoption of a rule to the City Manager. **AN APPEAL MUST BE FILED WITH THE CITY CLERK NOT LATER THAN THE 30TH DAY AFTER THE DATE THIS NOTICE OF RULE ADOPTION IS POSTED. THE POSTING DATE IS NOTED ON THE FIRST PAGE OF THIS NOTICE.** If the 30th day is a Saturday, Sunday, or official city holiday, an appeal may be filed on the next day which is not a Saturday, Sunday, or official city holiday.

An adopted rule may be appealed by filing a written statement with the City Clerk. A person who appeals a rule must (1) provide the person's name, mailing address, and telephone number; (2) identify the rule being appealed; and (3) include a statement of specific reasons why the rule should be modified or withdrawn.

Notice that an appeal was filed and will be posted by the city clerk. A copy of the appeal will be provided to the City Council. An adopted rule will not be enforced pending the City Manager's decision. The City Manager may affirm, modify, or withdraw an adopted rule. If the City Manager does not act on an appeal on or before the 60th day after the date the notice of rule adoption is posted, the rule is withdrawn. Notice of the City Manager's decision on an appeal will be posted by the city clerk and provided to the City Council.

On or before the 16th day after the city clerk posts notice of the City Manager's decision, the City Manager may reconsider the decision on an appeal. Not later than the 31st day after giving written notice of an intent to reconsider, the City manager shall make a decision.

CERTIFICATION BY CITY ATTORNEY


By signing this Notice of Rule Adoption R161-21.01, the City Attorney certifies that the City Attorney has reviewed the rule and finds that adoption of the rule is a valid exercise of the Director's administrative authority.

REVIEWED AND APPROVED



Richard Mendoza, Director
Department

Date: March 19, 2021



Anne L. Morgan
City Attorney

Date: March 22, 2021

ITEM NO. 101S - PREPARING RIGHT OF WAY 1-4-11

101S.1 - Description

This item shall govern the preparation of the right of way for construction operations by removal and disposal of all obstructions from the right of way and from designated easements, where removal of such obstructions is not otherwise indicated as a separate pay item.

Such obstructions shall be considered to include, but not be limited to, remains of houses not completely removed by others, foundations, floor slabs, concrete, brick, lumber, plaster, cisterns, water wells, septic tanks and drain fields, basements; abandoned utility pipes, conduits, underground service station tanks, fences, retaining walls, outhouses, shacks and all other debris.

This item shall also include, but not be limited to, the removal of trees, stumps, roots, bushes, shrubs, curb and gutter, driveways, paved parking areas, miscellaneous stone, brick, sidewalks, drainage structures, manholes, inlets, abandoned railroad tracks, scrap iron, and all rubbish and debris whether above or below ground. Care should be taken to identify and protect existing infrastructure.

This specification is applicable for projects or work involving either inch-pound or SI units. Within the text the inch-pound units are given preference followed by SI units shown within parentheses.

101S.2 - Submittals

The submittal requirements of this specification item may include:

- A. A permit when utility adjustments are made in the right-of-way, and
- B. A plan for removal and deposition of all non-salvageable materials and debris.

101S.3 - Construction Methods

Prior to commencement of this work, all required erosion controls and tree protection measures indicated on the Drawings shall be in place. The existing utilities shall be located and protected as specified in the Standard Contract Documents, Section 00700, "General Conditions" and/or as specified on the Drawings. A permit shall be required when utility adjustments are to be made in preparation for construction in the right-of-way, as specified in Section 5.2.0 of the City of Austin Utilities Criteria Manual.

Areas within the construction limits shall be cleared of all obstructions, abandoned structures, and other items as defined above. All vegetation, except trees or shrubs indicated for preservation, shall also be removed. Trees and shrubs, which are scheduled for preservation, shall be carefully trimmed as directed and shall be protected from scarring, barking or other injuries during construction operations in accordance with Item No. 610S, "Preservation of Trees and Other Vegetation". All exposed cuts over 2 inches (50 millimeters) in diameter, exposed ends of pruned limbs or scarred bark shall be treated with an approved asphalt material within 24 hours of the pruning or injury.

Construction equipment shall not be operated nor construction materials stockpiled under the canopies of trees, unless otherwise indicated on the Drawings and/or specified in the Contract Documents. Excavation or embankment materials shall not be placed within the drip line of trees until tree wells are constructed.

Culverts, storm sewers, manholes and inlets shall be removed in proper sequence for maintenance of traffic and drainage.

Unless otherwise indicated on the Drawings and/or Contract Documents, all underground obstructions, stumps and roots shall be removed to the following depths:

1. In areas to receive 6 inches (150 mm) or more embankment, a minimum of 12 inches (300 mm) below natural ground.
2. In areas to receive less than 6 inches (150 mm) of embankment, a minimum of 18 inches (450 mm) below the lower elevation of embankment, structure or excavation.
3. In areas to be excavated a minimum of 18 inches (450 mm) below the lower elevation of the embankment, structure or excavation.
4. In all other areas, a minimum of 12 inches (300 mm) below natural ground.

Holes remaining after removal of all obstructions, objectionable material, trees, stumps, etc. shall be backfilled with select embankment material and compacted by approved methods.

When a utility in service conflicts with the construction, it shall be modified as specified in the Standard Contract Documents, Section 00700, "General Conditions" and/or as specified on the Drawings.

Where an abandoned underground piped utility is found, it shall be cut and plugged with 6 inches (150 mm) of concrete (in accordance with Specification Item 403, "Concrete for Structures") brick and mortar (in accordance with Specification Item 506S, "Manholes") or a precast stopper grouted in place.

Material to be removed will be designated as salvageable or non-salvageable by the Engineer or designated representative prior to removal from the construction site by the Contractor. All material, which is located within the public right of way and is declared by the Engineer as salvageable, will remain the property of the City of Austin and will be stored at the site or loaded on city trucks as directed by the Engineer. All non-salvageable materials and debris shall become the property of the Contractor and shall be removed from the site and deposited at a permitted disposal site.

101S.4 - Measurement

The preparation of right of way for new construction, when included in the contract as a pay item, will be measured by the acre (hectare: 1 hectare equals 2.471 acres), 100 foot (100 feet equals 30.5 meters) stations or lump sum, regardless of the width of the right of way.

Measurement for payment will be made only on areas indicated and classified as "Preparing Right of Way."

101S.5 - Payment

The work and material presented herein will not be paid for directly, but shall be included in the unit price bid for the item of construction in which this item is used unless specified as a separate pay item in the contract bid form. When included for payment, it shall be paid for at the contract bid price for "Preparing Right of Way." This price shall include full compensation for work herein specified, including the furnishing of all materials, equipment, tools, labor and incidentals necessary to complete the work.

When payment is made under the Lump Sum pay item the total payment of this Item shall not exceed 5% of the original contract amount until final payment. Any remainder will be paid as part of final payment.

Payment, when included as a contract pay item, will be made under one of the following:

Pay Item No. 101S-A:	Preparing Right of Way -	Per Acre.
Pay Item No. 101S-B:	Preparing Right of Way -	Per 100 foot Station.
Pay Item No. 101S-C:	Preparing Right of Way -	Per Lump Sum.

End

<u>SPECIFIC CROSS REFERENCE MATERIALS</u>	
<u>Specification 101S, "PREPARING RIGHT-OF-WAY"</u>	
<u>City of Austin Standard Contract Documents</u>	
<u>Designation</u>	<u>Description</u>
00700	General Conditions
<u>City of Austin Utilities Criteria Manual</u>	
<u>Designation</u>	<u>Description</u>
Section 5.2.0	Permit for Excavation in the Public Right-of-Way
<u>City of Austin Standard Specifications</u>	
<u>Designation</u>	<u>Description</u>
Item No. 110S	Street Excavation
Item No. 111S	Excavation
Item No. 120S	Channel Excavation
Item No. 132S	Embankment
Item No. 403	Concrete for Structures
Item No. 506S	Manholes

Item No. 610S	Preservation of Trees and Other Vegetation
---------------	--

<u>RELATED CROSS REFERENCE MATERIALS</u>	
<u>Specification 101S, "PREPARING RIGHT-OF-WAY"</u>	
<u>City of Austin Standard Contract Documents</u>	
<u>Designation</u>	<u>Description</u>
01500	Temporary Facilities
01550	Public Safety and Convenience
<u>The Code of the City of Austin, Code of Ordinances, Volume 1</u>	
<u>Designation</u>	<u>Description</u>
Article 14-11-181	Permit Required
Article 14-11-189	Conditions for Permit Issuance
Article 14-11-190	Permit Term
<u>City of Austin Standard Specifications</u>	
<u>Designation</u>	<u>Description</u>
Item No. 102S	Clearing and Grubbing

Item No. 104S	Removing Portland Cement Concrete
Item No. 201S	Subgrade Preparation
Item No. 203	Lime Treatment for Materials In Place
Item No. 204S	Portland Cement Treatment for Materials In Place
Item No. 230S	Rolling (Flat Wheel)
Item No. 232S	Rolling (Pneumatic Tire)
Item No. 234S	Rolling (Tamping)
Item No. 236S	Rolling (Proof)
Item No. 602S	Sodding for Erosion Control
Item No. 604S	Seeding for Erosion Control
Item No. 622S	Diversion Dike
Item No. 628S	Sediment Containment Dikes
Item No. 642S	Silt Fence

City of Austin Standard Details

<u>Designation</u>	<u>Description</u>
610S-1	Tree Protection Fence Locations
610S-2	Tree Protection Fence, Type B Chainlink
610S-3	Tree Protection Fence, Type B Wood
610S-4	Tree Protection Fence, Modified Type A

610S-5	Tree Protection Fence, Modified Type B
621S-1	Diversion
622S-1	Diversion Dike
624S-1	Earth Outlet Sediment Trap
625S-1	Grade Stabilization Structure
627S-1	Grass Lined Swale
627S-2	Grass Lined Swale With Stone Center
628S	Triangular Sediment Filter Dike
628S-1	Hay Bale Dike
629S-1	Brush Berm
630S-1	Interceptor Dike
631S-1	Interceptor Swale
632S-1	Storm Inlet Sediment Trap
633S-1	Landgrading
634S-1	Level Spreader
635S-1	Perimeter Dike
636S-1	Perimeter Swale
637S-1	Pipe Slope Drain (Flexible)
637S-2	Pipe Slope Drain (Flexible)
638S-1	Pipe Outlet Sediment Trap

639S-1	Rock Berm
641S-1	Stabilized Construction Entrance
642S-1	Silt Fence
643S-1	Stone Outlet Structure
644S-1	Stone Outlet Sediment Trap
<u>Texas Department of Transportation: Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges</u>	
<u>Designation</u>	<u>Description</u>
Item No. 100	Preparing Right of Way
Item No. 110	Excavation
Item No. 112	Subgrade Widening
Item No. 132	Embankment
Item No. 150	Blading
Item No. 158	Specialized Excavation Work
Item No. 160	Furnishing and Placing Topsoil
Item No. 164	Seeding for Erosion Control
<u>Texas Department of Transportation: Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges</u>	
<u>Designation</u>	<u>Description</u>

Item No. 204	Sprinkling
Item No. 210	Rolling (Flat Wheel)
Item No. 211	Rolling (Tamping)
Item No. 213	Rolling (Pneumatic Tire)
Item No. 260	Lime Treatment for Materials Used as Subgrade (Road Mixed)
Item No. 265	Lime-Fly Ash (LFA) Treatment for Materials Used as Subgrade
<u>Texas Department of Transportation: Manual of Testing Procedures</u>	
<u>Designation</u>	<u>Description</u>
Tex-103-E	Determination of Moisture Content of Soil Materials
Tex-104-E	Determination of Liquid Limit of Soils
Tex-105-E	Determination of Plastic Limit of Soils
Tex-106-E	Method of Calculating the Plasticity Index of Soils
Tex-114-E	Laboratory Compaction Characteristics and Moisture-Density Relationship of Subgrade & Embankment Soil
Tex-115-E	Field Method for Determination of In-Place Density of Soils and Base Materials

ITEM NO. 102S - CLEARING AND GRUBBING 8-20-07

102S.1 - Description

This item shall govern the removal and disposal of all trees, stumps, brush, roots, shrubs, vegetation, logs, rubbish and other objectionable material.

This specification is applicable for projects or work involving either inch-pound or SI units. Within the text the inch-pound units are given preference followed by SI units shown within parentheses.

102S.2 - Submittals

The submittal requirements of this specification item may include:

- A. A permit when utility adjustments are made in the right-of-way, and
- B. A plan for removal and deposition of all clearing and grubbing materials and debris.

102S.3 - Construction Methods

Prior to commencement of this work, all required erosion control and tree protection measures indicated on the Drawings shall be in place. The existing utilities shall be located and protected as specified in the Standard Contract Documents, Section 00700, "General Conditions" and/or indicated on the Drawings. A permit shall be required when utility adjustments are to be made in preparation for construction in the right-of-way, as specified in Section 5.2.0 of the City of Austin Utilities Criteria Manual.

Areas within the construction limits indicated on the Drawings shall be cleared of all trees, stumps, brush, etc., as defined in section 102S.1; except trees or shrubs scheduled for preservation which shall be carefully trimmed as directed, in accordance with Item No. 610S, " Preservation of Trees and Other Vegetation" and shall be protected from scarring, barking or other injuries during construction operations. All exposed cuts over 2 inches (50 millimeters) in diameter, exposed ends of pruned limbs or scarred bark shall be treated with an approved asphalt material within 24 hours of the pruning or injury.

Construction equipment shall not be operated nor construction materials stockpiled under the canopies of trees, unless otherwise indicated on the Drawings and/or specified in the Contract Documents. Excavation or embankment materials shall not be placed within the drip line of trees until tree wells are constructed.

Within the construction limits or areas indicated, all obstructions, stumps, roots, vegetation, abandoned structures, rubbish and objectionable material shall be removed to the following depths:

1. In areas to receive 6 inches (150 mm) or more embankment, a minimum of 12 inches (300 mm) below natural ground.
2. In areas to receive embankment less than 6 inches (150 mm), a minimum of 18 inches (450 mm) below the lower elevation of embankment, structure or excavation.
3. In areas to be excavated a minimum of 18 inches (450 mm) below the lower elevation of the embankment, structure or excavation.
4. In all other areas a minimum of 12 inches (300 mm) below natural ground.

Holes remaining after removal of all obstructions, objectionable material, trees, stumps, etc. shall be backfilled with select embankment material and compacted by approved methods. All cleared and grubbed material shall be disposed of in a manner satisfactory to the Engineer or designated representative. Unless otherwise provided, all materials as described above shall become the property of the Contractor and removed from the site and disposed of at a permitted disposal site.

Burning materials at the site shall conform to Standard Contract Document Section 01550, "Public Safety and Convenience".

102S.4 - Measurement

"Clearing and Grubbing", when included in the contract as a pay item, will be measured by the acre (hectare: 1 hectare is equal to 2.471 acres), 100 foot (100 feet is equal to 30.5 meters) stations or lump sum, regardless of the width of the right of way.

102S.5 - Payment

The work and materials presented herein will not be paid for directly, but shall be included in the unit price bid for the item of construction in which this item is used, unless specified as a separate pay item in the contract bid form. When included for payment, it shall be paid for at the unit bid price for "Clearing and Grubbing". This price shall include full compensation for all work herein specified, including the furnishing of all materials, equipment, tools, labor and incidentals necessary to complete the Work.

When payment is made under the Lump Sum pay item, the total payment of this item shall not exceed 5% of the original contract amount until final payment. Any remainder will be paid at final payment.

Payment, when included as a contract pay items, will be made under one of the following:

Pay Item No. 102S-A:	Clearing and Grubbing	Per Acre.
Pay Item No. 102S-B:	Clearing and Grubbing	Per 100 foot Station.
Pay Item No. 102S-C:	Clearing and Grubbing	Lump Sum.

End

<u>SPECIFIC CROSS REFERENCE MATERIALS</u>	
Specification Item 102S, "CLEARING AND GRUBBING"	
<u>City of Austin Standard Contract Documents</u>	
<u>Designation</u>	<u>Description</u>
00700	General Conditions
01550	Public Safety and Convenience

<u>City of Austin Utilities Criteria Manual</u>	
<u>Designation</u>	<u>Description</u>
Section 5.2.0	Permit for Excavation in the Public Right-of-Way
<u>City of Austin Standard Specifications</u>	
<u>Designation</u>	<u>Description</u>
Item No. 110S	Street Excavation
Item No. 111S	Excavation
Item No. 610S	Preservation of Trees and Other Vegetation

<u>RELATED CROSS REFERENCE MATERIALS</u>	
Specification 102S, "CLEARING AND GRUBBING"	
<u>The Code of the City of Austin, Code of Ordinances, Volume 1</u>	
<u>Designation</u>	<u>Description</u>
Article 15-12-166	Permit Required
Article 15-12-173	Conditions for Permit Issuance

Article 15-12-174	Permit Term
<u>City of Austin Standard Contract Documents</u>	
<u>Designation</u>	<u>Description</u>
01500	Temporary Facilities
<u>City of Austin Standard Specifications</u>	
<u>Designation</u>	<u>Description</u>
Item No. 101S	Preparing Right of Way
Item No. 104S	Removing Portland Cement Concrete
Item No. 120S	Channel Excavation
Item No. 132S	Embankment
Item No. 201S	Subgrade Preparation
Item No. 203	Lime Treatment for Materials In Place
Item No. 204S	Portland Cement Treatment for Materials In Place
Item No. 230S	Rolling (Flat Wheel)
Item No. 232S	Rolling (Pneumatic Tire)
Item No. 234S	Rolling (Tamping)
Item No. 236S	Rolling (Proof)
Item No. 602S	Sodding for Erosion Control

Item No. 604S	Seeding for Erosion Control
Item No. 622S	Diversion Dike
Item No. 628S	Sediment Containment Dikes
Item No. 642S	Silt Fence
<u>City of Austin Standard Details</u>	
<u>Designation</u>	<u>Description</u>
610S-1	Tree Protection Fence Locations
610S-2	Tree Protection Fence, Type B Chainlink
610S-3	Tree Protection Fence, Type B Wood
610S-4	Tree Protection Fence, Modified Type A
610S-5	Tree Protection Fence, Modified Type B
621S-1	Diversion
622S-1	Diversion Dike
624S-1	Earth Outlet Sediment Trap
625S-1	Grade Stabilization Structure
627S-1	Grass Lined Swale
627S-2	Grass Lined Swale With Stone Center
628S	Triangular Sediment Filter Dike
628S-1	Hay Bale Dike

629S-1	Brush Berm
630S-1	Interceptor Dike
631S-1	Interceptor Swale
632S-1	Storm Inlet Sediment Trap
633S-1	Landgrading
634S-1	Level Spreader
635S-1	Perimeter Dike
636S-1	Perimeter Swale
637S-1	Pipe Slope Drain (Flexible)
637S-2	Pipe Slope Drain (Flexible)
638S-1	Pipe Outlet Sediment Trap
639S-1	Rock Berm
641S-1	Stabilized Construction Entrance
642S-1	Silt Fence
643S-1	Stone Outlet Structure
644S-1	Stone Outlet Sediment Trap
<u>Texas Department of Transportation: Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges</u>	
<u>Designation</u>	<u>Description</u>
Item No. 100	Preparing Right of Way

Item No. 110	Excavation
Item No. 112	Subgrade Widening
Item No. 132	Embankment
Item No. 150	Blading
Item No. 158	Specialized Excavation Work
Item No. 160	Furnishing and Placing Topsoil
Item No. 164	Seeding for Erosion Control
Item No. 204	Sprinkling
Item No. 210	Rolling (Flat Wheel)
Item No. 211	Rolling (Tamping)
Item No. 213	Rolling (Pneumatic Tire)
Item No. 260	Lime Treatment for Materials Used as Subgrade (Road Mixed)
Item No. 265	Lime-Fly Ash (LFA) Treatment for Materials Used as Subgrade
<u>Texas Department of Transportation: Manual of Testing Procedures</u>	
<u>Designation</u>	<u>Description</u>
Tex-103-E	Determination of Moisture Content of Soil Materials
Tex-105-E	Determination of Plastic Limit of Soils
Tex-106-E	Method of Calculating the Plasticity Index of Soils
Tex-114-E	Laboratory Compaction Characteristics and Moisture Density Relationship of Subgrade & Embankment Soil
Tex-115-E	Field Method for Determination of In-Place Density of Soils and Base Materials

--	--

ITEM NO. 641S - STABILIZED CONSTRUCTION ENTRANCE 6-21-07

641S.1 - Description

This item governs the construction of a stabilized pad of crushed stone located at any point where traffic will be entering or leaving a construction site to or from a public right of way, street, alley, sidewalk or parking area. The removal of the stabilized pad of crushed stone shall also be included in the item. The purpose of a stabilized construction entrance is to reduce or eliminate the tracking or deposition of sediment onto public right of way (Environmental Criteria Manual Section 1.4.2.N.4).

This specification is applicable for projects or work involving either inch-pound or SI units. Within the text, the inch-pound units are given preference followed by SI units shown within parentheses.

641S.2 - Submittals

The submittal requirements for this specification item shall include:

- A. Source, type and gradation of rock
- B. Drainage technique (i.e. drainage swale or entrance grading) proposed to prevent runoff from exiting the construction site.

641S.3 - Materials

Aggregate for construction shall conform to the following gradation:

Table 1: Aggregate Gradation Chart (TEX 401-A, % Retained per sieve)		
US 8 inch (SI 200 mm)	US 5 inch (SI 125 mm)	US 2 inch (SI 50 mm)
0	90-100	100

641S.4 - Construction Methods

All trees, brush, stumps, obstructions and other objectionable material shall be removed and disposed of in a manner that will not interfere with the excavation and construction of the entrance as indicated on the Drawings or as presented in Standard Details No. 641S-1. The entrance shall not drain onto the public right of way or shall not allow surface water runoff to exit the construction site.

When necessary, vehicle wheels shall be cleaned to remove sediment prior to entrance onto public right of way. When vehicle washing is required, it shall be done on an area stabilized with crushed stone, which drains into an approved sediment trap or sediment basin. All sediment shall be prevented from entering any storm drain, ditch or watercourse through use of sand bags, gravel, boards, silt fence (Standard Specification Item No 642S) or other methods approved by the Engineer or designated representative.

The entrance shall be maintained in a condition that will prevent tracking or disposition of sediment onto public right of way. This restriction may require periodic top dressing with additional stone as conditions

demand, as well as the repair and/or cleanout of any measures used to trap sediment. All sediment that is spilled, dropped, washed or tracked onto public right of way must be removed immediately.

641S.5 - Measurement

Acceptable work performed as prescribed in this item will be measured by unit of each stabilized construction entrance installed.

641S.6 - Payment

The work performed and materials furnished and measured as provided under "Measurement" will be paid for at the unit bid price per ~~linear foot of~~ each "Stabilized Construction Entrance". The price shall include full compensation for furnishing, hauling and placing all materials, labor, tools, equipment and incidentals necessary to complete the work including inspecting, repairing, replacing and relocating existing fencing, removal of silt and removal and disposal of all materials at the completion of construction. The price shall include full compensation for furnishing, installing, maintaining, moving, and removing any traffic control devices required by the installation of a stabilized construction entrance.

Payment, when included as a contract pay item, will be made under:

Pay Item No. 641S:	Stabilized Construction Entrance	Per Each.
---------------------------	----------------------------------	-----------

End

<u>SPECIFIC CROSS REFERENCE MATERIALS</u>	
<u>Specification 641S, "Stabilized Construction Entrance (SCE)"</u>	
<u>City of Austin Environmental Criteria Manual</u>	
<u>Designation</u>	<u>Description</u>
Section 1.4.2.N.4	Stabilized Construction Entrance "Design Criteria"
<u>City of Austin Standard Details</u>	

<u>Designation</u>	<u>Description</u>
Number 641S-1	Stabilized Construction Entrance
<u>City of Austin Standard Specifications</u>	
<u>Designation</u>	<u>Description</u>
Item No. 642S	Silt Fence (SF)

<u>RELATED CROSS REFERENCE MATERIALS</u>	
<u>Specification 641S, "Stabilized Construction Entrance (SCE)"</u>	
<u>City of Austin Environmental Criteria Manual</u>	
<u>Designation</u>	<u>Description</u>
Section 1.4.2.J	Sandbag Berm
Figure 1-11	Sand Bag Berm
Section 1.4.2.G	Silt Fence
<u>City of Austin Standard Specifications</u>	
<u>Designation</u>	<u>Description</u>
Item No. 101S	Preparing Right of Way
Item No. 102S	Clearing and Grubbing

Item No. 111S	Excavation
Item No. 120S	Channel Excavation
Item No. 401S	Structural Excavation and Backfill
Item No. 610S	Preservation of Trees and Other Vegetation
<u>Texas Department of Transportation: Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges</u>	
<u>Designation</u>	<u>Description</u>
Item No. 100	Preparing Right of Way
Item No. 110	Excavation
Item No. 132	Embankment
Item No. 158	Specialized Excavation Work
Item No. 168	Vegetative Watering