B-09 1 of 53

SITE PLAN REVIEW SHEET ENVIRONMENTAL VARIANCE REQUEST ONLY

CASE: SP-2021-0021D PLANNING COMMISSION DATE: July 20th, 2021

PROJECT NAME: 3800 Island Way

APPLICANT: Chris Hester **AGENT:** Janis Smith Consulting, LLC

(Janis Smith, PE)

ADDRESS OF SITE: 3800 Island Way

COUNTY: Travis **AREA:** .5 acres

WATERSHED: Lake Austin **JURISDICTION:** Full Purpose

EXISTING ZONING: LA, SF-3

PROPOSED DEVELOPMENT:

The applicant is proposing to construct a boat dock.

DESCRIPTION OF VARIANCES:

The applicant is requesting to vary from LDC 25-8-281(C)(2)(b) to allow construction of a boat dock within a 150-foot Critical Environmental Feature (CEF).

STAFF RECOMMENDATION:

The findings of fact have been met, and staff recommends approval for construction within a 150 foot Critical Environmental Feature (CEF) with the following conditions:

1) All construction activities to be completed by barge.

ENVIRONMENTAL BOARD ACTION:

July 7th, **2021**: With a 8-0 vote, the Environmental Commission recommends support of the request for a variance from LDC 25-8-281(C)(2)(b) with the following conditions;

1) All construction activities to be completed by barge.


WATERSHED PROTECTION STAFF: Eric Brown **PHONE:** 978-1539

Eric.Brown@austintexas.gov

CASE MANAGER: Clarissa Davis **PHONE:** 974-1423

Clarissa.Davis@austintexas.gov

B-09 2 of 53



ITEM FOR DEVELOPMENT COMMITTEE MEETING

MEETING June 16, 2021

DATE:

NAME & NUMBER OF 3800 Island Way PROJECT: SP-2021-0021D

NAME OF APPLICANT OR Janis Smith, PE

ORGANIZATION: Janis Smith Consulting, LLC

LOCATION: 3800 Island Way

Austin, Texas 78746

COUNCIL DISTRICT: Council District #10

ENVIRONMENTAL Eric Brown Senior Environmental Scientist

REVIEW STAFF Watershed Protection Department

Eric.Brown@austintexas.gov

WATERSHED: Lake Austin Watershed, Water Supply Rural Classification,

Drinking Water Protection Zone

REQUEST: Request to vary from LDC 25-8-281(C)(2)(B) to allow construction

within 150-feet of Critical Environmental Feature (Rimrock)

Staff recommends this variance having determined the findings of

RECOMMENDATION: facts have been met.

RECOMMENDED1. Construction to be completed by barge.

B-09 3 of 53


Staff Findings of Fact

B-09 4 of 53

3800 ISLAND WAY— BOAT DOCK REPLACEMENT

SP- 2021-0021D

Eric Brown
Hydrogeologic Reviewer
Watershed Protection Department



B-09 6 of 53

PROPERTY DATA

- LAKE AUSTIN WATERSHED
- WATER SUPPLY RURAL CLASSIFICATION
- CRITICAL ENVIRONMENTAL FEATURES ON SITE
- COUNCIL DISTRICT 10





B-09 9 of 53

BACKGROUND

- BOAT DOCK ON THE LAKE
- NEAR RIMROCK
- BRINGING EXISTING NON-COMPLIANT DOCK INTO COMPLIANCE
- ADDING SECOND STORY

B-09 10 of 53

CODE REFERENCE

•TITLE 25 – LAND DEVELOPMENT CODE, CHAPTER 25-8-281(C)(2)(B).

B-09 11 of 53

VARIANCE REQUEST

REQUEST TO VARY FROM LDC 25-8-281(C)(2)(B) TO ALLOW CONSTRUCTION WITHIN 150-FOOT OF CRITICAL ENVIRONMENTAL FEATURE (CEF) BUFFERS.





B-09 14 of 53

VARIANCE RECOMMENDATION

FINDING OF FACTS HAVE BEEN MET.

STAFF RECOMMENDS THE APPROVAL OF THIS VARIANCE WITH THE CONDITION THAT ALL CONSTRUCTION BE COMPLETED BY BARGE.

B-09 15 of 53

QUESTIONS?



B-09 16 of 53



Watershed Protection Department Staff Recommendations Concerning Required Findings

Project Name &

Case Number: 3800 ISLAND WAY Boat Dock Replacement SP- 2021-0021D

Ordinance Standard: Watershed Protection Ordinance

Variance Request: LDC 25-8-281(C)(2)(b) - To allow construction within 150 feet of a

Rimrock Critical Environmental Features (CEF)

Include an explanation with each applicable finding of fact.

A. Land Use Commission variance determinations from Chapter 25-8-41 of the City Code:

1. The requirement will deprive the applicant of a privilege available to owners of similarly situated property with approximately contemporaneous development subject to similar code requirements.

Yes. A variance from 25-8-281(C)(2)(b) allowing for construction of a boat dock, shoreline access, and stabilization, has been granted for similarly situated properties with approximately contemporaneous development subject to similar code.

2. The variance:

 Is not necessitated by the scale, layout, construction method, or other design decision made by the applicant, unless the design decision provides greater overall environmental protection than is achievable without the variance;

Yes. No disturbance of the rimrock CEF is proposed, all proposed construction activities are to occur downgradient of the rimrock CEFs, and construction is to occur from the lakeside by barge. The proposed construction to be performed from a barge provides greater overall environmental protection. Additionally, the applicant is providing wetland plantings that will reduce shoreline erosion and sediment-laden surface runoff from discharging into the lake.

b) Is the minimum deviation from the code requirement necessary to allow a reasonable use of the property;

B-09 17 of 53

Yes. The variance is the minimum deviation from the code requirement to allow for a reasonable use of the property. The code requires a 150-foot critical environmental feature buffer. This buffer is not being reduced. The scope of the variance is limited to allowing construction activities to occur within a critical environmental feature buffer temporarily and only for the proposed boat dock replacement.

c) Does not create a significant probability of harmful environmental consequences.

Yes. The variance does not create significant harmful environmental consequences. The construction of the boat dock from barge will not disturb the rimrock critical environmental feature. The applicant is providing wetland plantings that will reduce erosion and sediment-laden surface runoff from discharging into the lake.

3. Development with the variance will result in water quality that is at least equal to the water quality achievable without the variance.

Yes, the variance will result in water quality that is at least equal to the water quality achievable without the variance. The construction activities will not disturb the rimrock critical environmental features. The proposed wetland planting along the shoreline will reduce soil erosion along the shoreline and provide filtration of sediment-laden runoff from upgradient areas, thereby providing water quality that is at least equal to or greater than the water quality achievable without the variance.

Staff Recommendation: Staff recommends the variance as the Findings of Fact have been met, with the staff recommended condition that all construction be completed by barge.

- B. The Land Use Commission may grant a variance from a requirement of Section 25-8-422 (Water Supply Suburban Water Quality Transition Zone), Section 25-8-452 (Water Supply Rural Water Quality Transition Zone), Section 25-8-482 (Barton Springs Zone Water Quality Transition Zone), Section 25-8-368 (Restrictions on Development Impacting Lake Austin, Lady Bird Lake, and Lake Walter E. Long), or Article 7, Division 1 (Critical Water Quality Zone Restrictions), after determining that:
 - 1. The criteria for granting a variance in Subsection (A) are met;

Yes / No N/A

2. The requirement for which a variance is requested prevents a reasonable, economic use of the entire property;

Yes / No N/A

3. The variance is the minimum deviation from the code requirement necessary to allow a reasonable, economic use of the entire property.

Yes / No N/A

Hydrogeologic Reviewer (WPD)

Eric Brown

Date: 06-02-2021

Deputy Environmental Officer (WPD)

Liz Johnston

Date: 06-02-2021

B-09 19 of 53

Applicant Form and Findings of Fact



ENVIRONMENTAL COMMISSION VARIANCE APPLICATION FORM

PROJECT DESCRIPTION						
Applicant Contact Information						
Name of Applicant	Chris Hester					
Street Address	3800B Island Cove					
City State ZIP Code	Austin, TX 78746					
Work Phone	512-692-7175					
E-Mail Address	chris.hester@cttlp.com					
Variance Case Informat	ion					
Case Name	3800 Island Cove					
Case Number	SP-2021-0021D					
Address or Location	3800 Island Cove					
Environmental Reviewer Name	Pamela Abee-Taulli					
Environmental Resource Management Reviewer Name						
Applicable Ordinance	LDC 25-8-281(C)(2)(b)					
Watershed Name	Lake Austin					
Watershed Classification	☐ Urban ☐ Suburban X Water Supply Suburban					

Edwards Aquifer Recharge Zone		echarge	X Barton Springs Segment☐ Northern Edwards Segment☐ Not in Edwards Aquifer Zones			
	ds Aquifer outing Zone		☐ Yes X No			
	ce to Nearest ed Waterway		The boat dock is in Lake Austin.			
	and Waste W to be provid		NA			
Reques	st		The variance request is as follo	ows (Cite code references:		
			To allow construction in a ri	mrock CEF buffer.		
Imperviou	is cover		Existing	Proposed		
square foo	otage:					
acreage:						
percentag	ge:					
property (slope range, elevation range, summary of vegetation / trees, summary of the geology, CWQZ, WQTZ, CEFs, floodplain, heritage trees, any other potable or outstanding			Two-thirds of the site is in the an aerial photo of the site. It tersection of Westlake Drive at grandfathered dock and according home. It was originally dement featuring five duplex horeting dock moors three boats at as was common in the 80s. Let traffic is heavy with the assentation of the dock makes it put waves roll underneath. This high two slips oriented perpendicts.	A homesite on the shoreline of Lake lake underwater. Attachment 1 is located about two miles northwest and Redbud Trail. The site contains sess, and two rimrocks which border veloped in the 80s as part of a mesites, four of which are lakefront. and is oriented parallel to the On this very busy portion of the ociated high energy wave action. Perilous to get into and out of the project proposes to reconstruct the cular to the shoreline so that it's safe		

This project proposes to demolish an existing, grandfathered, dock and construct a new dock in the same location but oriented perpendicular to the shoreline. The existing and proposed dock location is about 120 LF from the nearest rimrock CEF and falls within the 150 ft. CEF setback required by Code. Please see Attachment 2 for the Proposed Conditions Site Plan Sheet. Attachment 3 contains the Environmental Resource Inventory.

FINDINGS OF FACT

As required in LDC Section 25-8-41, in order to grant a variance the Land Use Commission must make the following findings of fact:

Include an explanation with each applicable finding of fact.

Project:

Ordinance:

- A. Land Use Commission variance determinations from Chapter 25-8-41 of the City Code:
 - 1. The requirement will deprive the applicant of a privilege available to owners of similarly situated property with approximately contemporaneous development subject to similar code requirements.

Yes / No Please see Attachment 4, Basis of Determination.

- 2. The variance:
 - a) Is not necessitated by the scale, layout, construction method, or other design decision made by the applicant, unless the design decision provides greater overall environmental protection than is achievable without the variance;
 - **Yes** / No Please see Attachment 4, Basis of Determination.
 - b) Is the minimum deviation from the code requirement necessary to allow a reasonable use of the property;
 - **Yes** / No Please see Attachment 4, Basis of Determination.
 - c) Does not create a significant probability of harmful environmental consequences.
 - **Yes** / No Please see Attachment 4, Basis of Determination.

23 of 53

3. Development with the variance will result in water quality that is at least equal to the water quality achievable without the variance.

Yes / No Please see Attachment 4, Basis of Determination.

B. Additional Land Use Commission variance determinations for a requirement of Section 25-8-422 (Water Quality Transition Zone), Section 25-8-452 (Water Quality Transition Zone), Article 7, Division 1 (Critical Water Quality Zone Restrictions), or Section 25-8-368 (Restrictions on Development Impacting Lake Austin, Lady Bird Lake, and Lake Walter E. Long):

Not Applicable

1. The criteria for granting a variance in Subsection (A) are met;

Yes / No [provide summary of justification for determination]

2. The requirement for which a variance is requested prevents a reasonable, economic use of the entire property;

Yes / No [provide summary of justification for determination]

3. The variance is the minimum deviation from the code requirement necessary to allow a reasonable, economic use of the entire property.


Yes / No [provide summary of justification for determination]

^{**}Variance approval requires all above affirmative findings.

Exhibits for Commission Variance


- Aerial photos of the site
- Site photos
- Aerial photos of the vicinity
- Context Map—A map illustrating the subject property in relation to developments in the vicinity to include nearby major streets and waterways
- Topographic Map A topographic map is recommended if a significant grade change on the subject site exists or if there is a significant difference in grade in relation to adjacent properties.
- For cut/fill variances, a plan sheet showing areas and depth of cut/fill with topographic elevations.
- o Site plan showing existing conditions if development exists currently on the property
- Proposed Site Plan- full size electronic or at least legible 11x17 showing proposed development, include tree survey if required as part of site or subdivision plan
- Environmental Map A map that shows pertinent features including Floodplain, CWQZ,
 WQTZ, CEFs, Setbacks, Recharge Zone, etc.
- An Environmental Resource Inventory pursuant to ECM 1.3.0 (if required by 25-8-121)
- Applicant's variance request letter

ATTACHMENT 1 AERIAL SITE PHOTO



ATTACHMENT 2 PROPOSED CONDITIONS SITE PLAN SHEET

EXISTING SHORELINE LENGTH = 41.6' ALLOWABLE DOCK WIDTH = 23.6' (GRANDFATHERED STRUCTURES) PROPOSED DOCK WIDTH = 22.0' PROPOSED DOCK DEPTH = 35.8' DOCK FOOTPRINT = 658.7 SF



609S RESTORATION

- ALL DISTURBED AREAS WITHIN THE SHORELINE SETBACK SHALL BE REVEGETATED
- PURSUANT TO 609S SPECIFICATIONS, USING 609S SEEDING OR PLANTING AREA OF IMPACT IS APPROXIMATELY 79 SF
- PLANTING CRITERIA RECOMMENDS 1 NATIVE SHADE TREE AND 1 NATIVE UNDERSTORY TREE/500 SF OF DISTURBED AREA
- 79 SF/500 SF = 1 SHADE TREE AND 1 UNDERSTORY TREE
- AND 1 NATIVE SHRUB/100 SF
- 79 SF/100 = 1 SHRUBS WETLAND MITIGATION
- 24 SF AT 2 FT CENTERS IN A TRIANGULAR PATTERN YIELDS 7 PLANTS.

PLANTING MITIGATION NOTES

- ALL PLANTS TO BE SOURCED WITHIN A 200 MILE RADIUS OF AUSTIN.
- FOLLOW ALL GUIDELINES FOUND IN THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL, REFERENCE CODE SECTIONS ECM 1.13.0, ECM 1.10.4(D), & ITEM NO. 609S AS
- ALL PLANTS TO BE INSTALLED AT A MAXIMUM OF 3FT ON CENTERS.

SHORELINE	E MITIGATION PLANTIN	G SCHEDULE
PLANT NAME	NUMBER OF PLANTS	TYPE OF MITIGATION
Bald Cypress (Taxodium distichum)**	1	Floodplain
Mexican Plum (Prunus mexicana)**	1	Floodplain
White Mistflower (Ageratina havanensis))^ 1	Floodplain
Blue Flag Iris (Iris fulva or virginica)	2	Wetland
Big Muhly (Muhlenbergia lindheimeri)	2	Wetland
Cardinal flower (Lobelia cardinalis)	3	Wetland
· · · · · · · · · · · · · · · · · · ·	OTAL = 10 PLANTS	

- 2" caliper trees ^ Native shrub with low water needs
- Alternative native and adapted species may be substituted with the same quantity of another species and plant planting location maybe modified as approved by the PDR Environmental reviewer, ERM Wetland
- Biologist or ERM Landscape Architect.
- TOTAL 609S SHRUBS REQUIRED = 1 SHRUB. 1 SHRUB IS PROPOSED TOTAL 609S UNDERSTORY TREES REQUIRED = 1 TREE. 1 UNDERSTORY TREE IS PROPOSED
- TOTAL 609S SHADE TREES REQUIRED = 1 TREE. 1 SHADE TREE IS PROPOSED
- TOTAL 609S PLANTS REQUIRED = 3 PLANTS. 3 PLANTS PROPOSED WETLAND PLANTS REQUIRED = 7 PLANTS. 8 PLANTS PROPOSED

EXISTING = **PROPOSED ACCESS** 9.5' 25.0' _____ 22.00 ____ SECOND FLOOR PLAN VIEW FIRST FLOOR PLAN VIEW 1" = 10' 1" = 10' GRANDFATHERED HORIZONTAL PROPOSED AND VERTICAL FOOTPRINT SEE SHEET 4 FOR EXISTING PLAN/ELEVATION VIEWS NAVIGATION LIGHTS EL. 509.3' EL. 505.8' DOCK EL. = 494.8' EL. = 494.8' APPROX. WSEL = EXISTING = PROPOSED BOTTOM OF BEAM BULKHEAD ELEV = 493.8' LAKESIDE ELEVATION T.O.W. = 493.8' SIDE ELEVATION 1" = 10' 1" = 10'

THE PROPOSED BOAT DOCK MUST COMPLY WITH ALL REQUIREMENTS OF LDC 25-2-1174 ("STRUCTURAL REQUIREMENTS"), AND MUST COMPLY WITH CHAPTER 25-12, ARTICLE 1 (UNIFORM BUILDING CODE) AND THE BUILDING CRITERIA MANUAL.

NOTES:


- 1. ALL WORK SHALL OCCUR WITHIN THE LIMITS OF CONSTRUCTION AS SHOWN ON THE PLAN. ALL MATERIALS WILL BE TRANSPORTED TO THE SITE FROM WATER. ALL CONSTRUCTION ACTIVITY, INCLUDING STAGING AND SPOIL STORAGE, WILL BE COMPLETED BY WATER.
- 2. SHORELINE IMPROVEMENTS, INCLUDING GANGWAY ACCESS, ARE AUTHORIZED WITH THIS SITE PLAN.
- CONTAINERS OF HAZARDOUS MATERIALS, FUEL, OIL, HERBICIDES, INSECTICIDES, FERTILIZERS, OR OTHER POLLUTANTS WILL NOT BE STORED ON DOCKS EXTENDING INTO OR ABOVE LAKE AUSTIN.
- 4. FOR LA ZONING, PERMANENT IMPROVEMENTS ARE PROHIBITED WITHIN THE SHORELINE SETBACK AREA, EXCEPT FOR RETAINING WALLS, PIERS, WHARVES, BOATHOUSES, MARINAS, OR A DRIVE TO ACCESS THE STRUCTURES [LDC 25-2-551
- NO WATER OR WASTEWATER UTILITIES ARE PROPOSED WITH THIS DEVELOPMENT. DOCK SHALL BE AT LEAST 66% OPEN.
- PILINGS SHALL BE 6-5/8" DIAMETER STEEL PIPE.

RESISTANT DESIGN AND CONSTRUCTION.

8. THE PROJECT SITE IS WITHIN THE CITY OF AUSTIN FULL PURPOSE BOUNDARIES.

ATTENTION INSPECTOR NOTES:

- 1. COMPLIANCE WITH BUILDING CODE REQUIRED AND IS TO BE REVIEWED FOR COMPLIANCE DURING BUILDING CODE REVIEW.
- 2. FOR THE BUILDING PERMIT, A SIGNED AND SEALED LETTER SHALL BE SUBMITTED TO THE CITY OF AUSTIN, PER THE LAND DEVELOPMENT CODE, 25-12-3 1612.4, CERTIFYING THAT THE STRUCTURE IS IN ACCORDANCE WITH ASCE 24, FLOOD
- ENVIRONMENTAL INSPECTOR HAS THE AUTHORITY TO ADD AND/OR MODIFY EROSION/SEDIMENTATION CONTROLS ON SITE TO KEEP PROJECT IN COMPLIANCE WITH THE CITY OF AUSTIN RULES AND REGULATIONS.



sulting, Con Smith

Janis

3800

DESIGNED: JJS APPROVED: SCALE: AS SHOWN

DATE: JANUARY 11, 202

SHEET

PROPOSED PLAN/ELEVATION VIEWS

ATTACHMENT 3 **ENVIRONMENTAL RESOURCE INVENTORY**

B-09 30 of 53



City of Austin – Environmental Resource Inventory (ERI) 3800 Island Way Travis County, Texas

November 16, 2020, revised March 22, 2021

By: DESCO Environmental Consultants, LP 26902 Nichols Sawmill Road Magnolia, Texas 77355

Environmental Resource Inventory

For the City of Austin
Related to LDC 25-8-121, City Code 30-5-121, ECM 1.3.0 & 1.10.0

The ERI is required for projects that meet one or more of the criteria listed in LDC 25-8-121(A), City Code 30-5-121(A). 1. SITE/PROJECT NAME: 3800 Island Way - Lot E 2. COUNTY APPRAISAL DISTRICT PROPERTY ID (#'s): ⁵⁴¹²⁹⁶ 3. ADDRESS/LOCATION OF PROJECT: 3800 Island Way, Lot E, Austin, TX 78746 Austin-Travis Lakes 4. WATERSHED: 5. THIS SITE IS WITHIN THE (Check all that apply) Edwards Aguifer 1500 ft Verification Zone* □YES □No Note: If the property is over the Edwards Aquifer Recharge zone, the Hydrogeologic Report and karst surveys must be completed and signed by a Professional Geoscientist Licensed in the State of Texas. 6. DOES THIS PROJECT PROPOSE FLOODPLAIN MODIFICATION?......□YES** ☒NO If yes, then check all that apply: (1) The floodplain modifications proposed are necessary to protect the public health and safety; (2) The floodplain modifications proposed would provide a significant, demonstrable environmental benefit, as determined by a functional assessment of floodplain health as prescribed by the Environmental Criteria Manual (ECM), or (3) The floodplain modifications proposed are necessary for development allowed in the critical water quality zone under LDC 25-8-261 or 25-8-262, City Code 30-5-261 or 30-5-262. (4) The floodplain modifications proposed are outside of the Critical Water Quality Zone in an area determined to be in poor or fair condition by a functional assessment of floodplain health. ** If yes, then a functional assessment must be completed and attached to the ERI (see ECM 1.7 and Appendix X for forms and guidance) unless conditions 1 or 3 above apply. 7. IF THE SITE IS WITHIN AN URBAN OR SUBURBAN WATERSHED, DOES THIS PROJECT PROPOSE A UTILITY LINE PARALLEL TO AND WITHIN THE CRITICAL WATER QUALITY ZONE? □YES*** □NO ***If yes, then riparian restoration is required by LDC 25-8-261(E) or City Code 30-5-261(E) and a functional assessment must be completed and attached to the ERI (see ECM1.5 and Appendix X for forms and guidance). 8. There is a total of ³ (#'s) Critical Environmental Feature(s)(CEFs) on or within 150 feet of the project site. If CEF(s) are present, attach a detailed **DESCRIPTION** of the CEF(s), color PHOTOGRAPHS, the CEF WORKSHEET and provide DESCRIPTIONS of the proposed CEF buffer(s) and/or wetland mitigation. Provide the number of each type of CEFs on or within 150 feet of the site (Please provide the number of CEFs):

B-09 32 of 53

0	_ (#'s) Spring(s)/Seep(s)	0	_(#'s) Point Recharge Feature(s)	0	_(#'s) Bluff(s)
2	(#'s) Canyon Rimrock(s)	1	_ (#'s) Wetland(s)		

Note: Standard buffers for CEFs are 150 feet, with a maximum of 300 feet for point recharge features. Except for wetlands, if the standard buffer is <u>not provided</u>, you must provide a written request for an administrative variance from LDC 25-8-281(C)(1) and provide written findings of fact to support your request. Request forms for administrative variances from requirements stated in LDC 25-8-281 are available from Watershed Protection Department.

9. The following site maps are attached at the end of this report (Check all that apply and provide):

All ERI reports must include:

- Site Specific Geologic Map with 2-ft Topography
- **☒** Historic Aerial Photo of the Site

Only if present on site (Maps can be combined):

- ☑ Edwards Aquifer Recharge Zone with the 1500-ft Verification Zone (Only if site is over or within 1500 feet the recharge zone)
- □ Edwards Aquifer Contributing Zone
- □ Water Quality Transition Zone (WQTZ)
- □ Critical Water Quality Zone (CWQZ)
- 10. **HYDROGEOLOGIC REPORT** Provide a description of site soils, topography, and site specific geology below (Attach additional sheets if needed):

Surface Soils on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups*. If there is more than one soil unit on the project site, show each soil unit on the site soils map.

Soil Series Unit Names, Infiltration Characteristics & Thickness				
Soil Series Unit Name & Subgroup**	Group*	Thickness (feet)		
Eckrant soils and Urban land, 5 to 18 percent slopes	D	1		
Eckrant soils and Urban land, 18 to 40 percent slopes	D	1		

*Soil Hydrologic Groups Definitions (Abbreviated)

- A. Soils having a <u>high infiltration</u> rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a <u>slow infiltration</u> rate when thoroughly wetted.
- D. Soils having a <u>very slow</u> <u>infiltration</u> rate when thoroughly wetted.
- **Subgroup Classification See <u>Classification of Soil Series</u> Table in County Soil Survey.

WPD ERM ERI-2014-01 Page 2 of 6

B-09 33 of 53

Description of Site Topography and Drainage (Attach additional sheets if needed):

As verified from the City of Austin GIS, two rimrocks are present on the far northwestern portion of the property (Figure 4). Rimrock 1 averages approximately 25 feet tall and Rimrock 2 averages approximately 12 feet tall. At the bottom of Rimrock 1, the property is very gently sloped from northwest to southeast towards Lake Austin (Colorado River) in the Austin-Travis Lake watershed, downstream of Lake Travis. The average slope of the property at the bottom of the rimrocks is approximately 1%. Island Way borders the property to the northeast and similar properties border the property to the north, east, and west. A main residence with covered parking and two story boat slips are located on the property. A rock retaining wall is installed along the entire shoreline which extends 2' above the water line. One wetland (wetland 1) was identified by City of Austin staff adjacent to the boat dock consisting of landscaped umbrella sedge (Cyperus involucratus). Other than the two rimrocks and one wetland, no additional CEFs were observed on or adjacent to the property.

List surface geologic units below:

Geologic Units Exposed at Surface					
Group	Formation	Member			
Trinity	Glen Rose Formation	Cretaceous			
Comanche Peak	Fredericksburg Group	Comanchean			

Brief description of site geology (Attach additional sheets if needed):

Glen Rose Formation - Limestone, dolomite, and marl in alternating resistant and recessive beds forming stair step topography; limestone, alphantic to fine grained, hard to soft and marly, light grey to yellowish grey; dolomite, fine grained, porous, yellowish brown; marine megafossils include steinkems, rudistids oysters, andechinoids; upper part relatively thinner bedded, more dolomitic and less fossiliferous than lower part, thickness about 220 feet.

Fredericksburg Group - Limestone,dolomite,chert, marl. Limestone nodular, aphanitic, marly, gray, yellow, white, pink; dolomite, fine grained, gray; chert, in thin layers and nodules; marl locally gypsiferous, gray. Abundant Exogyra texana some beds made almost entirely of Gryphaea sp., exposed thickness 50 feet. Edwards Limestone, limestone, dolostone, and chert 60-350 feet thick. Comanche Peak Limestone 80 feet thick. Keys Valley Marl, soft, white as much as 50 feet thick. Cedar Park Limestone similar to Comanche Peak Ls (fine to very fine grained, fairly hard, nodular, light gray, burrowed). Bee Cave Marl soft, white Exogyra texana abundant, thickness 25-40 feet.

Wells - Identify all recorded	and unrecorded wells	s on site (tes	st holes, r	monitoring,	water, oi	il,
unplugged, capped and/or a	ibandoned wells, etc.)	:				

0)	
There are		_(#) wells present on the project site and the locations are shown and labeled
()	(#'s)The wells are not in use and have been properly abandoned.
_		(#'s)The wells are not in use and will be properly abandoned.
C)	(#'s)The wells are in use and comply with 16 TAC Chapter 76.
There are)	(#'s) wells that are off-site and within 150 feet of this site.

WPD ERM ERI-2014-01 Page 3 of 6

B-09 34 of 53

11. **THE VEGETATION REPORT** – Provide the information requested below:

Brief description of site plant	communities	(Attach additional	sheets if needed):
---------------------------------	-------------	--------------------	--------------------

luding live oak (Quercus virginiana), ceda vigata). The remaining property is landso	ne vicinity of the rimrocks contains native veget ar elm (Ulmus crassifolia), and sugarberry (Cel caped with St. Augustine grass (Stenotaphrum d cover. Umbrella sedge (wetland 1) was obser
There is woodland community on sit	e
If yes, list the dominant species belo	
Woodla	and species
Common Name	Scientific Name
There is grassland/prairie/savanna of lf yes, list the dominant species belo	on site□YES ■ NO <i>(Check one</i> ow:
Grassland/prair	rie/savanna species
Common Name	
Common Name	Scientific Name

WPD ERM ERI-2014-01 Page 4 of 6

B-09 35 of 53

Hydrophytic plant species					
Common Name	Scientific Name	Wetland Indicator Status			
Umbrella Sedge	Cyperus involucratus	FACW			
half feet above natural gra ☐YES ☑ NO (Check one).	with a diameter of at least eight inchade level has been completed on the	e site.			
12. WASTEWATER REPORT –	Provide the information requested be	elow.			
On-site system(s)City of Austin Cent					
Note: All sites that receive water or wastewater service from the Austin Water Utility must comply with City Code Chapter 15-12 and wells must be registered with the City of Austin					
The site sewage collection system is designed and will be constructed to in accordance to all State, County and City standard specifications. Types No (Check one).					
Calculations of the size of the drainfield or wastewater irrigation area(s) are attached at the end of this report or shown on the site plan.					
Wastewater lines are proposed within the Critical Water Quality Zone? ☐YES ■ NO (Check one). If yes, then provide justification below:					

WPD ERM ERI-2014-01 Page 5 of 6

Is the project site is over the Edwards YES NO (Check one).	Aquifer?
If yes, then describe the wastewater of level and effects on receiving watercomes	disposal systems proposed for the site, its treatment urses or the Edwards Aquifer.
All wastewater will be disposed of into the	City of Austin Centralized sewage collection system.
13. One (1) hard copy and one (1) electron provided. Date(s) ERI Field Assessment was performed.	ic copy of the completed assessment have been
and the bound of the second of the beautiful	Date(s)
My signature certifies that to the best of my reflect all information requested.	knowledge, the responses on this form accurately
Chris Little	281-252-9799
Print Name	Telephone clittle@descoenv.com
Signature	Email Address
DESCO Environmental Consultants, LP	November 16, 2020, revised March 22, 2021
Name of Company	Date

For project sites within the Edwards Aquifer Recharge Zone, my signature and seal also certifies that I am a licensed Professional Geoscientist in the State of Texas as defined by ECM 1.12.3(A).

Richard W Griffin Soil Science #3244

37 of 53

City of Austin Environmental Resource Inventory - Critical Environmental Feature Worksheet

1	B-09														
Project Name 3800 Island Way_Lot E. Austin, TX 78746 See Project Name Site Visit Data See See Project Name Site Visit Date November 11, 2020 See See					Springs Est.	Discharge	cfs								
Project Address; 3800 Island Way_Lot E. Austin, TX 78746 Environmental Resource Inventory Date: November 11, 2020 Environmental Resource Inventory Date: November 11, 2020 EATUNE LONGITUDE FEATUNE					EATURE	ONS	Trend								
Project Address; 3800 Island Way_Lot E. Austin, TX 78746 Environmental Resource Inventory Date: November 11, 2020 Environmental Resource Inventory Date: November 11, 2020 EATUNE LONGITUDE FEATUNE					RGE FI	1ENSI	Z								Ī
Project Address; 3800 Island Way_Lot E. Austin, TX 78746 Environmental Resource Inventory Date: November 11, 2020 Environmental Resource Inventory Date: November 11, 2020 EATUNE LONGITUDE FEATUNE				com	ECHA										
Project Name: 3800 Island Way_Lot E, Austin, TX 78746 Forest Name: 3800 Island Way_Lot E, Austin, TX 78746 Forest Name		66		coenv	H		\vdash								ŀ
Project Name: 3800 Island Way_Lot E, Austin, TX 78746 Forest Name: 3800 Island Way_Lot E, Austin, TX 78746 Forest Name	Chris Little	281-252-97	Chris Little	clittle@desc	K/RITEF	SIONS (ft)	Avg Height	25	12						
Project Name: 3800 Island Way_Lot E, Austin, TX 78746 Forest Name: 3800 Island Way_Lot E, Austin, TX 78746 Forest Name	ntact Name:	Phone Number:	Prepared By:	Email Address:	RIMBOO	DIMENS	Length	281	201						
Project Name 3800 Island Way. Lot E, Austin, TX 78746 6	Primary Cor					IONS (ft)	٨			9					
Project Name: 3800 Island Way - Lot E					WFT	DIMENS	×			4					
Project Name: 3800 Island Way. Lot E, Austin, TX 78746	2	9	7	8		rs)	notation								
Project Name: 3800 Island Way - Lot E					FEATURE LATITUD	(WGS 1984 in Mete	coordinate	616683.10775	616669.53960	616713.78004					
			:020	:020, revised March 22, 2021) L	DE rs)	notation								
	ay - Lot E				FEATURE LONGITUI	(WGS 1984 in Mete	coordinate	3352749.40460	3352741.16413	3352726.14027					
	3800 Island Wa	3800 Island Wa	November 11,	November 16,		FEATURE ID	(eg S-1)	Rimrock 1	Rimrock 2	Wetland 1					
- 0 m 4 m	Project Name:	Project Address:	Site Visit Date:	Environmental Resource Inventory Date:	FEATURE TVPE	{Wetland,Rimrock, Bluffs,Recharge	Feature, Spring}	Rimrock	Rimrock	Wetland					
	-	2	3	4		6									

Please state t precision and	Method	GPS Surveyed Other	
		For a spring or seep, locate the source of groundwater that feeds a pool or stream.	₹ 5
		For wetlands, locate the approximate centroid of the feature and the estimated area.	
City of Austin Use Only CASE NUMBER:		For rimrock, locate the midpoint of the segment that describes the feature.	

the method of coordinate data collection and the approximate d accuracy of the points and the unit of measurement.

×
שרכתו מר
ואוברווסמ

sub-meter	meter
GPS	Surveyed

□ >1 meter □ Professional Geologists apply seal below

B-09 38 of 53

List of Attachments for the Environmental Resource Inventory Form

Figure 1: Site Specific Geological Map with 2' Topography

Figure 2: Historical Aerial Imagery


Figure 3: Site Soils Map

Figure 4: Critical Environmental Features and Well Locations

Figure 5: CWQZ and Fully Developed Floodplain

Figure 6: 3800 Island Way - ERI Site Photos











Figure 2: Historical Aerial Imagery 3800 Island Way

 ${\it Travis\ County,\ Texas}$

1:855

DESCO





Travis County, Texas

Map Base: 2020 CAP Area 3in NC Imagery from TNRIS Map Datum: NAD 1983 UTM Zone 14N, meters Map Date: November 12, 2020



DESCO



Legend

Figure 4: Critical Environmental Features and Well Locations

3800 Island Way

Parcel of Interest (CoA)

Wetland

Travis County, Texas

Map Base: 2020 CAP Area 3in NC Imagery from TNRIS
Map Datum: NAD 1983 UTM Zone 14N, meters
Map Date: March 22, 2021

Wetland 150' Buffer



Map Base: 2020 CAP Area 3in NC Imagery from TNRIS Map Datum: NAD 1983 UTM Zone 14N, meters Map Date: November 12, 2020

Edwards Aquifer Recharge Zones (CoA)

B-09 44 of 53



Figure 6. 3800 Island Way ERI Site Photos

Photo 1: Front of the property adjacent to Island Way. Photo was taken from Island Way facing southwest.



Photo 2: Back (northwest) of the property adjacent to Rimrock 1 (Figure 4). Photo was taken from Island Way facing west.

B-09 45 of 53



Photo 3: Backyard of property facing Lake Austin to the southeast.



Photo 4: Rock retaining wall 2' above the water line with no wetlands along the shoreline.

Photo was taken from the boat dock facing west.

B-09 46 of 53



Photo 5: View of back of residence taken from second floor of boat dock facing northwest.



Photo 6: Rimrock 1 (Figure 4) extends southwest and northeast of property. Photo was taken from Island Way facing southwest toward the property.

B-09 47 of 53



Photo 7: Wetland 1 adjacent to the boat dock consisting of landscaped umbrella sedge (*Carex involucratus*). Photo was taken by City of Austin staff from the boat dock facing northwest toward the residence.

ATTACHMENT 4 BASIS OF DETERMINATION FOR THE FINDINGS OF FACT

B-09 49 of 53

A. 1. The requirement will deprive the applicant of a privilege available to owners of similarly situated property with approximately contemporaneous development subject to similar code requirements.

- YES. The Environmental Commission has recommended every variance application pertaining to LDC 25-8-281(C)(2)(b) for the past six years except one which included a tram.
- 2. The variance:
- a. Is not necessitated by the scale, layout, construction method, or other design decision made by the applicant, unless the design decision provides greater overall environmental protection than is achievable without the variance;
- YES. The entire shoreline is within the CEF setback. The proposed dock will be constructed in the same location as the existing dock.
- b. Is the minimum deviation from the code requirement necessary to allow reasonable use of the property;
- YES. A dock cannot be constructed on the lot without obtaining this variance.
- c. Does not create a significant probability of harmful environmental consequences.
- YES. Post construction, all disturbed areas will be revegetated per the COA 609S specification. Floating silt screen will contain sediment caused by any lakebed disturbance.
- 3. Development with the variance will result in water quality that is at least equal to the water quality achievable without the variance.
- YES. Mitigation plantings will be added to the site which should result in a greater water quality from overland flow entering the lake. The floating silt screen should contain any sediment caused by the boat dock construction.
- B. 1. The criteria for granting a variance in Subsection (A) are met:
 - YES. Please see answers to A (1), (2), and (3).
 - 2. The requirement for which a variance is requested prevents a reasonable, economic use of the entirety of the property;
 - YES. The existing dock, built in the 1980s, is oriented parallel to the shoreline on a very busy section of the lake. The wave action makes for a perilous entry and exit to/from the boat. Reconstructing the dock to a safe alignment perpendicular to the shoreline, as is typical today, requires this variance. Blocking the

B-09 50 of 53

construction of a safe dock "prevents a reasonable, economic use of the entirety of the property".

3. The variance is the minimum deviation from the code requirement necessary to allow a reasonable, economic use of the entire property;

YES. The construction is limited to replacing an unsafe dock with a safe dock. No further work is proposed; so this project "is the minimum deviation from the code". Denying the owner the ability to construct a safe dock on the lakefront lot would prevent "a reasonable economic use of the entirety of the property".

B-09 51 of 53

Applicant Exhibits

B-09 52 of 53



ENVIRONMENTAL COMMISSION MOTION 20210616 004a

Date: June 16, 2021

Subject: 3800 Island Way SP-2021-0021D

Motion by: Kevin Ramberg Seconded by: Perry Bedford

RATIONALE:

WHEREAS, the Environmental Commission recognizes the applicant is requesting a variance from LDC 25-8-281(C)(2)(B) to allow construction within 150-feet of Critical Environmental Feature (Rimrock).

WHEREAS, the Environmental Commission recognizes that staff recommends this variance (with one condition) having determined the required Findings of Fact have been met.

THEREFORE, the Environmental Commission recommends the variance request with the following:

Staff Condition:

1. That the construction be completed by barge.

VOTE 8-0

For: Bedford, Creel, Thompson, Brimer, Ramberg, Barrett Bixler, Bristol, and Guerrero


Against: None Abstain: None Recuse: None Absent: Coyne

Approved By:


Linda Guerrero, Environmental Commission Chair

hindatt querrero

53 of 53 B-09







Base Map

CASE#: SP-2021-0021D

LOCATION: 3800 ISLAND WAY UNIT BD

This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

