



COA FM-812 Landfill Gas Collection and Control System

System History and Efforts to
Enhance Landfill Gas Collection

Initial System Installation

- Installed in 1998 by Ecogas
 - 55-well system in Areas A and B
 - Above grade headers and laterals
 - Temporary blower/flare system
 - Operated only to preserve gas tax credits
 - System dormant until 2003

System Upgrades

- Upgrades implemented in late 2003 included
 - Addition of one well (for total of 56)
 - Burying of headers and laterals
 - Installation of permanent blower/flare system
 - Addition of heat exchange system for energy
- System operation commenced December 2003



COA FM-812 Landfill - Blower/Flare Station

Gas from landfill enters blower/flare station (BFS) through pipe from right. Passes through knockout to blower and then on to flare.



COA FM-812 Landfill - Blower/Flare Station

Single blower at BFS. Gas enters through top pipe, then exits pipe on left with 90° elbow. Flow meter on pipe at left edge of photo.



COA FM-812 Landfill - Blower/Flare Station

Candlestick flare with shroud surrounding it.

Vacuum System Installation

- Installed system to address gas migration
 - 11-wells placed on about 50-foot spacing
 - Intended to create vacuum barrier to migration
 - Equipped with own condensate sump
 - Connected to existing collection system
 - Installation complete in mid 2010



COA FM-812 Landfill Well

Single well with condensate sump to left.

Wellhead Improvements

- Modified wellhead connections to reduce air infiltration
 - Old connection consisted of “hard” coupling
 - New connection utilized 4 x 6 Fernco coupling
 - Wellhead upgrade completed in late 2011

Landfill Gas-to-Energy Targeted Feasibility Study

- Purposes of study included
 - Identifying options for enhancing gas collection
 - Estimating recoverable gas through modeling
 - Determining electrical generation potential
 - Identifying end-users for energy produced
 - Addressing possible greenhouse gas credits
- Overall goal was assessing viability of landfill gas-to-energy (LFGE) project

Phase I Improvements

- Consisted of basic improvements that could be implemented quickly including
 - Repair of damaged lateral pipe to well
 - Replacement of existing wellheads
 - Installation of separate vacuum source for vacuum curtain wells
- Improvements completed by mid 2013



COA FM-812 Landfill - Well Improvements

Old-style wellhead with butterfly valve.



COA FM-812 Landfill - Well Improvements

New-style QED wellhead with fine-tuning valve.

Phase II Improvements

- Consists of improvements that are more costly and time consuming including
 - Submittal of permit modification to install wells
 - Installation of 4 new wells
 - Replacement of 4 existing wells
 - Connection of 3 existing leachate collection risers to collection system
 - Installation of pneumatic pumps in 5 wells and 4 condensate sumps

Potential Impact of Phase II Improvements

- Increased gas volume being recovered
- Improved gas quality from new wells
- Decreased emissions of gases to air
- More reliable condensate sump operation