



# Meredith Street Storm Drain Improvements

Lake Austin Watershed – Alternative 1

## Alternative 1

### Summary

Includes rerouting a nearby storm drain system so that it connects to the proposed Meredith storm drain system with the outfall located at 1804 Rockmoor Ave.

### Pros

Alleviates flooding at 3605-3607 Meredith Street.

Eliminates second storm drain system west of the project area.

Eliminates drainage into the cave.

### Cons

Construction inside cave creates unforeseen challenges.

Discharge at private property requires new easements.

Adds two different drainage areas, increasing the pipe size at the outfall.

Affects more residents during construction.

### Estimated Cost

\$4 to \$5 million

