



Meredith Street Storm Drain Improvements

Lake Austin Watershed – Alternative 2

Alternative 2 Summary

Focuses on the immediate drainage issues and includes boring between the houses located at 1813 and 1815 Rockmoor Ave., as well as upgrading the existing pipe under Rockmoor Ave. between the intersection of Cherry Lane and the outfall at 1804 Rockmoor Ave.

Pros

Alleviates flooding at 3605-3607 Meredith Street, following the natural path of the runoff.

Avoids construction going against the natural path.

Cons

Construction in the cave area.

Proximity of bore to existing houses.

Estimated Cost

\$3 to \$4 million

