



Meredith Street Storm Drain Improvements

Lake Austin Watershed – Alternative 3

Alternative 3

Summary

This includes buying 3605 and 3607 Meredith St. and upgrading the existing pipe under Rockmoor Ave. between the intersection of Cherry Lane and the outfall at 1804 Rockmoor Ave. With alternative 3A, a detention pond would be constructed and there would be the bore in Alternative 2. With 3B, we would purchase 1813 and 1815 Rockmoor and convert the land to green space without a detention pond.

Pros

Alleviates flooding at 3605-3607 Meredith Street, following the natural path of the runoff.

Avoids construction going against the natural path.

Additional green space with option 3B

Cons

Construction in the cave area.

Proximity of the bore to houses.

Estimated Cost

\$5 to \$7 million



Alternative 3B - Drawing of Green Space

