CERTIFIED

CITY OF AUSTIN

BID TABULATION

PROJECT SPONSOR: PUBLIC WORKS
BID CERTIFICATION: JOHN HILBUN
CONTRACT REP: KITTY TUNNELL
PROJECT MANAGER: PETER DAVIS

BID OPENING DATE: 4/7/2011
TIME: 2:30 PM
LOCATION: ONE TEXAS CENTER
PRICE EXPIRATION: 90 CAL. DAYS
LIQUIDATED DAMAGES: $ 1500/CAL. DAY

PROJECT: EAST BOULDIN-ONE TEXAS CENTER WATER QUALITY RETROFITS
BID INVITATION NO: CLMC279
PROJECT NUMBER(S): 4850 6307 6115 ESTIMATE: $120,000.00

CIP ID NO.: 5282.039 DURATION: 60 CAL. DAYS
RESPONSES: 2

BIDDER(S):	MAC, INC.	AUSTIN ENGINEERING CO., INC.	
LOCATION:	AUSTIN	AUSTIN	
GUARANTEE: BB-Bid Bond CC-Cashiers Check CTC-Cert. Chk.	BB	BB	
ADDENDA ACKNOWLEDGED	0	0	

NO.	BID ITEM	QTY	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1	111S-A1	380	CY	EXCAVATION, INCLUDING OFFSITE DISPOSAL	$ 50.00	$ 19,000.00	$ 80.00	$ 30,400.00		$ -
2	111S-P1	150	LF	REMOVAL AND DISPOSAL OF PREVIOUSLY ABANDONED 20" DIAMETER CAST IRON WATER PIPE, INCLUDING OFFSITE DISPOSAL	$ 20.00	$ 3,000.00	$ 30.00	$ 4,500.00		$ -
3	130S-A	130	CY	CITY OF AUSTIN APPROVED BIO-FILTRATION MEDIA, CERTIFIED PER 2/24/2011 GUIDANCE, COMPLETE AND IN PLACE	$ 100.00	$ 13,000.00	$ 60.00	$ 7,800.00		$ -
4	206S-B	35	SY	FLEXIBLE STABILIZED BASE, 8 IN.	$ 50.00	$ 1,750.00	$ 150.00	$ 5,250.00		$ -
5	340AH	28	SY	CONCRETE PAVEMENT, 7 IN., (HIGH EARLY STRENGTH	$ 65.00	$ 1,820.00	$ 125.00	$ 3,500.00		$ -
6	340S-B	41	SY	HOT MIX ASPHALTIC CONCRETE PAVEMENT, 3 IN., TYPE D	$ 54.00	$ 2,214.00	$ 200.00	$ 8,200.00		$ -
7	430S-A	24	LF	CONCRETE CURB AND GUTTER (CURB AND GUTTER WORK INCLUDING EXCAVATION AND SUBGRADE PREPARATION.)	$ 50.00	$ 1,200.00	$ 65.00	$ 1,560.00		$ -
8	432SR-4	92	SF	REMOVE AND REPLACE EXISTING SIDEWALK, COMPLETE-IN-PLACE	$ 10.00	$ 920.00	$ 20.00	$ 1,840.00		$ -

CERTIFIED

BIDDER(S):					MAC, INC.		AUSTIN ENGINEERING CO., INC.			
NO.	BID ITEM	QTY	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
9	508S-A	96	LF	TRENCH DRAIN, INCLUDING FRAME AND GRATE, COMPLETE AND IN-PLACE	$ 50.00	$ 4,800.00	$ 350.00	$ 33,600.00		$ -
10	551-A1	95	LF	SOLID PVC PIPE, 6" DIA. (ALL DEPTHS), INCLUDING 17 CY FILTER MATERIAL (1 PART MULCH TO 9 PARTS CRUSHED LIMESTONE) LENGTH OF WYES AND CLEANOUTS, CONNECTION TO EXISTING INLET - COMPLETE AND IN PLACE	$ 50.00	$ 4,750.00	$ 35.00	$ 3,325.00		$ -
11	551-A2	96	LF	PERFORATED PVC PIPE, 6" DIA. (ALL DEPTHS), INCLUDING 19 CY FILTER MATERIAL (1 PART MULCH TO 9 PARTS CRUSHED LIMESTONE), LENGTH OF WYES AND CLEANOUTS - COMPLETE AND IN PLACE	$ 50.00	$ 4,800.00	$ 35.00	$ 3,360.00		$ -
12	591S-B1	15	CY	1-INCH DIA. GRAVEL MULCH 1-INCH THICKNESS, ROUNDED GRAVEL	$ 150.00	$ 2,250.00	$ 75.00	$ 1,125.00		$ -
13	591S-B2	20	SY	DRY RIPRAP, ROUNDED RIVER ROCK (COLORADO RAINBOW) 2"-6" DIAMETER	$ 150.00	$ 3,000.00	$ 60.00	$ 1,200.00		$ -
14	591S-D	8	SY	MORTARED ROCK RIPRAP, 3" THICK FLAT LIMESTONE ROCK	$ 50.00	$ 400.00	$ 200.00	$ 1,600.00		$ -
15	608S-1	20	EA	PLANTING TYPE "PLUGS" NATIVE SPECIES, PER PLANS, PLANTING TABLES AND DETAILS.	$ 25.00	$ 500.00	$ 25.00	$ 500.00		$ -
16	608S-1A	200	EA	PLANTING TYPE 4" CONTAINER NATIVE SPECIES, PER PLANS, PLANTING TABLES AND DETAILS	$ 5.00	$ 1,000.00	$ 25.00	$ 5,000.00		$ -
17	608S-1B	3,700	EA	PLANTING TYPE 1-GALLON NATIVE SPECIES, PER PLANS, PLANTING TABLES AND DETAILS	$ 11.00	$ 40,700.00	$ 25.00	$ 92,500.00		$ -
18	608S-1C	70	EA	PLANTING TYPE 5-GALLON NATIVE SPECIES, PER PLANS, PLANTING TABLES AND DETAILS	$ 20.00	$ 1,400.00	$ 30.00	$ 2,100.00		$ -
19	608S-1D	5	EA	PLANTING TYPE 15-GALLON PLANTS, PER PLANS, PLANTING TABLES AND DETAILS	$ 200.00	$ 1,000.00	$ 100.00	$ 500.00		$ -
20	608S-2P	1	LS	PERMANENT IRRIGATION SYSTEM, INCLUDING REMOVAL OF EXISTING IRRIGATION SYSTEM, FULL DESIGN SUBMITTALS FOR NEW SYSTEM BY REGISTERED LANDSCAPE ARCHITECT, AND INSTALLATION OF NEW SYSTEM, COMPLETE AND IN PLACE	$ 9,000.00	$ 9,000.00	$ 8,500.00	$ 8,500.00		$ -
21	608S-T1	11	EA	TRANSPLANTING, TREE, LESS THAN 4" DIAMETER	$ 300.00	$ 3,300.00	$ 2,100.00	$ 23,100.00		$ -
22	608S-T2	90	EA	TRANSPLANTING, CLUMP GRASS OR SHRUB	$ 25.00	$ 2,250.00	$ 300.00	$ 27,000.00		$ -

CERTIFIED

BIDDER(S):					MAC, INC.		AUSTIN ENGINEERING CO., INC.			
NO.	BID ITEM	QTY	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
23	609S-G	24	EA	EXTENDED LANDSCAPE MANAGEMENT, TWO-YEAR DURATION, PER EVENT	$ 300.00	$ 7,200.00	$ 1,200.00	$ 28,800.00		$ -
24	609S-S	200	SY	BUFFALO GRASS (609 VARIETY) SODDING	$ 7.00	$ 1,400.00	$ 6.00	$ 1,200.00		$ -
25	610S-A	380	LF	PROTECTIVE FENCING TYPE A (TREE PROTECTION) CHAIN LINK FENCE (TYPICAL APPLICATION-HIGH DAMAGE POTENTIAL)	$ 5.00	$ 1,900.00	$ 4.00	$ 1,520.00		$ -
26	610S-AP	2	EA	PROTECTIVE FENCING, WOODEN TREE PLANKING TRUNK PROTECTION, PER TREE	$ 100.00	$ 200.00	$ 250.00	$ 500.00		$ -
27	620S	135	SY	FILTER FABRIC	$ 25.00	$ 3,375.00	$ 3.00	$ 405.00		$ -
28	628S-C	30	LF	FILTER CURB INLET PROTECTION (EXISTING INLET)	$ 10.00	$ 300.00	$ 20.00	$ 600.00		$ -
29	640S1	210	SF	MORTARED ROCK WALL, 12" X 6" X 2" LIMESTONE	$ 40.00	$ 8,400.00	$ 35.00	$ 7,350.00		$ -
30	640S-2	255	SF	MORTARED ROCK WALL, 12" X 6" X 24" LIMESTONE, INCLUDING WATER BARRIER (DEEP ROOT WB 36/30 OR APPROVED EQUAL) AND SEALANT IF REQUIRED, COMPLETE AND IN PLACE	$ 50.00	$ 12,750.00	$ 45.00	$ 11,475.00		$ -
31	640S3	95	SF	MORTARED ROCK WALL, 8" X 6" X (12" - 24") LIMESTONE, SINGLE COURSE STONE EDGING USING EXISTING LIMESTONE SALVAGED FROM ONSITE	$ 20.00	$ 1,900.00	$ 35.00	$ 3,325.00		$ -
32	648S	310	LF	MULCH SOCK FOR EROSION CONTROL	$ 12.00	$ 3,720.00	$ 4.00	$ 1,240.00		$ -
33	700S-TM	1	LS	TOTAL MOBILIZATION PAYMENT	$ 15,000.00	$ 15,000.00	$ 12,000.00	$ 12,000.00		$ -
34	701-S	285	LF	FENCE (42" TALL, 2" X 2" WIRE PANEL FENCE WITH STEEL POSTS)	$ 15.00	$ 4,275.00	$ 6.00	$ 1,710.00		$ -
35	802S-B	1	EA	PROJECT SIGN	$ 500.00	$ 500.00	$ 800.00	$ 800.00		$ -
36	803S-MO	3	MO	BARRICADES, SIGNS, AND TRAFFIC HANDLING	$ 500.00	$ 1,500.00	$ 200.00	$ 600.00		$ -
37	824S	1	EA	RELOCATE EXISTING TRAFFIC SIGNS	$ 250.00	$ 250.00	$ 2,000.00	$ 2,000.00		$ -
				Mathematical errors found and corrected.						
				TOTAL BID:		$ 184,724.00		$ 339,985.00		$ -

TRUE COPY OF BID TABULATION AS RECEIVED
OR CORRECTED IN ACCORDANCE WITH
CONDITIONS GOVERNING PROPOSALS.

04/19/11

CONTRACT & LAND MANAGEMENT DEPARTMENT DATE
CONTRACT PROCUREMENT DIVISION, CITY OF AUSTIN, TX