

FOR NON- C.I.P. PROJECTS USE THIS BARRICADING SUMMARY TABLE

Streets

Street	Classification	Street From	Street To	Planned Improvements	Traffic Control Plan Sheet	Allowed Barricading Hours	Duration	Set Up	Comments
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Water Line and Meter Install	TC10	9am-4pm Mon-Fri; 7am-7pm Weekends	1 Week	Daily	
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Electrical Work	sheet 23	9am-4pm Mon-Fri; 7am-7pm Weekends	3 Days	Daily	**804s-2, sheet 2
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Storm Drain Installation	sheet 23	9am-4pm Mon-Fri; 7am-7pm Weekends	1 Week	Daily	**804s-2, sheet 2
Lewis Ln.	ASMP 1	40th St.	42nd St.	Wastewater Line, Manholes & Connections	sheet 23	7am-7pm Mon-Fri; 7am-7pm Weekends	3 Weeks	Daily	**804s-2, sheet 2
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Flat Work, Driveway & Sidewalk	TC11	9am-4pm Mon-Fri; 7am-7pm Weekends	2 Weeks	Intermediate-Term Stationary	**24 hr for concrete cure (1 day)
45th St.	ASMP 3	Burnet Rd.	Sinclair Ave.	Electric Manhole	TC12	9am-4pm Mon-Fri; 7am-7pm Weekends	1 Week	Daily	
Lewis Ln.	ASMP 1	40th St.	42nd St.	Deliveries, Concrete Pours	TC14	7am-7pm Mon-Fri; 7am-7pm Weekends	13 Months	Daily	
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Crane Install & or Removal	TC09	Friday 7pm -Sunday Midnight	3 Days	Intermediate-Term Stationary	
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Pedestrian Walkway	TC13	24/7	13 Months	Long-Term Stationary	

Intersections

Street Intersection	Classification	Planned Improvements	Traffic Control Plan Sheet	Allowed Barricading Hours	Duration	Set Up	Comments
40th St./Ramsey Ave.	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC14	9am-4pm Mon-Fri; 7am-7pm Weekends	1 Week	Daily	
40th St./Baily Ln.	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC15 & TC16	9am-4pm Mon-Fri; 7am-7pm Weekends	3 Days	Daily	
40th St./Medical Parkway	ASMP 2 / ASMP 2	Water, Wastewater, & Storm installation	TC17 & TC18	9am-4pm Mon-Fri; 7am-7pm Weekends	1 Week	Daily	
41st St./Lewis Ln	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC19 & TC20	9am-4pm Mon-Fri; 7am-7pm Weekends	3 Weeks	Daily	
42nd St./Lewis Ln.	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC21 & TC22	9am-4pm Mon-Fri; 7am-7pm Weekends	1 Day	Daily	

Daily: Closures are set up and removed the same day within the allowed barricading hours provided.

Intermediate-Term Stationary: Closures remain in place continuously for one to three days (or nighttime work lasting more than 1 hour).

Long-Term Stationary: Closures remain in place continuously for more than three days.

Mobile: The work zone is continuously moving and must not remain in a single location for more than 15 minutes.

****Comments:** Use this field to provide any additional details or clarification related to the selected work zone type.

****When including a standard detail, include a sheet with work zone shown as high resolution, to scale drawing representing the existing street conditions and geometrics.**

FOR C.I.P. PROJECTS USE THIS BARRICADING SUMMARY TABLE

Streets

Street	Classification	Street From	Street To	Planned Improvements	Traffic Control Plan Sheet	Allowed Barricading Hours	Duration(*)	Set Up	Comments
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Water Line and Meter Install	TC10	9am-4pm Mon-Fri; 7am-7pm Weekends	1 week	Daily	
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Electrical Work	sheet 23	9am-4pm Mon-Fri; 7am-7pm Weekends	3 days	Daily	**804s-2, sheet 2
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Storm Drain Installation	sheet 23	9am-4pm Mon-Fri; 7am-7pm Weekends	1 week	Daily	**804s-2, sheet 2
Lewis Ln.	ASMP 1	40th St.	42nd St.	Wastewater Line, Manholes & Connections	sheet 23	7am-7pm Mon-Fri; 7am-7pm Weekends	3 weeks	Daily	**804s-2, sheet 2
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Flat Work, Driveway & Sidewalk	TC11	7am-7pm Mon-Fri; 7am-7pm Weekends	2 weeks	Intermediate-Term Stationary	**24 hr for concrete to cure (1 day)
45th St.	ASMP 3	Burnet Rd.	Sinclair Ave.	Electric Manhole	TC12	7am-7pm Mon-Fri; 7am-7pm Weekends	1 week	Daily	
Lewis Ln.	ASMP 1	40th St.	42nd St.	Deliveries, Concrete Pours	TC14	7am-7pm Mon-Fri; 7am-7pm Weekends	13 months	Daily	
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Crane Install & or Removal	TC09	Friday 7pm -Sunday Midnight	3 days	Intermediate-Term Stationary	
40th Street	ASMP 2	Ramsey Ave.	Rosedale Ave.	Pedestrian Walkway	TC13	24/7	13 months	Long-Term Stationary	
* DURATION IS ESTIMATED. THE DURATION COLUMN OF THIS TABLE MAY BE REVISED BY CONTRACTOR BASED UPON THE PROJECT SEQUENCING REQUIREMENTS AND PROPOSED MEANS AND METHODS FOR CONSTRUCTING THE PROJECT.									

Intersections

Street Intersection	Classification	Planned Improvements	Traffic Control Plan Sheet	Allowed Barricading Hours	Duration(*)	Set Up	Comments
40th St./Ramsey Ave.	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC13 & TC14	9am-4pm Mon-Fri; 7am-6pm Weekends	1 week	Daily	
40th St./Baily Ln.	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC15 & TC16	9am-4pm Mon-Fri; 7am-6pm Weekends	3 days	Daily	
40th St./Medical Parkway	ASMP 2 / ASMP 2	Water, Wastewater, & Storm installation	TC17 & TC18	9am-4pm Mon-Fri; 7am-6pm Weekends	1 week	Daily	
41st St./Lewis Ln	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC19 & TC20	7am-7pm Sun.-Sat.	3 weeks	Daily	
42nd St./Lewis Ln.	ASMP 2 / ASMP 1	Water, Wastewater, & Storm installation	TC21 & TC22	7am-7pm Sun.-Sat.	1 day	Daily	
* DURATION IS ESTIMATED. THE DURATION COLUMN OF THIS TABLE MAY BE REVISED BY CONTRACTOR BASED UPON THE PROJECT SEQUENCING REQUIREMENTS AND PROPOSED MEANS AND METHODS FOR CONSTRUCTING THE PROJECT.							

Daily: Closures are set up and removed the same day within the allowed barricading hours provided.

Intermediate-Term Stationary: Closures remain in place continuously for one to three days (or nighttime work lasting more than 1 hour).

Long-Term Stationary: Closures remain in place continuously for more than three days.

Mobile: The work zone is continuously moving and must not remain in a single location for more than 15 minutes.

****Comments:** Use this field to provide any additional details or clarification related to the selected work zone type.

****When including a standard detail, include a sheet with work zone shown as high resolution, to scale drawing representing the existing street conditions and geometrics.**