



Lower Buttermilk Branch Stream Restoration

PUBLIC MEETING
July 25, 2024

www.AustinTexas.gov/Buttermilk





Welcome and Agenda

- Introductions
- Watershed Protection Department
- Project Status
- Preliminary Engineering Report Summary
- Schedule and Next Steps
- Questions & Comments





Introductions

Sponsoring Department: Watershed Protection Department

Project Sponsor: Donald Heisch, P.E., CFM

Sponsor Manager: Eric Loucks, P.E.

Communications: Becca Villarreal

Managing Department: Capital Delivery Services

Project Manager: Minda Sarmiento, P.E.

Consulting Engineer: Carollo Engineers Inc.


Project Manager: TJ Rhoads, P.E., CFM

Watershed Protection Department

Mission:

Protect lives, property, and the environment of our community by reducing the impact of:

- Flooding
- Erosion
- Water Pollution







Creek Assessment | Project Goals


- Creek bottom and banks eroding
- Public and private property threatened by erosion
- Water quality pollution
- Degradation of stream

- Stabilize and repair creek banks
- Protect properties from erosion damage
- Protect the ecology of the creek
- Plant native vegetation
- The project will not worsen flooding















Project Status

February 2023 - Completed Initial Geomorphic Assessment

Identified Erosion Sites

Spring 2023 – Initiated Preliminary Engineering

- Hydraulic Modelling
- Geotechnical Investigations
- Environmental Investigations
- Alternatives Analysis

Spring 2024 - Completed Preliminary Engineering Report

- Recommended Actions
- Conceptual Designs for Each Improvement




O Preliminary Engineering Report Summary



Widespread downcutting (to bedrock), channel widening, and bank erosion

- Geomorphic Assessment
 - Identified 14 active erosion sites (A through N)
- Erosion Site Screening and Project Prioritization (4 Steps)
 - Data compilation
 - Site screening
 - Site prioritization
 - Project site recommendations
























EROSION SITECREAK ALIGNMENT

— CROSS-SECTION

PLANNING

REPAIRED





STA. 3500

CULVERTS UNDER CAMERON RD

() STA. 3200

FAILED WEIR IN CREEK CHANNEL





Recommended Projects


Selected Sites

- Six sites were selected to move forward (A, B, C, E, F, and I)
- Top priority sites: A, B, C, and E
 - Needs extensive bank repairs
- Sites: F and I
 - Typical bank repairs (i.e. Mechanically Stabilized Earth (MSE) block walls and vegetated riprap)



WATERSHED PROTECTION

- 12 ft high, steep bank erosion threatens adjacent building
- Proposed improvements are within existing drainage easement
- ± 200 linear feet of improvements
- Existing stormwater outlet near improvements to be modified
- No Critical Environmental Features (CEFs) or heritage trees identified within the immediate vicinity





Site A (bank in the background)





Drilled Shaft Wall

- Drilled shaft wall, with H-pile and concrete lagging
- Limestone facing options
- Top of wall to extend at least 0.5 ft above the 100yr storm water surface elevation (WSEL)
- Opposite bank grading
- 3:1, vegetated shelf to existing grade
- Estimated Costs ~ \$2,100,000




Similar project completed in 2017



WATERSHED PROTECTION

- Scour upstream and downstream of existing bank armoring
- Additional easement may be required
- Nearby CEFs include seeps and a rock outcrop, just upstream of site
- Improvements to be extended between both sites B & C
- ± 530 linear feet of improvements (Sites B and C combined)






Typical segment of Sites B and C



Sites B & C

Drilled Shaft Wall

- Description:
 - Drilled shaft wall, with H-pile and concrete lagging
 - Limestone facing options
 - Top of wall to extend at least 0.5 ft above the 10-yr storm water surface elevation
 - Opposite bank grading
 - 3:1, vegetated shelf to existing grade
- Estimated Costs (Sites B & C combined) ~ \$3,800,000




Schematic of Drilled Shaft Wall





- 20 ft high bank erosion threatens nearby apartment buildings
- Improvements likely to be situated within an existing easement
- Nearby CEF includes rock outcrop extending along the site
- 1 nearby heritage tree threatened with construction
- \pm 200 linear feet of improvements





Site E Typical Conditions






Drilled Shaft Wall

- Description:
 - Drilled shaft wall, with H-pile and concrete lagging
 - Limestone facing options
 - Top of wall to extend at least 0.5 ft above the 10-yr storm WSEL to protect against higher shear stresses
 - Opposite bank grading
 - 3:1, vegetated shelf to existing grade
- Estimated Costs ~ \$1,900,000





- 12 ft high bank erosion threatens a private yard and residential building
- Proposed improvements are likely to be situated within an existing easement
- Site falls within 150 ft of a rock outcrop;
- 1 nearby heritage tree not likely to be threatened by improvements
- ± 135 linear feet of improvements





Site F Typical Conditions





Mechanically Stabilized Earth (MSE) Block Wall

- Description:
 - Stacked limestone block with geogrid.
 - 3:1, vegetated shelf to existing grade.
- Estimated Costs ~ \$1,400,000



Example of MSE Block Wall




WATERSHED PROTECTION

- 6 ft high bank erosion threatens yard
- Proposed improvements will likely extend beyond the existing easement
- Additional easement may be required
- Nearby fault according to state-sponsored mapping system
- Site I falls within 150 ft of a rock outcrop
- 4 nearby heritage trees. It's likely some of these will be removed for construction
- ± 110 linear feet



Site I







Vegetated Riprap

- Description:
 - Riprap installed at a 2:1 slope
 - Riprap filled with topsoil and vegetated
- Estimated Costs ~ \$1,000,000



Example of Vegetated Riprap



Anticipated Schedule and Next Steps

Fall 2024

- Detailed Design Phase: Sites A, B, & C
- Watershed in-house project delivery assignment:
 Sites F & I
- Pending capital improvement Funding: Site E

Fall 2026 - Bid Phase

Summer 2027 – Construction Phase





Questions & Comments







Contact Information

City of Austin Capital Delivery Services <u>Minda.Sarmiento@austintexas.gov</u> 512-974-5645

City of Austin Watershed Protection Department <u>Donald.Heisch@austintexas.gov</u> 512-978-1964