

#### Austin City Council:

Steve Adler - Mayor
Kathie Tovo - Mayor Pro Tem
Ora Houston
Delia Garza
Sabino Renteria

Gregorio Casar Ann Kitchen


Don Zimmerman

Leslie Pool Ellen Troxclair

#### Austin City Manager:

Marc A. Ott

Sheri Gallo



## Number Description Revised ( R ) Add ( A ) Void ( V ) Sheet No.'s Sheet No.'s Sheet No.'s Net Change (Sq. Ft.) Cover (Sq. Ft.) Cover (Sq. Ft.) Cover (Sq. Ft.)

COA GRID: H22 MAPSCO #: 584Y

#### NOTES:

- 1. THIS PROJECT IS LOCATED IN THE BARTON CREEK WATERSHED.
- 2. THIS PROJECT IS LOCATED IN THE BARTON SPRINGS ZONE.
- 3. THIS PROJECT IS PARTIALLY LOCATED OVER THE EDWARDS AQUIFER RECHARGE ZONE
- L THIS PROJECT IS LOCATED WITHIN THE 100-YEAR FLOODPLAIN PER FEMA MAP NO. 48453C0445H
- 5. THIS PROJECT IS SUBJECT TO THE VOID AND WATER FLOW MITIGATION RULE (ECM 1.12.0) AND COA STANDARD SPECIFICATION ITEM 658S, ALL TRENCHING GREATER THAN 5 FT DEEP MUST BE INSPECTED BY A GEOLOGIST (TEXAS P.G. OR A GEOLOGISTS REPRESENTATIVE).
- 6. THE PROJECT SITE IS ZONED PUBLIC-P AND PUBLIC-HISTORIC P-H
- 7. AN AMENDMENT TO THE SAVE OUR SPRINGS ORDINANCE WILL BE REQUIRED TO ALLOW CONSTRUCTION OF THIS PROJECT WITHIN THE BARTON SPRINGS ZONE.
- 8. CALL ONE CALL CENTER (1-800-344-8377) FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREETS RIGHT-OF-WAY.
- 9. NOTIFY THE PUBLIC WORKS DEPARTMENT, IN WRITING, TWENTY FOUR (24) HOURS PRIOR TO STARTING CONSTRUCTION OR CLEARING OPERATIONS.
- 10. RELEASE OF THE APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY, AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY THE CITY ENGINEERS.

Construction Drawings for

## ELIZA SPRING OUTLET DAYLIGHTING

BARTON SPRINGS POOL AREA

C.I.P. No. 6660.046

SITE ADDRESS: 2201 Barton Springs Rd

Austin, TX 78746

HDR Project No. Austin, Texas 00000000220162 JULY 2015

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF REVIEW UNDER THE AUTHORITY OF SCOTT M. MUCHARD TEXAS P.E. NO. 89409 DATE: JULY 24, 2015

IT IS NOT TO BE USED FOR CONSTRUCTION OR ANY OTHER PURPOSE.

ISSUED FOR 90% REVIEW JULY 24, 2015

#### INDEX OF DRAWINGS

No.	General	
1	G1.1	Cover
2	G1.2	General Notes
3	G1.3	Overall Site Plan
4	G1.4	Enlarged Site Plan
No.	Demolition	
5	X1.1	Amphitheater Masonry and Ramp Demolition Plan
6	X1.2	Amphitheater Masonry Demolition Elevation
No.	Civil	
7	C1.1	Erosion/Sedimentation Control & Tree Protection Plan
8	C1.2	Erosion/Sedimentation Control & Tree Protection Notes
9	C1.3	Erosion/Sedimentation Control Standard Details
10	C1.4	Care of Water Plan and Notes
11	C2.1	General Project Layout
12	C2.2	Project Grading Plan
13	C2.3	Horizontal Alignment Data
14	C2.4	Outlet Channel - Plan & Right Profile
15	C2.5	Typical Channel Sections w/ Slope System Details
16	C2.6	Miscellaneous Channel Details
17	C2.7	Cross Sections
18	C3.1	Storm Drain Line A Drainage Area Map
19	C3.2	Storm Drain Line A Plan & Profile
20	C3.3	Storm Drain Line B Drainage Area Map
21	C3.4	Storm Drain Line B Plan & Profile
22	C3.5	Construction Details
No.	Structural	
23	S1.1	Amphitheater & Junction Box Structural Plan
24	S1.2	Structural Enlarged Plans
25	S1.3	Amphitheater Sections
No.	Landscape	
26	L 1.1	Fencing Plan
27	L 1.2	Planting Plan
28	L 2.1	Landscape Sections & Details
29	IR 1	Irrigation Plan
30	IR 2	Irrigation Details



HDR Engineering, Inc. Firm Registration No. 754 4401 West Gate Blvd., Ste 400 Austin,Tx 78745 Ph: (512)912-5100 Fax: (512)912-5158

#### OWNER:

City of Austin

#### MANAGING DEPARTMENT CONTACT:

Jules Parrish, Project Manager
Public Works Department
505 Barton Springs Road
9th Floor
Austin, TX 78704
(512) 974-9385 Fax: (512) 974-7222

#### SPONSORING DEPARTMENT CONTACT:

Donelle Robinson, Project Sponsor WPD 505 Barton Springs Road 11th Floor Austin, TX 78704 (512) 974-1242 Fax: (512) 974-2846

#### **ENGINEER OF RECORD:**

Scott M. Muchard P.E., C.F.M. HDR Engineering, Inc. 4401 West Gate Blvd., Ste. 400 Austin, Texas 78745 Phone: (512) 912-5100 Fax: (512) 912-5158

#### **Sponsoring Department:**

Watershed Protection Department	Date
Managing Department:	
Watershed Protection Department	Date
Submitted By:	
HDR Engineering	Date
Reviewed By:	
For Director, Planning and Development Review Department	Date
SP-####-####	
Site Plan/ Development Permit Number	Date
SUBMITTAL DATE: XXXXXXXXX	SHEET 1 OF 30

1. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY OF AUSTIN MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.

2

- 2. CONTRACTOR SHALL CALL THE ONE CALL CENTER (1-800-344-8377) FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET R.O.W.
- 3. CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTION DIVISION OF THE CITY'S ONE STOP SHOP (OSS) AT 974-6360 OR 974-7034 AT LEAST 24 HOURS PRIOR TO THE INSTALLATION OF ANY DRAINAGE FACILITY WITHIN A DRAINAGE EASEMENT OR STREET R.O.W. THE METHOD OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S R.O.W. MUST BE APPROVED PRIOR TO THE START OF BACKFILL OPERATIONS.
- 4. FOR SLOPES OR TRENCHES GREATER THAN FIVE FEET IN DEPTH, A NOTE MUST BE ADDED STATING: "ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION." (OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE: INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 EAST 6TH STREET, AUSTIN TEXAS.)
- 5. ALL SITE WORK MUST ALSO COMPLY WITH ENVIRONMENTAL REQUIREMENTS.
- 6. UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS AND PRIOR TO THE FOLLOWING, THE ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DRAINAGE, FILTRATION AND DETENTION FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS:
- RELEASE OF THE CERTIFICATE OF OCCUPANCY BY THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT (INSIDE THE CITY LIMITS); OR
- INSTALLATION OF AN ELECTRIC OR WATER METER (IN THE FIVE-MILE ETJ).

#### SPECIAL CONSTRUCTION NOTES

- 1. BLASTING WITHIN THE PROJECT AREA WILL NOT BE ALLOWED WITHOUT A SEPARATE BLASTING PERMIT.
- 2. BURNING WILL NOT BE ALLOWED ONSITE.
- 3. THE CONTRACTOR SHALL FURNISH, INSTALL AND MAINTAIN BARRICADES, WARNING SIGNS, FLASHERS AND OTHER DEVICES OF THE TYPE AND SIZE AS INDICATED IN THE LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, OR AS DIRECTED BY THE ENGINEER.
- 4. THE CONTRACTOR SHALL MAINTAIN AT LEAST ONE DUST-FREE LANE FOR TRAFFIC WITH FLAGMEN DURING CONSTRUCTION ACTIVITIES AND TWO LANES AT ALL OTHER TIMES. ACCESS TO CONTIGUOUS PRIVATE PROPERTIES SHALL BE MAINTAINED AT ALL TIMES.
- 5. ALL STRUCTURAL CONCRETE SHALL BE CLASS "A" (5 SACK, 25-8-36100 PSI @ 28 DAYS) AND ALL REINFORCING STEEL SHALL BE GRADE SIXTY, UNLESS OTHERWISE NOTED.
- 6. THE CONTRACTOR SHALL NOT DISPOSE OF SURPLUS EXCAVATED MATERIAL FROM THE SITE WITHOUT NOTIFYING THE ENVIRONMENTAL INSPECTOR, AT 974-2278, 48 HOURS PRIOR TO THE REMOVAL. THIS NOTIFICATION SHALL INCLUDE THE DISPOSAL LOCATION AND A COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL, IF APPLICABLE.
- 7. UTILITIES SHOWN REFLECT THE BEST INFORMATION AVAILABLE AT THE TIME THE PROJECT WAS SURVEYED. UTILITY RELOCATION WORK HAS BEEN OR WILL BE ACCOMPLISHED TO CLEAR THE WORK SPACE. THESE RELOCATIONS ARE NOT REFLECTED ON THESE DRAWINGS. FOR EXACT LOCATIONS CALL 472-2822. 48 HOURS PRIOR TO BEGINNING EXCAVATION.
- 8. SIGNS IN THE WAY OF CONSTRUCTION SHALL BE REMOVED AND RELOCATED AS SOON AS POSSIBLE. ALL TRAFFIC CONTROL SIGNS, INCLUDING STOP AND STREET—NAME SIGNS, SHALL NOT BE REMOVED OR RELOCATED WITHOUT THE APPROVAL OF THE PROJECT INSPECTOR AND THE TRANSPORTATION ENGINEERING DIVISION OF THE DEPARTMENT OF TRANSPORTATION. THIS WORK SHALL BE SUBSIDIARY TO OTHER BID ITEMS.
- 9. ALL SITE WORK MUST COMPLY WITH THE ENVIRONMENTAL REQUIREMENTS.
- 10. THE CONTRACTOR SHALL ERECT AND MAINTAIN A FILTER FABRIC FENCE AT LOCATIONS SHOWN ON THE PLANS AND ANY OTHER LOCATIONS DESIGNATED BY THE ENGINEER. PAYMENT WILL BE MADE UNDER ITEM NO. 620 FILTER FABRIC FENCE.
- 11. ANY UTILITY METERS IN THE WAY OF THE CONSTRUCTION WILL BE RELOCATED OUTSIDE OF THE PROPOSED CONSTRUCTION AREA BY THE UTILITY OWNER UNLESS SUCH WORK AFFECTING THOSE METERS IS INCLUDED IN THE CONTRACT.
- 12. ANY AREAS TO RECEIVE TRANSITION PAVEMENT SHALL BE CONSTRUCTED WITH THE SAME TYPICAL SECTION AS THE ADJACENT NEW CONSTRUCTION.
- 13. ANY EXISTING SIDEWALKS, CURBS OR DRIVEWAYS DISTURBED BY THE CONSTRUCTION SHALL BE REMOVED AND RESTORED WITH SURFACE MATERIALS EQUAL TO OR BETTER THAN THE ORIGINAL.
- 14. THE REMOVAL OF EXISTING DRIVEWAY PIPE CULVERTS, RIPRAP AND HEADWALLS IN THE WAY OF CONSTRUCTION WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE SUBSIDIARY TO OTHER BID
- 15. IN AREAS WHERE EXISTING CURBS AND GUTTERS ARE TO REMAIN, THE OLD PAVING AND BASE MUST BE REMOVED AND THE NEW BASE AND PAVING PLACED AND COMPACTED SO AS NOT TO DISTURB EXISTING CURBS AND GUTTERS.
- 16. USE OF HYDRATED LIME SHALL BE RESTRICTED AND SHALL BE APPROVED BY OWNER. OWNER MAY DENY APPROVAL FOR USE OF HYDRATED LIME AT OWNER'S DISCRETION.
- 17. ALL STORM SEWER PIPE SHALL BE RCP, CLASS V, WITH BEDDING THAT CONFORMS TO COA STANDARD SPECIFICATION 510-PIPE, UNLESS OTHERWISE NOTED. ALL BEDDING MATERIAL SHALL BE APPROVED BY OWNER PRIOR TO PLACEMENT.
- 18. THE CONTRACTOR SHALL ERECT AND MAINTAIN FILTER FABRIC FENCE, MULCH SOCKS, AND SPILL CONTAINMENT BOOMS AT LOCATIONS SHOWN ON THE PLANS AND ANY OTHER LOCATIONS DESIGNATED BY THE ENGINEER OR OWNER. PAYMENT WILL BE MADE UNDER THE APPROPRIATE ITEMS LISTED ON THE BID FORM 300U.

- 19. COMPLIANCE WITH FEDERAL AND STATE ENDANGERED SPECIES PERMITS IS REQUIRED. OVERSIGHT BY CITY OF AUSTIN SALAMANDER BIOLOGIST IN ADDITION TO CITY OF AUSTIN ENVIRONMENTAL INSPECTOR IS REQUIRED THROUGHOUT THE ENTIRE CONSTRUCTION PHASE.
- 20. THE ENTIRE FLOOR OF THE ELIZA SPRING AMPHITHEATER IS ENDANGERED SPECIES HABITAT AND CANNOT BE IMPACTED BY CONSTRUCTION. EQUIPMENT AND CREW CANNOT ENTER THE AMPHITHEATER FLOOR, NOR CAN MATERIALS, DEBRIS, OR SILT DROP INTO IT.
- 21. ELIZA SPRING AMPHITHEATER IS A HISTORICAL STRUCTURE. ONLY THE PARTS NOTED TO BE REMOVED CAN BE AFFECTED. DEMOLITION AND CONSTRUCTION MUST LEAVE THE REST OF THE HISTORICAL STRUCTURE UNDAMAGED.
- 22. DAMAGED STRUCTURES MUST BE REPAIRED BY THE CONTRACTOR AT CONTRACTOR'S EXPENSE.
- 23. SPECIFIED MATERIALS, MEANS, METHODS, TECHNIQUES, SEQUENCES, OR PROCEDURES SHALL NOT BE SUBSTITUTED WITHOUT APPROVAL BY OWNER.
- 24. COMPLIANCE WITH WPAP WAIVER IS REQUIRED
- 25. COORDINATION WITH USFWS AND TPWD ARE REQUIRED. CITY OF AUSTIN WILL ARRANGE COORDINATION WITH THESE ENTITIES, AND CONTRACTOR WILL NEED TO COMPLY.
- 26. CONTRACTOR SHALL TAKE EXTREME CARE NOT TO DAMAGE EXISTING BURIED PIPE UNTIL WATER FLOW IS DIVERTED.
- 27. MAXIMUM ALLOWABLE UNIFORM LIVE LOAD ON THE BYPASS TUNNEL ROOF IS 100 PSF.
- 28. MAXIMUM ALLOWABLE EQUIPMENT LOAD ON THE BYPASS TUNNEL ROOF IS 2,000 LBS. EQUIPMENT DATASHEETS MUST BE SUBMITTED FOR ENGINEER/OWNER APPROVAL BEFORE EQUIPMENT WILL BE ALLOWED ON THE BYPASS TUNNEL ROOF. DATASHEETS WILL BE USED TO DETERMINE THE APPLIED LOADING ON THE BYPASS TUNNEL ROOF.
- 29. FOR THE PROTECTION OF NATURAL AREAS. NO EXCEPTIONS WILL BE TAKEN TO THE LOCATIONS OF FENCES AT THE LIMITS OF CONSTRUCTION AS SHOWN ON PLANS. CONTRACTOR NOT TO EXCEED THE LIMITS OF CONSTRUCTION.
- 30. CONTRACTOR TO NOTIFY CITY OF AUSTIN SALAMANDER BIOLOGISTS PRIOR TO WORK NEAR OR WITHIN SALAMANDER HABITAT AREA, INCLUDING ANY WORK WITHIN THE ELIZA SPRING AMPHITHEATER. CONTRACTOR SHALL COORDINATE TIMING OF WORK WITHIN THE ELIZA SPRING AMPHITHEATER WITH CITY OF AUSTIN SALAMANDER BIOLOGISTS.
- 31. CITY OF AUSTIN SALAMANDER BIOLOGIST MUST BE PHYSICALLY PRESENT AT ALL TIMES WHEN THE CONTRACTOR IS WORKING WITHIN THE ELIZA SPRING AMPHITHEATER.
- 32. CITY OF AUSTIN SALAMANDER BIOLOGIST MUST HAVE CONTINUAL ACCESS TO ALL PARTS OF THE CONSTRUCTION SITE.
- 33. CITY OF AUSTIN SALAMANDER BIOLOGIST HAVE IMMEDIATE STOP WORK AUTHORITY FOR ANY ACTIVITY THAT IN THEIR SOLE JUDGEMENT POSES POTENTIAL HARM TO PROTECTED SALAMANDER HABITAT.
- 34. NO STRUCTURAL WORK IS ALLOWED TO INTRUDE INTO THE FLOOR OF THE AMPHITHEATER WITHIN SALAMANDER HABITAT.
- 35. HAZARDOUS MATERIALS SHALL NOT BE ALLOWED TO ENTER ENDANGERED SPECIES HABITAT OR THE CONSTRUCTED SPRING OUTLET CHANNEL.
- 36. PROJECT CONSTRUCTION WORKING HOURS ARE FROM 7 AM TO 7 PM WEEKDAYS AND 8 AM TO 7 PM WEEKENDS.

#### **DEVELOPER INFORMATION**

OWNER: DONELLE ROBINSON, CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT ADDRESS: 505 BARTON SPRINGS ROAD, AUSTIN, TX 78701

PHONE #: 512-974-1242

OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: SCOTT M. MUCHARD, P.E., HDR ENGINEERING, INC.

PHONE#: 512-912-5100

PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE: PHONE#:

PERSON OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION MAINTENANCE: PHONE#:

#### AMERICANS WITH DISABILITIES ACT

THE CITY OF AUSTIN HAS REVIEWED THIS PLAN FOR COMPLIANCE WITH CITY DEVELOPMENT REGULATIONS ONLY. THE APPLICANT, PROPERTY OWNER, AND OCCUPANT OF THE PREMISES ARE RESPONSIBLE FOR DETERMINING WHETHER THE PLAN COMPLIES WITH ALL OTHER LAWS, REGULATIONS, AND RESTRICTIONS WHICH MAY BE APPLICABLE TO THE PROPERTY AND ITS USE.

PROJECT MANAGER S. MUCHARD

**DESIGNED BY** MUCHARD DRAWN BY AMARAL C 07/24/2015 90% DRAFT FOR REVIEW B 10/3/2014 90% DRAFT FOR REVIEW CHECKED BY PARKER A 1/24/2014 60% DRAFT FOR REVIEW DATE CTOBER 2014 ISSUE DATE PROJECT NUMBER | 220162 DESCRIPTION

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF REVIEW UNDER THE AUTHORITY OF <u>SCOTT M. MUCHARD</u> EXAS P.E. NO.89409 <u> DATE: JULY 24, 201</u> T IS NOT TO BE USED FOR CONSTRUCTION OF ANY OTHER PURPOSE **90% DRAFT** 



**ELIZA SPRING OUTLET DAYLIGHTING** 

**Austin, Texas** 


#### **GENERAL NOTES**

FILENAME | G1.2.DWG

SHEET

G1.2

SCALE NONE





			PROJECT MANAGER	5. MUCHARD
			DESIGNED BY	S. MUCHARD
			DRAWN BY	C. AMARAL
С	07/24/2015	90% DRAFT FOR REVIEW		
В	10/3/2014	90% DRAFT FOR REVIEW	CHECKED BY	C. PARKER
A	1/24/2014	60% DRAFT FOR REVIEW	DATE	OCTOBER 2014
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	220162
			•	•


90% DRAFT



**Austin, Texas** 



SHEET G1.3



SHEET

G1.4

FILENAME G1.4.DWG

**SCALE** 1" = 30'

**Austin, Texas** 

B 10/3/2014 90% DRAFT FOR REVIEW

A 1/24/2014 60% DRAFT FOR REVIEW

DESCRIPTION

ISSUE DATE


Texas P.E. Firm Registration No. F-754


CHECKED BY | C. PARKER

OCTOBER 2014

DATE

PROJECT NUMBER 220162






(2) ELEVATION - MASONRY INFILL TO BE REMOVED

#### 4'-6"± - LIMESTONE WALL BEYOND TO BE REMOVED CONCRETE WALL BEYOND TO REMAIN — LIMESTONE STEPS TO BE REMOVED **ROCKWALL** BEYOND TO BE REMOVED -437.73 F.V. -EXISTING SOIL LIMESTONE INFILL TO BE REMOVED TO BE REMOVED -EXISTING PIPE EXISTING AMPHITHEATER TO BE REMOVED FLOOR TO REMAIN-AMPHITHEATER FLOOR-ENDANGERED SPECIES HABITAT — SECTION-MASONRY INFILL TO BE REMOVED

1 ELEVATION - MASONRY INFILL TO BE REMOVED



JUNCTION BOX DEMOLITION PLAN

SCALE: 3/8" = 1'-0"

#### GENERAL NOTES

- 1. REFER TO CARE OF WATER SHEET C1.4 PRIOR TO CONSTRUCTION.
- 2. THE ACCURACY OF ITEMS SHOWN AS EXISTING ON DRAWINGS WAS DETERMINED FROM RECORD DRAWINGS AND FIELD OBSERVATIONS.
- 3. DRAWINGS ARE NOT TO BE SCALED FOR DETERMINATION OF QUANTITIES, LENGTHS, OR FIT OF MATERIALS.
- 4. DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHODS OF CONSTRUCTION UNLESS SO STATED OR NOTED. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE, THE WORKMEN AND ALL OTHER PERSONS DURING CONSTRUCTION.
- 5. CONTRACTOR SHALL PROVIDE TEMPORARY BRACING AND SHORING OF ALL WORK AS REQUIRED FOR STABILITY OF THE STRUCTURE DURING ALL PHASES OF CONSTRUCTION. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY CONDITION WHICH, IN HIS/HER OPINION, MIGHT ENDANGER THE STABILITY OF THE STRUCTURE OR CAUSE DISTRESS IN THE STRUCTURE.
- 6. ALL EXISTING CONDITIONS AND DIMENSIONS SHALL BE FIELD VERIFIED PRIOR TO PREPARATION OF SHOP DRAWINGS AND THE BEGINNING OF THE CONSTRUCTION PROCESS
- 7. ENTIRE AMPHITHEATER FLOOR IS ENGDANDERED SPECIES HABITAT AND CANNOT BE IMPACTED BY CONSTRUCTION.
- 8. EQUIPMENT AND PEOPLE CANNOT ENTER THE FLOOR, NOR CAN ANY MATERIALS OR SILT DROP INTO IT. PROVIDE NETTING OR OTHER BARRIERS (APPROVED BY OWNER) TO PREVENT CONSTRUCTION DEBRIS FROM ENTERING AMPHITHEATER
- 9. PRECAUTION NEEDS TO BE TAKEN WHEN REMOVING THE KEYWAY TO PREVENT DEWATERING OF THE AMPHITHEATER FLOOR. REFER TO SHEET C1.4 FOR CARE OF WATER. DEMOLITION ACTIVITIES SHALL BE COORDINATED WITH CITY OF AUSTIN BIOLOGIST. BIOLOGIST MAY NEED TO MOVE HABITAT AND SALAMANDERS ADJACENT TO REMOVAL OF GRATING AND PIPE TO PREVENT INJURY/DEATH.
- 10. ELIZA SPRING AMPHITHEATER IS A HISTORICAL STRUCTURE. ONLY THE PARTS NOTED TO BE REMOVED CAN BE AFFECTED. DEMOLITION AND CONSTRUCTION MUST LEAVE THE REST OF THE HISTORICAL STRUCTURE UNDAMAGED.
- 11. DAMAGED STRUCTURES MUST BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
- 12. EQUIPMENT USED IN AMPHITHEATER SHALL BE HAND OR ELECTRIC POWERED.

#### **KEYED NOTES:**

- (1) EXISTING GRATING AND OUTLET PIPE TO BE REMOVED.
- (2) EXISTING CONCRETE AMPHITHEATER SEATING STEPS TO REMAIN.
- (3) EXISTING STEEL GATE TO BE REMOVED.
- (4) EXISTING LIMESTONE MASONRY INFILL TO BE REMOVED.
- (5) EXISTING LIMESTONE MASONRY STEPS TO BE REMOVED.
- (6) EXISTING PERIMETER FENCE TO REMAIN.
- (7) EXISTING AMPHITHEATER FLOOR TO REMAIN.
- ig(8ig) EXISTING CONCRETE JUNCTION BOX TO BE REMOVED.
- (9) EXISTING CONCRETE RETAINING WALL TO BE REMOVED.

#### LEGEND:

PERIMETER FENCE


LIMESTONE MASONRY


CONCRETE


SOIL

Jose I. Guerra, Inc.
Consulting Engineers
2401 South IH-35 Suite 210
Austin, Texas 78741
(512) 445-2090
Structural • Civil • Mechanical • Electrical
TBPE FIRM F-3










### ELIZA SPRING OUTLET DAYLIGHTING

**Austin, Texas** 

#### STRUCTURAL DEMOLITION ELEVATIONS AND ENLARGED PLANS



**X1.2** 



ISSUE DATE

DESCRIPTION

PROJECT NUMBER | 220162

RELOCATION OF PUBLIC ACCESS ROUTES. WORK SHALL BE COMPLETED DURING THE OFF-PEAK SEASON BETWEEN OCTOBER 1 AND FEBRUARY 28. REFER TO PROJECT MANUAL FOR

- CONTRACT REQUIREMENTS. SUBMIT AND RECEIVE OWNER APPROVAL OF A SPILL PREVENTION AND CONTROL PLAN PER SS130300.
- 4. INSTALL TEMPORARY SECURITY FENCE.
- 5. INSTALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS AS INDICATED ON THE EROSION/SEDIMENTATION CONTROL AND TREE PROTECTION PLAN. INSTALL TREE PROTECTION AS INDICATED ON THE EROSION/SEDIMENTATION CONTROL AND TREE PROTECTION PLAN AND INITIATE TREE MITIGATION MEASURES.
- CONTACT THE WATERSHED PROTECTION DEPARTMENT, ENVIRONMENTAL INSPECTION AT 512-974-2278, 72 HOURS PRIOR TO THE SCHEDULED DATE OF THE REQUIRED ON-SITE PRECONSTRUCTION MEETING.
- REVISE TEMPORARY EROSION AND SEDIMENTATION CONTROLS, IF NEEDED, TO COMPLY WITH CITY INSPECTORS' DIRECTIVES
- INSPECT AND MAINTAIN TEMPORARY EROSION AND SEDIMENTATION CONTROLS IN ACCORDANCE WITH THE SITE PLAN REQUIREMENTS.
- BEGIN SITE CLEARING/CONTRUCTION ACTIVITIES. PROJECT COMPONENTS SHALL BE CONSTRUCTED IN THE ORDER DESCRIBED BELOW. AN ALTERNATE PHASING PLAN MAY BE SUBMITTED FOR REVIEW AND APPROVAL, BUT WILL ONLY BE CONSIDERED IF THE ALTERNATE PLAN IS MORE PROTECTIVE OF ENDANGERED SPECIES AND ENVIRONMENTAL QUALITY THAN THE SEQUENCE PROVIDED HEREIN.
- A. IMPLEMENT BYPASS TUNNEL COFFERDAM AT LOCATION OF PROPOSED JUNCTION BOX (COFFERDAM NO.1). (REFER TO SHEET C1.4.)
- B. CONSTRUCT PROPOSED STORM DRAIN LINE B, INCLUDING PROPOSED BYPASS TUNNEL JUNCTION BOX. (REFER TO SHEET C3.4.) IMPLEMENT EXCAVATION DEWATERING AS NECESSARY. (REFER TO SHEET C1.4.) TEMPORARILY BLOCK TUNNEL OPENING AND/OR STORM DRAIN LINE B AND CHANNEL FLOW CONTROL GATE ENTRANCES TO THE JUNCTION BOX TO PREVENT WATER DISCHARGE FROM THE CONSTRUCTION SITE INTO THE BYPASS TUNNEL. (REFER TO SHEET C1.4.) TEMPORARY BLOCKING OF TUNNEL OPENING AND/OR STORM DRAIN LINE B AND FLOW CONTROL GATE ENTRANCES MAY BE REMOVED WITH OWNER APPROVAL UPON COMPLETION OF STORM DRAIN LINE B AND INSTALLATION OF JUNCTION BOX CHANNEL FLOW CONTROL GATE. FLOW CONTROL GATE SHALL REMAIN CLOSED UNTIL OPENING OF GATES IS APPROVED BY OWNER AS DESCRIBED IN (K)
- C. INSTALL SALAMANDER EXCLUSION SCREEN AT AMPHITHEATER KEYWAY ENTRANCE. (REFER TO SHEET C1.4.)
- D. CONTRACTOR SHALL NOTIFY OWNER 48 HOURS PRIOR TO INITIATING SPRING FLOW DIVERSION AND/OR AMPHITHEATER KEYWAY DEWATERING. INSTALL AND ACTIVATE AMPHITHEATER KEYWAY DEWATERING COFFERDAM (COFFERDAM NO. 2) AND PUMP. (REFER TO SHEET C1.4.)
- E. CONSTRUCT TEMPORARY GRAVITY-FED SPRING FLOW DIVERSION JUNCTION BOX AND PIPE FROM AMPHITHEATER TO STORM DRAIN LINE B MANHOLE. (REFER TO SHEET C1.4.) CARRY OUT CONSTRUCTION ACTIVITIES IN A MANNER SO AS TO MINIMIZE TIME DURING WHICH USE OF AMPHITHEATER KEYWAY DEWATERING PUMPING SYSTEM IS REQUIRED.
- F. REMOVE COFFERDAM NO. 2 AND DE-ACTIVATE AMPHITHEATER KEYWAY DEWATERING PUMP TO ALLOW GRAVITY FLOW FROM THE AMPHITHEATER THROUGH THE EXISTING OUTFALL PIPE IN THE KEYWAY INTO THE TEMPORARY GRAVITY-FED SPRING FLOW DIVERSION. CONSULT WITH OWNER REGARDING SUITABILITY OF AMPHITHEATER WATER LEVELS FOR ENDANGERED SPECIES HABITAT. PROVIDE SUPPLEMENTAL PUMPING OR RESTRICTION OF DIVERSION IF DIRECTED BY OWNER TO ADJUST WATER LEVEL IN AMPHITHEATER.
- G. IMPLEMENT BYPASS-TUNNELL COFFERDAM AT STORM DRAIN LINE A (COFFERDAM NO. 3). (REFER TO SHEET C1.4.) CONSTRUCT STORM DRAIN LINE A (REFER TO SHEET C3.2), IMPLEMENTING EXCAVATION DEWATERING AS NECESSARY (REFER TO SHEET C1.4).
- H. SCHEDULE A MID-CONSTRUCTION CONFERENCE TO COORDINATE CHANGES IN THE CONSTRUCTION SCHEDULE AND EVALUATE EFFECTIVENESS OF THE EROSION CONTROL PLAN AFTER POSSIBLE CONSTRUCTION ALTERATIONS TO THE SITE. PARTICIPANTS SHALL INCLUDE THE CITY INSPECTOR. CITY BIOLOGIST. PROJECT ENGINEER. GENERAL CONTRACTOR AND ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR. THE ANTICIPATED COMPLETION DATE AND FINAL CONSTRUCTION SEQUENCE AND INSPECTION SCHEDULE WILL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR.
- CONSTRUCT OUTLET CHANNEL SLOPE SYSTEMS DOWNSTREAM OF TEMPORARY GRAVITY-FED SPRING FLOW DIVERSION JUNCTION BOX. (REFER TO SHEET C2.4.) REFER TO SHEET C2.5 FOR ADDITIONAL COMMENTARY ON SLOPE SYSTEM CONSTRUCTION PHASING. IMPLEMENT EXCAVATION DEWATERING AS NECESSARY. (REFER TO SHEET C1.4.)
- J. IMPLEMENT AMPHITHEATER KEYWAY DEWATERING COFFERDMAN (COFFERDAM NO. 2) AND PUMP AND REMOVE TEMPORARY GRAVITY SPRING FLOW DIVERSION. (REFER TO SHEET C1.4.) CONTRACTOR SHALL NOTIFY OWNER 48 HOURS PRIOR TO INITIATING ANY NEW PHASE OF AMPHITHEATER KEYWAY DEWATERING. COMPLETE OUTLET CHANNEL CONSTRUCTION (REFER TO SHEET C2.4), INCLUDING DEMOLITION OF AMPHITHEATER KEYWAY MASONRY AND LIMESTONE STEPS (REFER TO SHEET X1.1), CONSTRUCTION OF AMPHITHEATER HEADWALL AND FLOW CONTROL GATE (REFER TO SHEET S1.1), AND INSTALLATION OF CHANNEL SUBSTRATE MATERIAL. IF REMOVED FOR KEYWAY DEMOLITION, REINSTALL SALAMANDER EXCLUSION SCREEN AT

- AMPHITHEATER KEYWAY. CARRY OUT CONSTRUCTION ACTIVITIES IN A MANNER SO AS TO MINIMIZE TIME DURING WHICH USE OF AMPHITHEATER PUMPING SYSTEM IS REQUIRED.
- K. UPON RECEIVING APPROVAL FROM OWNER, CEASE AMPHITHEATER KEYWAY DEWATERING AND OPEN AMPHITHEATER AND JUNCTION BOX FLOW CONTROL GATES TO RELEASE SPRING FLOW INTO THE OUTLET CHANNEL AND TO THE BYPASS TUNNEL.
- 10. COMPLETE CONSTRUCTION AND REVEGETATION OF THE SITE AND INSTALL REMAINING LANDSCAPING AND IRRIGATION.
- 11. UPON COMPLETION OF THE SITE CONSTRUCTION AND PROJECT SITE REVEGETATION. THE DESIGN ENGINEER SHALL SUBMIT AN ENGINEER'S LETTER OF CONCURRENCE TO THE WATERSHED PROTECTION DEPARTMENT INDICATING THAT CONSTRUCTION IS COMPLETE AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AN ADDITIONAL LETTER OF CONCURRENCE WILL BE PROVIDED BY THE LANDSCAPE ARCHITECT INDICATING THAT THE REQUIRED LANDSCAPING IS COMPLETE AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AFTER RECEIVING THESE LETTERS, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY INSPECTOR.
- 12. AT THE FINAL INSPECTION WALK-THROUGH, THE OWNER WILL DETERMINE WHETHER THE TEMPORARY SALAMANDER EXCLUSION SCREEN AT THE AMPHITHEATER KEYWAY CAN BE REMOVED. REMOVE SCREEN WHEN DIRECTED BY OWNER.
- 13. AFTER A FINAL INSPECTION HAS BEEN CONDUCTED BY THE CITY INSPECTOR AND WITH APPROVAL FROM THE CITY INSPECTOR, REMOVE THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS, PUMPING SYSTEM, AND COMPLETE ANY NECESSARY FINAL REVEGETATION RESULTING FROM REMOVAL OF THESE CONTROLS.

#### <u>CITY OF AUSTIN — STANDARD NOTES EROSION AND SEDIMENTATION CONTROL</u>

- 1. THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL AREA PROTECTIVE FENCING PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR EXCAVATION)
- THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE ENVIRONMENTAL CRITERIA MANUAL AND THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN.
- THE PLACEMENT OF TREE/NATURAL AREA PROTECTIVE FENCING SHALL BE IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION AND THE APPROVED GRADING/TREE AND NATURAL AREA PLAN.
- A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD ON-SITE WITH THE CONTRACTOR, DESIGN ENGINEER/PERMIT APPLICANT AND ENVIRONMENTAL INSPECTOR AFTER INSTALLATION OF THE EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL AREA PROTECTION MEASURES AND PRIOR TO BEGINNING ANY SITE PREPARATION WORK. THE CONTRACTOR SHALL NOTIFY THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT AT, 512-974-2278, AT LEAST THREE DAYS PRIOR TO THE MEETING DATE. THE COA-APPROVED ESC PLAN SHOULD BE REVIEWED BY COA EV INSPECTOR AT THIS TIME.
- ANY SIGNIFICANT VARIATION IN MATERIALS OR LOCATIONS OF CONTROLS OR FENCES FROM THOSE SHOWN ON THE APPROVED PLANS MUST BE APPROVED BY THE REVIEWING ENGINEER, ENVIRONMENTAL SPECIALIST OR CITY ARBORIST AS APPROPRIATE.
- FIELD REVISIONS TO THE EROSION AND SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THE ENVIRONMENTAL INSPECTOR DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL INADEQUACIES. ANY REVISIONS TO THE PERMITTED PLAN MUST BE APPROVED BY THE SITE PLAN REVIEW OFFICE OF THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT.
- THE CONTRACTOR IS REQUIRED TO PROVIDE A CERTIFIED INSPECTOR WITH EITHER A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC), CERTIFIED EROSION, SEDIMENT AND STORMWATER-INSPECTOR (CESSWI) OR CERTIFIED INSPECTOR OF SEDIMENTATION AND EROSION CONTROLS (CISEC) CERTIFICATION TO INSPECT THE CONTROLS AND FENCES AT WEEKLY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO INSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES. SILT ACCUMULATION AT INLET DEVICES SHALL BE REMOVED WHEN THE DEPTH REACHES TWO (2) INCHES.
- PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BE DISPOSED OF IN APPROVED SPOIL DISPOSAL SITES.
- ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS; ONE SQUARE FOOT IN TOTAL AREA; BLOWS AIR FROM WITHIN THE SUBSTRATE AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER TO IMMEDIATELY CONTACT A CITY OF AUSTIN ENVIRONMENTAL INSPECTOR FOR FURTHER INVESTIGATION.
- 10. PERMANENT EROSION/SEDIMENTATION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED IN ACCORDANCE WITH CURRENT CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL AND STANDARD SPECIFICATIONS, UNLESS OTHERWISE INDICATED IN THE PLAN SET AND SPECIFICATIONS.
- 11. DEVELOPER INFORMATION: OWNER

COMPANY: CITY OF AUSTIN

CONTACT: DONELLE ROBINSON

ADDRESS: 505 BARTON SPRINGS ROAD, 11TH FLOOR, AUSTIN, TX 78704 FAX: 512-974-2845 PHONE: 512-974-1242

OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: COMPANY: HDR ENGINEERING, INC.

ADDRESS: 4401 WEST GATE BLVD, SUITE 400; AUSTIN, TX 78745 FAX: 512-912-5158 PHONE: 512-912-5100

PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL COMPANY: CONTRACTOR

PERSON OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION COMPANY: CONTRACTOR

- THE CONTRACTOR SHALL NOT DISPOSE OF SURPLUS EXCAVATED MATERIAL FROM THE SITE WITHOUT NOTIFYING THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT AT 974-2278 AT LEAST 48 HOURS PRIOR WITH THE LOCATION AND A COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL.
- INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY PRIOR TO STREET WORK, AND WILL BE REMOVED AS SOON AS THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT ENVIRONMENTAL INSPECTOR AGREES THAT THERE IS NO POTENTIAL FOR SEDIMENTATION.
- 14. THE ENVIRONMENTAL INSPECTOR HAS THE AUTHORITY TO ADD AND/OR MODIFY EROSION/SEDIMENTATION CONTROLS ON SITE TO KEEP PROJECT IN COMPLIANCE WITH THE CITY OF AUSTIN RULES, REGULATIONS, AND ORDINANCES.

#### CITY OF AUSTIN — ADDITIONAL EROSION CONTROL NOTES FOR BARTON SPRINGS CONTRIBUTING ZONE

- DESIGNATION OF AN ENVIRONMENTAL PROJECT MANAGER WHO IS ON SITE >90% OF THE TIME. WHO IS REQUIRED TO BE AT THE PRECONSTRUCTION AND MID-CONSTRUCTION MEETINGS. AND IS RESPONSIBLE FOR COMPLIANCE ON SITE OF THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS. THE ENVIRONMENTAL PROJECT MANAGER IS RESPONSIBLE FOR ENSURING COMPLIANCE OF THE CONTROLS DURING THE CONSTRUCTION PERIOD. SHOULD THE PROJECT MANAGER NEED TO BE ABSENT FROM THE SITE FOR AN EXTENDED PERIOD (IN EXCESS OF ONE WEEK), THE ENVIRONMENTAL INSPECTOR WITH THE WATERSHED PROTECTION AND DEVELOPMENT REVIEW DEPARTMENT SHOULD BE INFORMED OF THE NAME OF A DESIGNATED REPLACEMENT.
- THE MAXIMUM LENGTH OF TIME BETWEEN CLEARING AND FINAL REVEGETATION OF A PROJECT SHALL NOT EXCEED 18 MONTHS, UNLESS EXTENDED BY THE DIRECTOR OF THE WATERSHED PROTECTION AND DEVELOPMENT REVIEW DEPARTMENT (THIS DOES NOT AFFECT THE EXPIRATION OF THE SITE PLAN OR BUILDING PERMIT. THIS REQUIREMENT APPLIES TO SITES THAT HAVE SUSPENDED WORK AND ARE EXPERIENCING EROSION CONTROL PROBLEMS DUE TO DISTURBED SOIL CONDITIONS.) DISTURBED AREAS MUST BE MAINTAINED TO PREVENT EROSION AND SEDIMENT LOADING OF ANY WATERWAYS OR DRAINAGE FACILITIES.
- IT IS A VIOLATION OF THE CODE AND THIS DEVELOPMENT PERMIT TO ALLOW SEDIMENT FROM A CONSTRUCTION SITE TO ENTER A CLASSIFIED WATERWAY DUE TO A FAILURE TO MAINTAIN THE REQUIRED EROSION AND SEDIMENTATION CONTROLS OR TO FOLLOW THE APPROVED CONSTRUCTION SEQUENCE.

#### SPECIAL NOTES TO COMPLY WITH BARTON SPRINGS SALAMANDER RECOVERY PLAN AND BARTON SPRINGS POOL HABITAT CONSERVATION PLAN (EFFECTIVE 9/13/2013)

- COMPLIANCE WITH U.S. FISH AND WILDLIFE PERMIT REQUIRES SHOULD ANY MORTALITY OR PHYSICAL INJURY OCCUR TO AN INDIVIDUAL OF THE SPECIES DURING PERMITTED ACTIVITIES (ABOVE THE AMOUNT SPECIFIED IN THE HABITAT CONSERVATION PLAN) ALL OPERATIONS MUST IMMEDIATELY CEASE AND THE SALAMANDER BIOLOGIST ON STAFF WILL CALL THE ESFO WITHIN 24 HOURS.
- ANY CHANGE IN WATER LEVEL IN THE AMPHITHEATER AT ELIZA SPRING EXCEPT WITH PRIOR NOTICE TO AND APPROVED BY OWNER, WILL RESULT 13. ALL FINISHED PRUNING SHALL BE DONE ACCORDING TO RECOGNIZED, IN OPERATIONS CEASING UNTIL THE WATER LEVEL IS RESTORED. UNPLANNED EVENTS LEADING TO TEMPORARY LOSS OF HABITAT
- (HAZARDOUS MATERIAL SPILLS, TEMPORARY DEWATERING) WILL IMMEDIATELY CEASE OPERATIONS SO THAT SPECIFIC PROTOCOLS IN THE HABITAT CONSERVATION PLAN CAN BE FOLLOWED.
- CHEMICAL FERTILIZERS WILL NOT BE USED AS PER THE HABITAT CONSERVATION PLAN. ONLY SPRING WATER WILL BE USED FOR IRRIGATION AS PER THE HABITAT CONSERVATION PLAN.
- HEAVY METALS: SOURCE INCLUDES VEHICLE WEAR.
- FUELING AND EQUIPMENT MAINTENANCE WILL OCCUR AT LEAST 25 FEET AWAY FROM WATER TO AVOID THE CHANCE OF DETRIMENTAL IMPACTS ON THE SPRING HABITAT OR AQUATIC LIFE. ABSORBENT PADS WILL BE USED UNDERNEATH OR AROUND ALL EQUIPMENT, SUPPLIES, AND VEHICLES CONTAINING TOXIC COMPONENTS DURING ALL OPERATIONS, FUELING, AND MAINTENANCE ACTIVITIES. (BARTON SPRINGS POOL HABITAT CONSERVATION PLAN ITEM 6.1.6.2)
- UNDER CONDITIONS WHEN DECREASED DISSOLVED OXYGEN CONCENTRATIONS MAY BE HARMFUL TO SALAMANDERS, THE CITY MAY SUPPLEMENT DISSOLVED OXYGEN IN ELIZA SPRINGS USING AIR PUMPS, WATER RECIRCULATION, OR OTHER METHOD APPROVED BY THE US FISH AND WILDLIFE SERVICE. (BARTON SPRINGS POOL HABITAT CONSERVATION PLAN ITEM 6.2.4)

#### CITY OF AUSTIN — STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION

- ALL TREES AND NATURAL AREAS SHOWN ON PLAN TO BE PRESERVED SHALL BE PROTECTED DURING CONSTRUCTION WITH TEMPORARY FENCING.
- PROTECTIVE FENCES SHALL BE ERECTED ACCORDING TO CITY OF AUSTIN STANDARDS FOR TREE PROTECTION.
- PROTECTIVE FENCES SHALL BE INSTALLED PRIOR TO THE START OF ANY

- SITE PREPARATION WORK (CLEARING, GRUBBING OR GRADING), AND SHALL BE MAINTAINED THROUGHOUT ALL PHASES OF THE CONSTRUCTION
- 4. EROSION AND SEDIMENTATION CONTROL BARRIERS SHALL BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT RESULT IN SOIL BUILD-UP WITHIN TREE DRIP LINES.
- PROTECTIVE FENCES SHALL SURROUND THE TREES OR GROUP OF TREES, AND WILL BE LOCATED AT THE OUTERMOST LIMIT OF BRANCHES (DRIP LINE) , FOR NATURAL AREAS, PROTECTIVE FENCES SHALL FOLLOW THE LIMIT OF CONSTRUCTION LINE, IN ORDER TO PREVENT THE FOLLOWING:
  - A. SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC OR STORAGE OF EQUIPMENT OR MATERIALS;
  - B. ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATER THAN 6 INCHES CUT OR FILL), OR TRENCHING NOT REVIEWED AND AUTHORIZED BY THE CITY ARBORIST;
- C. WOUNDS TO EXPOSED ROOTS, TRUNK OR LIMBS BY MECHANICAL EQUIPMENT;
- D. OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CEMENT TRUCK CLEANING, AND FIRES.
- EXCEPTIONS TO INSTALLING FENCES AT TREE DRIP LINES MAY BE PERMITTED IN THE FOLLOWING CASES: A. WHERE THERE IS TO BE AN APPROVED GRADE CHANGE,
- IMPERMEABLE PAVING SURFACE, TREE WELL, OR OTHER SUCH SITE DEVELOPMENT, ERECT THE FENCE APPROXIMATELY 2 TO 4 FEET BEYOND THE AREA DISTURBED;
- B. WHERE PERMEABLE PAVING IS TO BE INSTALLED WITHIN A TREE'S DRIP LINE, ERECT THE FENCE AT THE OUTER LIMITS OF THE PERMEABLE PAVING AREA (PRIOR TO SITE GRADING SO THAT THIS AREA IS GRADED SEPARATELY PRIOR TO PAVING INSTALLATION TO MINIMIZED ROOT DAMAGE);
- C. WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE TO ALLOW 6 TO 10 FEET OF WORK SPACE BETWEEN THE FENCE AND THE BUILDING;
- D. WHERE THERE ARE SEVERE SPACE CONSTRAINTS DUE TO TRACT SIZE, OR OTHER SPECIAL REQUIREMENTS, CONTACT THE CITY ARBORIST AT 512-974-1876 TO DISCUSS ALTERNATIVES.
- E. SPECIAL NOTE: FOR THE PROTECTION OF NATURAL AREAS, NO EXCEPTIONS TO INSTALLING FENCES AT THE LIMIT OF CONSTRUCTION LINE WILL BE PERMITTED.
- WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE BEING CLOSER THAN 4 FEET TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF 8 FT (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING PROVIDED.
- TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.
- ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SOIL. BACKFILL ROOT AREAS WITH GOOD QUALITY TOP SOIL AS SOON AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN 2 DAYS, COVER THEM WITH ORGANIC MATERIAL IN A MANNER WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EVAPORATION.
- 10. ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION SHALL BE PLACED AS FAR FROM EXISTING TREE TRUNKS AS
- 11. NO LANDSCAPE TOPSOIL DRESSING GREATER THAN 4 INCHES SHALL BE PERMITTED WITHIN THE DRIP LINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE.
- 12. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND EQUIPMENT SHALL TAKE PLACE BEFORE DAMAGE OCCURS (RIPPING OF BRANCHES, ETC.).
- APPROVED STANDARDS OF THE INDUSTRY (REFERENCE THE NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES AVAILABLE ON REQUEST FROM THE CITY ARBORIST).
- 14. ALL GRADING WITHIN PROTECTED ROOT ZONE AREAS SHALL BE DONE BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE ROOT DAMAGE. PRIOR TO GRADING, RELOCATE PROTECTION FENCES TO 2 FEET BEHIND THE GRADE CHANGE AREA.
- 15. TREES IMPACTED BY CONSTRUCTION ACTIVITIES SHALL BE WATERED DEEPLY ONCE A WEEK DURING PERIODS OF HOT OR DRY WEATHER. TREE CROWNS WILL BE SPRAYED WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
- 16. NO LANDSCAPE TOPSOIL DRESSING GREATER THAN 4 INCHES SHALL BE PERMITTED WITHIN THE DRIPLINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE.
- 17. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND EQUIPMENT SHALL TAKE PLACE BEFORE CONSTRUCTION BEGINS.
- 18. ALL PRUNING MUST BE DONE ACCORDING TO RECOGNIZED, APPROVED INDUSTRY STANDARDS. REFERENCE THE NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES.
- 19. TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.
- 20. DEVIATIONS FROM THE ABOVE NOTES MAY BE CONSIDERED ORDINANCE VIOLATIONS IF THERE IS SUBSTANTIAL NON-COMPLIANCE OR IF A TREE SUSTAINS DAMAGE AS A RESULT.

SUPPLEMENTAL TREE PROTECTION NOTES

- ALL TREE PROTECTION MUST COMPLY WITH CITY OF AUSTIN REQUIREMENTS AS OUTLINED IN THE ENVIRONMENTAL CRITERIA MANUAL AND AS INDICATED BY STANDARD COA NOTES AND DETAILS INCLUDED WITHIN THIS DOCUMENT SET. CONTRACTOR SHALL INSTALL PROTECTION PRIOR TO PRE-CONSTRUCTION CONFERENCE, MAKE ADJUSTMENTS TO PROTECTION AS DIRECTED BY THE ENVIRONMENTAL INSPECTOR, AND MAINTAIN PROTECTION UNTIL PROJECT IS COMPLETE.
- TYPE AND LOCATION OF ALL TREE PROTECTION MUST BE APPROVED IN THE FIELD BY THE ENVIRONMENTAL INSPECTOR PRIOR TO CONSTRUCTION
- 3. WALK-THROUGH: CONTRACTOR SHALL CONDUCT WALK-THROUGH MEETING WITH THE ENVIRONMENTAL INSPECTOR PRIOR TO PERFORMING ANY PRUNING ACTIVITIES ON TREES IN PROJECT AREA. PURPOSE OF WALK-THROUGH WILL BE TWOFOLD. ONE PURPOSE WILL BE TO DETERMINE THE MINIMUM AMOUNT OF PRUNING NECESSARY TO ALLOW CONSTRUCTION WORK TO BE COMPLETED. SECOND PURPOSE WILL BE TO DETERMINE AREAS OF PROJECT IN WHICH EXHAUST DIVERTERS WILL BE REQUIRED ON CONSTRUCTION EQUIPMENT TO PREVENT SCORCHING OF EXISTING TREES.
- 4. ALL PRUNING MUST BE PERFORMED IN ACCORDANCE WITH ANSI A300 (PART 1) - 2001 AMERICAN NATIONAL STANDARD FOR TREE CARE OPERATIONS (PRUNING) OR LATEST APPROVED VERSION. THIS DOCUMENT MAY BE OBTAINED ONLINE FOR A FEE AT <u>WWW.ANSI.ORG</u>
- 5. PRUNING SHALL BE DONE WITH CLEAN, SHARP TOOLS, TO PREVENT BARK TEARS, THE WEIGHT OF THE BRANCH SHALL BE REMOVED BEFORE MAKING FINAL PRUNING CUT.
- 6. ALL PRUNING SHALL PRESERVE THE NATURAL CHARACTER OF THE TREE 7. ONLY COLLAR CUTS ARE ACCEPTABLE. NO FLUSH CUTS OR STUB CUTS
- WILL BE ALLOWED. 8. ALL BRANCHES BROKEN OR DAMAGED DURING CONSTRUCTION SHALL BE
- PRUNING CUTS OR DAMAGED AREAS ON AN OAK TREE SHALL BE PAINTED WITHIN FIVE MINUTES WITH A STANDARD TREE WOUND DRESSING. TREE WOUND DRESSING SHALL BE EITHER TREEKOTE AEROSOL OR TANGLEFOOD PRUNING SEALER OR APPROVED EQUAL. THIS

REQUIREMENT APPLIES TO WOUND CREATED BY CONSTRUCTION VEHICLES

- OR EQUIPMENT. 10. ANY TREE ROOTS THAT ARE EXPOSED, CUT, OR TORN DURING CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SURROUNDING SOIL. (REFER ALSO TO NUMBER 9 OF THE TREE AND
- NATURAL AREA PROTECTION NOTES INCLUDED IN THIS PLAN SET.) 11. ALL TRENCHING WITHIN THE CRITICAL ROOT ZONE OF A TREE TO BE

PRESERVED WILL BE SAW CUT.

#### REMEDIAL TREE CARE NOTES AERATION AND SUPPLEMENTAL NUTRIENT REQUIREMENTS FOR TREES WITHIN CONSTRUCTION AREAS

- 1. AS A COMPONENT OF AN EFFECTIVE REMEDIAL TREE CARE PROGRAM PER ENVIRONMENTAL CRITERIA MANUAL SECTION 3.5.4, PRESERVED TREES WITHIN THE LIMITS OF CONSTRUCTION MAY REQUIRE SOIL AERATION AND SUPPLEMENTAL NUTRIENTS. SOIL AND/OR FOLIAR ANALYSIS SHOULD BE USED TO DETERMINE THE NEED FOR SUPPLEMENTAL NUTRIENTS. THE CITY ARBORIST MAY REQUIRE THESE ANALYSES AS PART OF A COMPREHENSIVE TREE CARE PLAN. SOIL PH SHALL BE CONSIDERED WHEN DETERMINING THE FERTILIZATION COMPOSITION AS SOIL PH INFLUENCES THE TREE'S ABILITY TO UPTAKE NUTRIENTS FROM THE SOIL, IF ANALYSES INDICATE THE NEED FOR SUPPLEMENTAL NUTRIENTS, THEN HUMATE/NUTRIENT SOLUTIONS WITH MYCORRHIZAE COMPONENTS ARE HIGHLY RECOMMENDED. IN ADDITION. SOIL ANALYSIS MAY BE NEEDED TO DETERMINE IF ORGANIC MATERIAL OR BENEFICIAL MICROORGANISMS ARE NEEDED TO IMPROVE SOIL HEALTH. MATERIALS AND METHODS ARE TO BE APPROVED BY THE CITY ARBORIST (512-974-1876) PRIOR TO APPLICATION. THE OWNER OR GENERAL CONTRACTOR SHALL SELECT A FERTILIZATION CONTRACTOR AND ENSURE COORDINATION WITH THE CITY ARBORIST.
- PRE-CONSTRUCTION TREATMENT SHOULD BE APPLIED IN THE APPROPRIATE SEASON, IDEALLY THE SEASON PRECEDING THE PROPOSED CONSTRUCTION. MINIMALLY, AREAS TO BE TREATED INCLUDE THE ENTIRE CRITICAL ROOT ZONE OF TREES AS DEPICTED ON THE CITY APPROVED PLANS. TREATMENT SHOULD INCLUDE, BUT NOT LIMITED TO, FERTILIZATION, SOIL TREATMENT, MULCHING, AND PROPER PRUNING.
- POST-CONSTRUCTION TREATMENT SHOULD OCCUR DURING FINAL REVEGETATION OR AS DETERMINED BY A QUALIFIED ARBORIST AFTER CONSTRUCTION. CONSTRUCTION ACTIVITIES OFTEN RESULT IN A REDUCTION IN SOIL MACRO AND MICRO PORES AND AN INCREASE IN SOIL BULK DENSITY. TO AMELIORATE THE DEGRADED SOIL CONDITIONS, AERATION VIA WATER AND/OR AIR INJECTED INTO THE SOIL IS NEEDED OR BY OTHER METHODS AS APPROVED BY THE CITY ARBORIST. THE PROPOSED NUTRIENT MIX SPECIFICATIONS AND SOIL AND/OR FOLIAR ANALYSIS RESULTS NEED TO BE PROVIDED TO AND APPROVED BY THE CITY ARBORIST PRIOR TO APPLICATION (FAX # 512-974-3010). CONSTRUCTION WHICH WILL BE COMPLETED IN LESS THAN 90 DAYS MAY USE MATERIALS AT 1/2 RECOMMENDED RATES. ALTERNATIVE ORGANIC FERTILIZER MATERIALS ARE ACCEPTABLE WHEN APPROVED BY THE CITY
- THE CONTRACTOR SHALL PROVIDE DOCUMENTATION OF THE WORK PERFORMED TO THE CITY ARBORIST, PLANNING AND DEVELOPMENT REVIEW DEPARTMENT. P.O. BOX 1088, AUSTIN, TX 78767. THIS NOTE SHOULD BE REFERENCED AS ITEM #1 IN THE SEQUENCE OF CONSTRUCTION.

ARBORIST. WITHIN 7 DAYS AFTER FERTILIZATION IS PERFORMED,

Texas P.E. Firm Registration No. F-754

**DESIGNED BY** ROSS DRAWN BY AMARAL C 07/24/2015 90% DRAFT FOR REVIEW B 10/3/2014 90% DRAFT FOR REVIEW **CHECKED BY** PARKER A 1/24/2014 60% DRAFT FOR REVIEW CTOBER 2014 PROJECT NUMBER | 220162 ISSUE DATE DESCRIPTION

PROJECT MANAGER S. MUCHARD

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF REVIEW UNDER THE AUTHORITY OF <u>SCOTT M. MUCHA</u>RD EXAS P.E. NO.89409 <u> DATE: JULY 24, 201</u> T IS NOT TO BE USED FOR CONSTRUCTION OF ANY OTHER PURPOSE **90% DRAFT** 




**ELIZA SPRING OUTLET DAYLIGHTING** 

Austin, Texas

#### **EROSION/SEDIMENTATION** CONTROL AND TREE PROTECTION PLAN NOTES

SCALE | NONE




FILENAME | C1.2.DWG

C1.2

SHEET


2 5 5



- STEEL OR WOOD POSTS WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD
  THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 300 mm (12 INCHES). IF
  WOOD POSTS CANNOT ACHIEVE 300 mm (12 inches) DEPTH, USE STEEL POSTS.
- 2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.
- 3. THE TRENCH MUST BE A MINIMUM OF 150 mm (6 inches) DEEP AND 150 mm (6 inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.
- 4. SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE , WHICH IS IN TURN ATTACHED TO THE STEEL OR WOOD FENCE POST.
- 5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED.
- 6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT		SILT FENCE	
RECORD COPY SIGNED BY MORGAN BYARS 09/01/2011 ADOPTED		THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. 642S-1



1. STEEL OR WOOD POSTS WHICH SUPPORT THE MULCH SOCK SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 600mm (24 inches). IF WOOD POSTS CANNOT ACHIEVE 600mm (24 inches) DEPTH, USE STEEL POSTS. EARTH ANCHORS ARE ALSO ACCEPTABLE.

2. THE TOE OF THE MULCH SOCK SHALL BE PLACED SO THAT THE MULCH SOCK IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. IN ORDER TO PREVENT WATER FROM FLOWING BETWEEN THE JOINTS OF ADJACENT ENDS OFMULCH SOCKS, LAP THE ENDS OF ADJACENT MULCH SOCKS A MINIMUM OF 300mm (12 inches).

3. MULCH MATERIAL MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH; IT IS NOT ACCEPTABLE FOR THE MULCH MATERIAL TO CONTAIN GROUND CONSTRUCTION DEBRIS, BIOSOLIDS, OR

4. SOCK MATERIAL WILL BE 100% BIODEGRADABLE, PHOTODEGRADABLE, OR RECYCLABLE SUCH AS BURLAP, TWINE, UV PHOTOBIODEGRADABLE PLASTIC, POLYESTER, OR ANY OTHER ACCEPTABLE MATERIAL.


5. MULCH SOCKS SHOULD BE USED AT THE BASE OF SLOPES NO STEEPER THAN 2:1 AND SHOULD NOT EXCEED THE MAXIMUM SPACING CRITERIA PROVIDED IN CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL TABLE 1.4.5.F.1 FOR A GIVEN SLOPE CATEGORY.

6. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	MULCH SOCK

ADOPTED

RECORD COPY SIGNED BY 08/24/2010



NOTEC


- 1. STONE SIZE: 75-125 mm (3-5") OPEN GRADED ROCK.
  2. LENGTH: AS EFFECTIVE BUT NOT LESS THAN 15 m (50').
- 3. THICKNESS: NOT LESS THAN 200 mm (8").
- 4. WIDTH: NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS/EGRESS.
  5. WASHING: WHEN NECESSARY, VEHICLE WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE AND DRAINS INTO AN APPROVED TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY
- STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.


  6. MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AS WELL AS REPAIR AND CLEAN OUT OF ANY MEASURE DEVICES USED TO TRAP SEDIMENT.
- ROADWAY MUST BE REMOVED IMMEDIATELY.

  7. DRAINAGE: ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE SWALE TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.


ALL SEDIMENTS THAT IS SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC


CITY OF AUSTIN		STABILIZED CONSTRUCTION ENTRANCE	
WATERSHED PROTECTION DEPARTMENT		STABILIZED CONSTRUCTION ENTINANCE	
RECORD COPY SIGNED		THE ARCHITECT/ENGINEER ASSUMES	STANDARD NO.
BY J. PATRICK MURPHY	5/23/00	RESPONSIBILITY FOR APPROPRIATE USE	641S-1
	ADOPTED	OF THIS STANDARD.	

















Austin, Texas



C1.3



Registration No. F-754

SSUE	DATE	DESCRIPTION	PROJECT NUMBER	220162
Α	1/24/2014	60% DRAFT FOR REVIEW	DATE	JULY 2015
В	10/3/2014	90% DRAFT FOR REVIEW	CHECKED BY	C. PARKER
С	07/24/2015	90% DRAFT FOR REVIEW		
			DRAWN BY	J. FELAN
			DESIGNED BY	S. MUCHARD
			PROJECT WANAGER	3. MUCHARD


T IS NOT TO BE USED FOR CONSTRUCTION OF ANY OTHER PURPOSE 90% DRAFT




**Austin, Texas** 

FILENAME | C1.4.DWG **SCALE** 1"=5"

SHEET C1.4





\_\_\_\_\_

\_\_\_\_\_

Curve Point Data Description Station Northing Easting PC: 0+12.964 10069138.24 3105793.374 RP: 10069127.57 3105778.221

PT: 0+24.367 10069145.03 3105784.436 Circular Curve Data Parameter ValueParameter Value

Delta: "35° 14' 47.9497"" Type:LEFT Radius: 18.536 Length: 11.403 Tangent: 5.888

Mid-Ord: 0.87 External: 0.913 Chord: 11.224 Course: "N 52° 47' 03.5147"" W"

Tangent Data

Description PT StationNorthing Easting Start:0+24.367 10069145.03 3105784.436 End: 0+24.995 10069145.24 3105783.845

Tangent Data Parameter ValueParameter Value

Length: 0.628 Course: "N 70° 24' 27.4897"" W"

Curve Point Data

Description Station Northing Easting PC: 0+24.995 10069145.24 3105783.845 10069158.02 3105788.393 PT: 0+36.644 10069153.11 3105775.748 Circular Curve Data

Parameter ValueParameter Value Delta: "49° 12' 55.6039""" Type:RIGHT

Radius: 13.562 Length: 11.65 Tangent: 6.212

Mid-Ord: 1.232 External: 1.355

Chord: 11.295 Course: "N 45° 47' 59.6876"" W"

\_\_\_\_\_

Tangent Data

Description PT StationNorthing Easting Start:0+36.644 10069153.11 3105775.748 End: 0+46.454 10069162.26 3105772.201

Tangent Data

Parameter ValueParameter Value

Length: 9.81 Course: "N 21° 11' 31.8856"" W"

Curve Point Data Description Station Northing Easting PC: 0+46.454 10069162.26 3105772.201 RP: 10069155.03 3105753.554

PT: 0+62.768 10069173.56 3105761.07 Circular Curve Data Parameter ValueParameter Value

Delta: "46° 44' 06.9443"" Type:LEFT Radius: 20

Length: 16.314 Tangent: 8.641

Mid-Ord: 1.64 External: 1.787 Chord: 15.865 Course: "N 44° 33' 35.3578"" W"

Tangent Data Description PT StationNorthing Easting Start:0+62.768 10069173.56 3105761.07

End: 0+67.180 10069175.22 3105756.981

Tangent Data

Parameter ValueParameter Value

Length: 4.412 Course: "N 67° 55' 38.8300"" W"

Description:

Tangent Data Description PT StationNorthing Easting Start:0+-10.000 10069118.28 3105802.584 End: 0+03.283 10069129.05 3105794.818 Tangent Data Parameter ValueParameter Value Length: 13.283 Course: "N 35° 46' 32.6873"" W"

Curve Point Data Description Station Northing Easting PC: 0+03.283 10069129.05 3105794.818 RP: 10069119.7 3105781.837 PT: 0+12.376 10069134.57 3105787.743 Circular Curve Data Parameter ValueParameter Value Delta: "32° 33' 47.7371""" Type:LEFT Radius: 16

Length: 9.093 Tangent: 4.673 Mid-Ord: 0.642 External: 0.668 Chord: 8.971 Course: "N 52° 03' 26.5558"" W"

Description PT StationNorthing Easting Start:0+12.376 10069134.57 3105787.743 End: 0+25.148 10069139.28 3105775.873

Tangent Data Parameter ValueParameter Value

Length: 12.772 Course: "N 68° 20' 20.4243"" W"

Curve Point Data Description Station Northing Easting PC: 0+25.148 10069139.28 3105775.873 10069154.16 3105781.779 PT: 0+38.314 10069148.37 3105766.861 Circular Curve Data Parameter ValueParameter Value Delta: "47° 08' 48.5387""" Type:RIGHT

Radius: 16 Length: 13.166 Tangent: 6.981 Mid-Ord: 1.335 External: 1.457

Chord: 12.798 Course: "N 44° 45' 56.1550"" W" \_\_\_\_\_

Tangent Data Description PT StationNorthing Easting Start:0+38.314 10069148.37 3105766.861 End: 0+49.332 10069158.64 3105762.878 Tangent Data

Parameter ValueParameter Value Length: 11.018 Course: "N 21° 11' 31.8857"" W"

Curve Point Data Description Station Northing Easting PC: 0+49.332 10069158.64 3105762.878 RP: 10069155.03 3105753.554 PT: 0+57.489 10069164.3 3105757.312 Circular Curve Data Parameter ValueParameter Value Delta: "46° 44' 06.9443""" Type:LEFT Radius: 10

Length: 8.157 Tangent: 4.321 Mid-Ord: 0.82 External: 0.893

Parameter ValueParameter Value

Chord: 7.933 Course: "N 44° 33' 35.3578"" W"

Length: 22.509 Course: "N 67° 55' 38.8300"" W"

Texas P.E. Firm

Registration No. F-754

ISSUE DATE

Tangent Data Description PT StationNorthing Easting Start:0+57.489 10069164.3 3105757.312 End: 0+79.998 10069172.75 3105736.453 Tangent Data

Alignment: LEFT CHANNEL TOE

Tangent Data Description PT StationNorthing Easting Start:0+00.000 10069125.69 3105794.427 End: 0+03.929 10069128.87 3105792.13 Tangent Data Parameter ValueParameter Value

Length: 3.929 Course: "N 35° 46' 32.6876"" W" \_\_\_\_\_\_

Curve Point Data Description Station Northing Easting PC: 0+03.929 10069128.87 3105792.13 RP: 10069124.2 3105785.64 PT: 0+08.863 10069131.77 3105788.229 Circular Curve Data Parameter ValueParameter Value Delta: "35° 20' 21.4623"" Type:LEFT

Radius: 8 Length: 4.934 Tangent: 2.548 Mid-Ord: 0.377 External: 0.396 Chord: 4.856 Course: "N 53° 26' 43.4188"" W"

Description PT StationNorthing Easting Start:0+08.863 10069131.77 3105788.229 End: 0+23.485 10069136.5 3105774.394 Tangent Data

Parameter ValueParameter Value Length: 14.622 Course: "N 71° 06' 54.1499"" W"

Curve Point Data Description Station Northing Easting PC: 0+23.485 10069136.5 3105774.394 10069151.64 3105779.573 PT: 0+37.948 10069146.34 3105764.474 Circular Curve Data Parameter ValueParameter Value Delta: "51° 47' 24.6483""" Type:RIGHT

Radius: 16 Length: 14.463 Tangent: 7.767 Mid-Ord: 1.606 External: 1.786

Chord: 13.975 Course: "N 45° 13' 11.8258"" W"

\_\_\_\_\_\_ Tangent Data

Description PT StationNorthing Easting Start:0+37.948 10069146.34 3105764.474 End: 0+52.000 10069159.6 3105759.824 Tangent Data

Parameter ValueParameter Value Length: 14.052 Course: "N 19° 19' 29.5016"" W"

Curve Point Data

Description Station Northing Easting PC: 0+52.000 10069159.6 3105759.824 RP: 10069157.44 3105754.23 PT: 0+56.853 10069162.98 3105756.523 Circular Curve Data

Parameter ValueParameter Value Delta: "46° 20' 17.9496""" Type:LEFT Radius: 6 Length: 4.853 Tangent: 2.568

Mid-Ord: 0.484 External: 0.526 Chord: 4.721 Course: "N 44° 21' 40.8604"" W"

Tangent Data


Length: 3.572 Course: "N 67° 31' 49.8353"" W"

Description PT StationNorthing Easting Start:0+56.853 10069162.98 3105756.523 End: 0+60.425 10069164.35 3105753.222 Tangent Data

Parameter ValueParameter Value

**PROJECT MANAGER** S. MUCHARD **DESIGNED BY** STEWART **DRAWN BY** AMARAL C 07/24/2015 90% DRAFT FOR REVIEW B 10/3/2014 90% DRAFT FOR REVIEW CHECKED BY C. PARKER A 1/24/2014 60% DRAFT FOR REVIEW DATE OCTOBER 2014 DESCRIPTION PROJECT NUMBER | 220162

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF REVIEW UNDER THE AUTHORITY OF ERIC J. STEWART TEXAS P.E. NO. 95907 <u> DATE: JULY 24, 2015</u> IT IS NOT TO BE USED FOR CONSTRUCTION OF ANY OTHER PURPOSE **90% DRAFT** 







Austin, Texas



HORIZONTAL ALIGNMENT DATA

SHEET





**DESIGN CRITERIA NOTE:** 

imestone Block

S Block Interface

1. WALLS WERE DESIGNED IN ACCORDANCE WITH THE CITY OF AUSTIN, TRANSPORTATION CRITERIA MANUAL, CHAPTER 11.

24

#### PROJECT MANAGER S. MUCHARD **DESIGNED BY** BOEHM DRAWN BY AMARAL C 07/24/2015 90% DRAFT FOR REVIEW 10/3/2014 90% DRAFT FOR REVIEW CHECKED BY PARKER A 1/24/2014 60% DRAFT FOR REVIEW CTOBER 2014 DATE Registration No. F-754 ISSUE DATE DESCRIPTION PROJECT NUMBER | 220162


4000

NA

140

NA

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF REVIEW JNDER THE AUTHORITY OF ATE: JULY 24, 201 T IS NOT TO BE USED FOR CONSTRUCTION OF ANY OTHER PURPOSE **90% DRAFT** 



MAX 6"H X MIN 36" X MIN 24"L

DRY STACK LIMESTONE FLAGSTONE (TYP).

SEE NOTE 9. PAY ITEM SS130100-A.

**SUBSTRATE** 

PAY ITEM

SEE NOTE 7.

SS130100-D.

PROPOSED CHANNEL ALIGNMENT -& PROFILE CONTROL POINT

#### **ELIZA SPRING OUTLET DAYLIGHTING**

3' MIN

TYPICAL SECTION W/ TYPE | SLOPE SYSTEM (1 BLOCK . TYPE 1 SLOPE = 2')

**Austin, Texas** 

STA 0+00 TO 0+05



LANDSCAPE: SEE LANDSCAPE PLANS FOR FENCE LAYOUT.

FILENAME | C2.5.DWG **SCALE** | 1"=2'

(CLSM) INNER

FROM STA 0+54 TO

0+00 ONLY. PAY ITEM 402S-A.

SHEAR KEY.


C2.5

SHEET

#### NOTES:


- 1. ANCHOR TRM WITH 12-INCH, 8-GAUGE WIRE STAPLES, 2.5 STAPLES PER SQUARE YARD. FOR CLARITY, NOT ALL STAPLES ARE ILLUSTRATED.
- 2. ROLL SHALL BE INSTALLED PARALLEL TO CHANNEL. EDGES SHALL BE OVERLAPPED BY 4-INCHES. ROLL ENDS SHALL BE OVERLAPPED BY 6-INCHES. EDGES SHALL BE SECURED WITH STAPLES IN ACCORDANCE WITH MANUFACTURER'S GUIDELINES.
- 3. TRM SHALL BE SHINGLED IN THE DIRECTION OF THE DOWN SLOPE AND FLOW.
- 4. CONTRACTOR SHALL CONTACT OWNER/ENGINEER 3 DAYS PRIOR TO INSTALLATION OF TRM TO ALLOW FOR INSPECTION OF INSTALLATION BY CITY STAFF.
- SCARIFY STRUCTURAL BACKFILL BY HAND RAKING TO A DEPTH NO DEEPER THAN 1-INCH PRIOR TO PLACEMENT OF APPROVED TOPSOIL.

1 TOP SLOPE DETAIL




- 1. LIMESTONE BOULDER CLUSTERS SHALL EXTEND DOWN AND REST SOUNDLY ON FLAGSTONE LAYER AT BASE OF CHANNEL SUBSTRATE.
- 2. EACH CLUSTER BOULDER SHALL BE HAND SELECTED BY CONTRACTOR AND PRE-APPROVED BY OWNER PRIOR TO INSTALLATION. FINAL LOCATION OF EACH BOULDER SHALL BE COORDINATED WITH THE OWNER IN THE FIELD.
- 3. CLUSTER BOULDER DIMENSIONS SHALL VARY. LENGTH AND WIDTH SHALL BE 18 INCHES MIN, BUT HEIGHT SHALL BE 20 TO 24 INCHES TO EXTEND 8 TO 12 INCHES ABOVE PROPOSED FINISHED GRADE OF

LIMESTONE BOULDER CLUSTER



GRADE CONTROL PROFILE



#### **GRADE CONTROL NOTES:**

- 1. PLAN: BUILD GRADE CONTROL STRUCTURE (GCS) TO EXTEND ACROSS BASE OF CHANNEL WITH LARGEST DIAMETER BOULDERS AT THE CREST LINE AND REDUCE SIZES PROGRESSIVELY UPSTREAM AND DOWNSTREAM. MANUAL PLACEMENT AND SELECTION OF BOULDERS IS REQUIRED.
- 2. PROFILE: CONSTRUCT DOWNSTREAM FACE OF GRADE CONTROL AT APPROXIMATELY 20H:1V AND UPSTREAM FACE AT APPROXIMATELY 4H:1V SLOPE.
- 3. GCS BOULDERS SHALL BE HAND SELECTED TO COMPLY WITH GEOMETRIC REQUIREMENTS. BOULDERS IN CHANNEL ARE TO BE PRE-APPROVED BY OWNER AND ENGINEER PRIOR CONSTRUCTION. BOULDER PLACEMENT SHALL BE APPROVED BY OWNER AND ENGINEER.
- 4. EACH GCS CREST SHALL CONSIST OF TWO HAND SELECTED BOULDERS WHICH TOGETHER EXTEND THE FULL WIDTH OF CHANNEL. THE HEIGHT OF EACH GCS CREST BOULDER SHALL EXTEND 6 INCHES ABOVE PROPOSED FINISHED GRADE OF CHANNEL.
- 5. GCS CREST BOULDERS SHALL EXTEND AND REST SOUNDLY ON FLAGSTONE LAYER AT BASE OF CHANNEL SUBSTRATE.
- 6. ADDITIONAL BOULDERS (MIN 1' DIA. EACH AXIS) SHALL ABUT THE DOWNSTREAM AND UPSTREAM FACES OF THE GCS BOULDERS.

3 GRADE CONTROL STRUCTURE (GCS) DETAIL

Texas P.E. Firm Registration No. F-754

**PROJECT MANAGER** S. MUCHARD **DESIGNED BY STEWART** DRAWN BY AMARAL C 07/24/2015 90% DRAFT FOR REVIEW B 10/3/2014 90% DRAFT FOR REVIEW CHECKED BY C . PARKER A 1/24/2014 60% DRAFT FOR REVIEW OCTOBER 2014 ISSUE DATE DESCRIPTION PROJECT NUMBER | 220162

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF REVIEW UNDER THE AUTHORITY OF IT IS NOT TO BE USED FOR CONSTRUCTION OR ANY OTHER PURPOSE. 90% DRAFT




**ELIZA SPRING OUTLET DAYLIGHTING** 

**Austin, Texas** 

MISC. CHANNEL DETAILS

FILENAME C2.5.DWG SCALE AS NOTED SHEET

C2.6






ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	220162
<del></del>	1/24/2014	60% DRAFT FOR REVIEW	DATE	OCTOBER 2014
В	10/3/2014	90% DRAFT FOR REVIEW	CHECKED BY	C. PARKER
С	07/24/2015	90% DRAFT FOR REVIEW		
			DRAWN BY	C. AMARAL
			DESIGNED BY	E. STEWART
			PROJECT MANAGER	S. MUCHARD


ERIC J. STEWART TEXAS P.E. NO. 95907 DATE: JULY 24, 2015 IT IS NOT TO BE USED FOR CONSTRUCTION OR ANY OTHER PURPOSE. **90% DRAFT** 



## **OUTLET DAYLIGHTING**










IF THIS SHEET IS NOT 34" X 22", IT IS A REDUCED PRINT.

Jul 22, 2015 - 11:53am Drawing name: J:\1049-Eliza Springs Improvements\00-Drawings\Permit\C-1049--STORM PNP.dwg







Drawing name: J:\1049-Eliza Springs Improvements\00-Drawings\Permit\C-1049--DETAILS.dwg Jul 22, 2015 - 11:53am

**Austin, Texas** 

CONSTRUCTION PURPOSES.

IF THIS SHEET IS NOT 34" X 22", IT IS A REDUCED PRINT

DATE

PROJECT NUMBER 220162

TEXAS REGISTRATION NO. F-13013


Texas P.E. Firm

Registration No. F-754

ISSUE DATE

DESCRIPTION

C-1049--DETAILS.DWG FILENAME SCALE




NEW GUNITE RETAINING WALL NEW FLOW CONTROL GATE VALVE NEW CONCRETE ENDANGERED SPECIES HABITAT HEADWALL + S1.3 NEW CONCRETE HEADWALL PERPENDICULAR TO THE NEW GUNITE RETAINING WALL

PROPOSED AMPHITHEATER
KEYWAY FLOW CONTROL PLAN

SCALE: 1/2" = 1'-0"

#### GENERAL NOTES

- 1. THE ACCURACY OF ITEMS SHOWN AS EXISTING ON DRAWINGS WAS DETERMINED FROM RECORD DRAWINGS AND FIELD OBSERVATIONS.
- 2. DRAWINGS ARE NOT TO BE SCALED FOR DETERMINATION OF QUANTITIES, LENGTHS, OR FIT OF MATERIALS.
- 3. DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHODS OF CONSTRUCTION UNLESS SO STATED OR NOTED. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE, THE WORKMEN AND ALL OTHER PERSONS DURING CONSTRUCTION.
- 4. CONTRACTOR SHALL PROVIDE TEMPORARY BRACING AND SHORING OF ALL WORK AS REQUIRED FOR STABILITY OF THE STRUCTURE DURING ALL PHASES OF CONSTRUCTION. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY CONDITION WHICH, IN HIS/HER OPINION, MIGHT ENDANGER THE STABILITY OF THE STRUCTURE OR CAUSE DISTRESS IN THE STRUCTURE.
- 5. ALL EXISTING CONDITIONS AND DIMENSIONS SHALL BE FIELD VERIFIED PRIOR TO PREPARATION OF SHOP DRAWINGS AND THE BEGINNING OF THE CONSTRUCTION PROCESS.
- 6. ENTIRE AMPHITHEATER FLOOR IS ENGDANDERED SPECIES HABITAT AND CANNOT BE IMPACTED BY CONSTRUCTION.
- 7. EQUIPMENT AND PEOPLE CANNOT ENTER THE FLOOR, NOR CAN ANY MATERIALS OR SILT DROP INTO IT. PROVIDE NETTING OR OTHER BARRIERS (APPROVED BY OWNER) TO PREVENT CONSTRUCTION DEBRIS FROM ENTERING AMPHITHEATER FLOOR.
- 8. ELIZA SPRING AMPHITHEATER IS A HISTORICAL STRUCTURE. ONLY THE PARTS NOTED TO BE REMOVED CAN BE AFFECTED. DEMOLITION AND CONSTRUCTION MUST LEAVE THE REST OF THE HISTORICAL STRUCTURE UNDAMAGED.
- 9. DAMAGED STRUCTURES MUST BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
- 10. EQUIPMENT USED IN AMPHITHEATER SHALL BE HAND OR ELECTRIC POWERED.
- 11. REFER TO CIVIL FOR PIPE AND PIPINGSUPPORTS. PIPE MAY BE SUPPORTED FROM THE CONCRETE ROOF SPAB.



NOTE: REFER TO CIVIL SHEETS FOR LOCATION OF JUNCTION BOX.

PROPOSED CONCRETE

JUNCTION BOX PLAN


SCALE: 1/2" = 1'-0"


**5** 

Jose I. Guerra, Inc.
Consulting Engineers
2401 South IH-35 Suite 210
Austin, Texas 78741
(512) 445-2090
Structural • Civil • Mechanical • Electrical
TBPE FIRM F-3



ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	220162
В	10/03/14	90% DRAFT FOR REVIEW	DATE	07-20-15
С	07-20-15	90% DRAFT FOR REVIEW	CHECKED BY	JL
			DRAWN BY	FS
			DESIGNED BY	JL
			PROJECT MANAGER	JL







#### ELIZA SPRING OUTLET DAYLIGHTING


Austin, Texas






S1.2








Texas P.E. Firm Registration No. F-754

			PROJECT WANAGER	3 MOCHARD
			DESIGNED BY	CK
			DRAWN BY	CK
С	7/24/2015	90% RESUBMITTAL FOR REVIEW		
В	10/3/2014	90% DRAFT FOR REVIEW	CHECKED BY	СК
Α	1/24/2014	60% DRAFT FOR REVIEW	DATE	7/24/2015
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	220162



FILENAME ELIZA03 SCALE AS SHOWN L1.2



512.445.0431 512.857.1342 fax carolyn@ckla.net



			PROJECT MANAGER	S MUCHARD
			DESIGNED BY	СК
			DRAWN BY	СК
С	7/24/2015	90% RESUBMITTAL FOR REVIEW		
В	10/3/2014	90% DRAFT FOR REVIEW	CHECKED BY	СК
Α	1/24/2014	60% DRAFT FOR REVIEW	DATE	7/24/2015
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	220162


APPROVAL





### **OUTLET DAYLIGHTING**


L2.1


FILENAME ELIZA03 SCALE AS SHOWN


























#### IRRIGATION SCHEDULE

# MANUFACTURER/MODEL/DESCRIPTION Hunter MPIOOO PROS-06-PRS40-CV-R Turf Rotator, 6" (15.24 cm) pop-up with check valve, reclaimed body cap, pressure regulated to 40 psi (2.76 bar), MP Rotator nozzle on PRS40 body. M=Maroon adj arc 90 to 210, L=Light Blue 210 to 270 arc, 0=0live 360 arc. Hunter MP Corner PROS-06-PRS40-CV-R Turf Rotator, 6" (15.24 cm) pop-up with factory installed check valve, reclaimed body cap, pressure regulated to 40 psi (2.76 bar), MP Rotator nozzle on PRS40 body. T=Turquoise adj

<b>★ ★ ● ○</b> 25 50 10 20	Hunter PCB-R Flood Bubbler, 1/2" FIPT. Reclaimed Water Use.	With Purple	Cap for
----------------------------	---	-------------	---------

SYMBOL

MANUFACTURER/MODEL/DESCRIPTION

Hunter PGP-ADJ-B
Turf Rotor, 4.0" Pop-Up. Adjustable and Full
Circle. Standard Angle Blue Nozzle.

Use PGP-ADJ-B

Turf Rotor, 4.0" Pop-Up. Adjustable and Full Circle. Standard Angle Blue Nozzle.

3.00

Hunter PGP-ADJ-B

Circle. Standard Angle Blue Nozzle.

5.00

Hunter PGP-ADJ-B

Turf Rotor, 4.0" Pop-Up. Adjustable and Full

Circle Standard Angle Blue Nozzle.

SYMBOL MANUFACTURER/MODEL/DESCRIPTION

Hunter ICZ-101-40
Drip Control Zone Kit. I" ICV Globe Valve with I"
HY100 filter system. Pressure Regulation: 40psi.
Flow Range: 2 GPM to 20 GPM. 150 mesh
stainless steel screen.

Turf Rotor, 4.0" Pop-Up. Adjustable and Full

Area to Receive Dripline
Netafim O&WRAM-06-12 (18)
Bioline Pressure Compensating Landscape
Dripline w/Purple Color Tubing for Non-Potable
Water Applications. O.6GPH emitters at 12.0"
O.C. Dripline laterals spaced at 18.0" apart, with emitters offset for triangular pattern. Reclaimed Water Use Only.

SYMBOL

MANUFACTURER/MODEL/DESCRIPTION

Hunter ICV-G-FS-R
I", I-I/2", 2", and 3" Plastic Electric Remote
Control Valves, Globe Configuration, with NPT

Threaded Inlet/Outlet, for Commercial/Municipal Use. With Filter Sentry Factory Installed Option, and Reclaimed Water ID, Purple Handle.

Hunter XCH-0600-SS

Electromechanical controller, 6 stations, outdoor

model, battery-powered. Stainless Steel Cabinet. For residential/commercial use.

RS

Hunter MINI-CLIK

Rain Sensor, mount as noted

Existing Pump

Irrigation Lateral Line: PVC Class 200 SDR 21

PVC Class 200 irrigation pipe. Only lateral


transition pipe sizes 3/4" and above are

— New Irrigation Mainline: PVC Class 200 SDR 21 irrigation pipe.

indicated on the plan, with all others being 1/2" in

Existing Irrigation Mainline: PVC Class 200 SDR 21 irrigation pipe.

Valve Callout



#### Design Notes

- (1) Sprinkler heads and driplines must be placed at least 6 inches inches from impervious surfaces such as streets, sidewalks and driveways.
- (2) Use of sprinklers is prohibited on landscaped strips less than six feet wide. Surface or subsurface drip irrigation may be used in lieu of sprinklers.
- (3) All Dripline zones must have an Air Relief Valve and a Flush Valve.
- (4) All local municipal and state laws rules and regulations governing or relating to any portion of this work are hereby incorporated into and made a part of these specifications and their provisions shall be carried out by the Contractor. In case of conflict between specifications, drawings, and/or code, the more stringent requirement shall prevail.
- (5) The mainline and sleeving is diagrammatic. All piping is for design clarification only and shall be installed within limit of work boundaries. Avoid any conflicts between the irrigation system, planting and architectural features.
- (6) Irrigation equipment as shown is diagrammatic.
- (7) Do not willfully install any equipment as shown on the plans when it is obvious in the field that unknown conditions exist that were not evident at the time these plans were prepared.
- 8) All heads are to be adjusted to prevent overspray onto buildings, walls, fences and hardscape.
- (9) The irrigation system design is based on the minimum operating pressure and the maximum flow demand shown on the irrigation drawings at each point of connection. The irrigation Contractor shall verify water pressure by direct field measurement prior to construction.
- (10) Wiring splices must be waterproof.
- (11) Wiring must be minimum of #14 gauge, UL rated for direct burial and must be buried a minimum of 6 inches.
- (12) Must use colored primer.
- (13) Rain or moisture sensor/shut-off devices required.
- (14) Lateral pipe to be installed at a minimum of 8 inches, and mainline pipe at a minimum of 18 inches.
- (15) Trenches and holes must be returned to original grade using select fill.
- (16) No drinking or domestic use allowed from irrigation system.
- (17) If Quick Coupling valves are installed, there must be a PVC gate valve between the QCV and source of water. Lids must be purple for QCV.
- (18) Machine trenching is not permitted within the root zone of existing trees. Hand dig is required within the root zone of existing trees. Do not cut roots over 1 inch in diameter.

#### **VALVE SCHEDULE**

NUMBER	MODEL	SIZE	TYPE	<u>PSI</u>	<u>PSI @ POC</u>	<u>GPM</u>	HEAD ELEV	VALVE ELEV	PRECIP
	Hunter  CZ- 0 -40	"	Area for Dripline	47.27	47.3 <i>0</i>	5.33	3.00 ft	0.00 ft	0.67 in/h
2	Hunter ICV-G-FS-R	"	Turf Rotary '	46.89	46.90	3.50	8.00 ft	0.00 ft	0.28 in/h
3	Hunter  CZ- 0 -40	["	Area for Ďripline	46.97	45.25	3.19	8.00 ft	-4.00 ft	0.67 in/h
4	Hunter ICV-G-FS-R	"	Bubbler '	41.34	39.86	18.00	11.00 ft	-4.00 ft	15.32 in/h
5	Hunter ICV-G-FS-R	[ "	Turf Rotor	46.67	45.19	16.20	10.00 ft	-4.00 ft	1.30 in/h

#### **SUGGESTED SUMMER WATERING SCHEDULE**

NUMBER   2   3   4   5	Hunter ICV-G-FS-R Hunter ICZ-101-40 Hunter ICV-G-FS-R	Area for Ďripline Bubbler	0.28 in/h 0.67 in/h 15.32 in/h	1 0.80 7	MIN./WEEK 72 216 72 28 47	GAL./WEEK 383.6 756.3 229.7 504 761.4	GAL./DAY
5	Hunter ICV-G-FS-R	Turf Rotor TOTALS:	1.30 in/h		47 435	761.4 2,635	

NOT FOR CONSTRUCTION,
PERMITTING, OR
REGULATORY APPROVAL



ELIZA SPRING OUTLET DAYLIGHTING

0 1" 2" FILENAME ELIZA03
SCALE AS SHOWN